

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(9,10,11) RS	SCHUYLER	23	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVING SCHEDULE														
STATION	STATION	LENGTH	MILLED WIDTH	SURFACE PAVED WIDTH	HMA SURF REM BUTT JOINT	HMA SURF REM VAR. DEPTH	EXCAVATE & GRADING EXISTING SHLDR (1 FT)	HMA SHOULDERS, 6"	AGGREGATE SHOULDERS	LEVELING BINDER	HMA SURFACE CSE	AGG PRIME COAT	HMA PRIME COAT	TEMPORARY RAMPS
		FT	FT	FT	SOYD	SOYD	UNITS	SOYD	TON	TON	TON	TON	TON	SOYD
469+00	469+30	30	22	24	73		1	7	3	2	7	0.16	0.03	15
469+30	488+10	1880	22	24		4596	38	418	214	193	439	9.19	1.75	
488+10	506+00	1790	22	24.5		4376	18	199	102	184	418	8.75	1.66	
506+00	577+00	7100	22	24		17356	142	1578	809	729	1756	34.71	6.60	
577+00	581+60	460	24	28		1227			52	52	120	2.45	0.47	
581+60	584+50	290	23	27		741			33	31	73	1.48	0.28	
584+50	588+44 (BK)	394	24	28		1051			45	44	103	2.10	0.40	
150+38 (AH)	387+00	23662	24	28	80	63099			2695	2650	6184	126.20	23.98	16
TOTALS		35,606			153	92,444	198	2,201	3,953	3,884	9,099	185	35	31

\* LT GUTTER FILLED IN 1.5 FT WIDE (SEE TYPICAL DETAIL)

GUARDRAIL SCHEDULE								
LT/RT	STATION	STATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TY A	TRAF BAR TERM, TY 1 SPECIAL (TANGENT)	TERMINAL MARKER DIRECT APPLY	FURNISHED EXCAVATION	GUARDRAIL MARKERS
			FT	FT	EA	EA	CUYD	EA
LT	380+50	385+00	450	350	2	2	10	6
RT	381+00	383+50	250	150	2	2	10	3
TOTALS			700	500	4	4	20	9

PATCHING SCHEDULE		
	PAVT PATCHING TY 2, 12"	PAVT PATCHING TY 3, 12"
	SOYD	SOYD
TOTALS	320	140

PAVEMENT MARKING SCHEDULE							
STATION	STATION	LENGTH	SHORT-TERM PAVT MKG	WORK ZONE PAVT MKG REM	RAISED REFL PAVT MKR	RAISED REFL PAVT MKR REM	
		FT	FT	SOFT	EACH	EACH	
469+00	588+44 (BK)	11944	3583.2	398	149	149	
150+38 (AH)	387+00 (BK)	23662	7098.6	789	296	296	
TOTALS			10,682	1,187	445	445	

PAVEMENT MARKING FOR NO PASSING ZONES							
STATION	STATION	LENGTH	PAINT PAVT MKG LINE - 5" SKIP YELLOW	PAINT PAVT MKG LINE - 5" SOLID SINGLE YELLOW	PAINT PAVT MKG LINE - 5" SOLID DOUBLE YELLOW	PAINT PAVT MKG LINE - 5" SOLID WHITE	TEMP PAVT MKG LINE - 5"
		FT	FT	FT	FT	FT	FT
<b>EDGE LINE</b>							
469+00	588+44 (BK)	11944				23888	23888
150+38 (AH)	387+00	23662				47324	47324
<b>SKIP DASH</b>							
438+51	496+94	5843	1461				1461
509+87	588+44 (BK)	7857	1964				1964
150+38 (AH)	387+00	23662	5916				5916
<b>NO PASSING ZONES</b>							
486+41	496+94	1053		1053			1053
496+94	509+87	1293			2586		2586
509+87	520+19	1032		1032			1032
526+30	535+54	924		924			924
537+92	543+42	550		550			550
TOTALS			9,341	3,559	2,586	71,212	86,698
			<b>PAINT TOTAL</b>		<b>86,698</b>		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<b>SCHEDULES</b>  SCALE: VERT. _____ HORIZ. _____ DATE _____	
		CHECKED BY _____	

PLOT DATE = 3/22/2007  
 FILE NAME = M:\projects\8855803\pavement\82-82-2884\schedule.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = laughton