

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(9,10,11) RS-3	SCHUYLER	23	7
STA. 438+51		TO STA. 388+80		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT 72838				

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS															
LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT. CONC. THICKNESS	BIT. SURF. REM. - BUTT JOINT	DRIVE WAY PAVEMENT REMOVAL	PREP OF BASE	PCC DRIVE WAY PAVEMENT 8"	AGGREGATE SURFACE COURSE TY - B	BIT (P. C.)	AGG (P. C.)	INCIDENTAL BIT. SURF.
(LT / RT) (STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / BIT. / P. C. C.)	FOOT	FOOT	FOOT	FOOT	INCH	SO. YD.	SO. YD.	SO. YD.	TON	TON	TON	TON	TON
LT 477+37	FE	GRASS	40			3									
RT 477+37	FE	GRASS	40			3									
RT 492+10	FE	GRASS	25			3									
LT 496+71	FE	GRASS	20			3									
RT 499+44	FE	GRASS	25			3									
RT 506+61	FE	GRASS	25			3									
LT 507+61	FE	GRASS	25			3									
LT 516+53	FE	GRASS	25			3									
RT 516+53	FE	DIRT	20			3									
LT 529+48	PE	AGG	48			7	3.5			37.3		1.4		0.07	7.3
RT 529+48	PE	AGG	23			7	3.5			17.9		0.5		0.04	3.5
RT 537+79	FE	GRASS	25			3									
RT 544+84	FE	GRASS	30			3									
RT 547+29	FE	GRASS	25			3									
RT 550+91	FE	GRASS	25			3									
LT 551+46	FE	GRASS	20			3									
RT 560+82	FE	GRASS	25			3									
LT 570+46	FE	GRASS	25			3									
RT 571+00	FE	GRASS	25			3									
RT 571+86.5	FE	GRASS	25			3									
RT 573+44	PE	AGG	53			7	3.5			41.2		1.5		0.08	8.1
RT 587+00	PE	AGG	28			7	3.5			21.8		0.7		0.04	4.3
LT 587+17	MB	BIT.	42			7	3.5	32.7					0.05		6.4
LT 151+25	CE	AGG.	60.2			9	8			60.2		1.8		0.1	27.0
LT 156+70	FE	AGG.	33			3									
RT 168+52	FE	GRASS	25			3									
LT 181+73.5	PE/MB	AGG.	71	26		7	3.5			55.2				0.1	10.8
RT 184+34	FE	AGG.	35			3									
LT 189+00	FE	GRASS	42			3									
LT 205+00	FE	GRASS	32			3									
RT 205+25	PE	AGG.	39			7	3.5	30.3						0.04	5.9
LT 205+76	MB	BIT.	42			7	3.5	32.7		32.7				0.06	6.4
RT 214+85	FE	GRASS	43			3									
RT 221+44	PE	AGG.	33			7	3.5			25.7		0.9			
LT 231+27	CE	P. C. C.	126			9	1.5		126		126		0.18		10.6
LT 234+16	MB	BIT.	42			7	3.5	32.7		32.7				0.06	6.4
LT 235+63	PE	AGG.	33			7	3.5			25.7		0.9		0.05	5.0
RT 237+78	FE	GRASS	39			3									
LT 242+61	FE	AGG.	41			3									
RT 242+75	FE	GRASS	42			3									
RT 251+38	PE	BIT.	40			7	3.5	31.1						0.04	6.1
LT 251+50	FE	BIT.	18			7	1.5	14						0.02	1.2
LT 251+95	MB	BIT.	38			7	3.5	29.6						0.04	5.8
LT 259+85	FE	GRASS	40			3									
RT 261+60	PE	BIT.	38			7	1.5	29.6						0.04	2.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT SIX
SCHEDULES FOR RURAL / URBAN
ENTRANCE & MAILBOX TURNOUT
W / O CONCRETE GUTTER
(PPP - PROJECTS)

SCALE: NOT TO SCALE
DATE: OCT, 2003

DRAWN BY AGG
CHECKED BY MJS

DGN-SPEC
DATE-TIME
*REF:01