

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	87 RS-3	SCHUYLER	26	6
STA. 69+70		TO STA.370+00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH	LINE 5" SKIP-DASH YELLOW	LINE 5" SKIP-DASH WHITE	LINE 5" SOLID WHITE	LINE 5" SOLID YELLOW
(LT / RT) (STA) (+)	FOOT	FOOT	FOOT	FOOT	FOOT
SOLID WHITE - EDGE LINES					
107+69.0 TO 112+91.90 (BK)	522.90			1045.80	
12+93.18 (AH) TO 96+28.0	8334.82			16669.64	
96+28.0 TO 97+48.0 (BRIDGE)	120.00			240.00	
97+48.0 TO 147+62.37 (BK)	5014.37			10028.74	
147+72.99 (AH) TO 303+41.66 (BK)	15568.67			31137.34	
303+46.54 (AH) TO 325+08.0	2161.46			4322.92	
325+08.0 TO 326+82.0 (BRIDGE)	174.00			348.00	
326+82.0 TO 370+30.0	4348.00			8696.00	
WHITE SKIP DASH					
RT 108+61.0 TO RT 147+62.37 (BK)	3901.37		975.34		
RT 147+72.99 (AH) TO RT 159+10.7	1137.71		284.43		
YELLOW SKIP DASH					
107+69.0 TO 112+91.90 (BK)	522.90	130.73			
12+93.18 (AH) TO 96+28.0	8334.82	2083.71			
96+28.0 TO 97+48.0 (BRIDGE)	120.00	30.00			
97+48.0 TO 147+62.37 (BK)	5014.37	1253.59			
147+72.99 (AH) TO 154+09.0	636.01	159.00			
155+53.0 TO 301+93.0	14640.00	3660.00			
305+96.0 TO 325+08.0	1912.00	478.00			
325+08.0 TO 326+82.0 (BRIDGE)	174.00	43.50			
326+82.0 TO 370+30.0	4348.00	1087.00			
SOLID YELLOW - NO PASSING ZONES					
RT 105+27.0 TO RT 147+62.37 (BK)	4235.37				4235.37
RT 147+72.99 (AH) TO RT 155+53.0	780.01				780.01
LT 154+09.0 TO LT 169+93.0	1584.00				1584.00
RT 189+65.0 TO RT 202+95.0	1330.00				1330.00
LT 206+89.0 TO LT 217+45.0	1056.00				1056.00
RT 231+89.0 TO RT 242+55.0	1066.00				1066.00
LT 245+85.0 TO LT 259+74.0	1389.00				1389.00
RT 287+33.0 TO RT 305+96.0	1863.00				1863.00
LT 301+93.0 TO LT 320+46.0	1853.00				1853.00
RT 334+90.0 TO RT 345+56.0	1066.00				1066.00
LT 346+86.0 TO LT 364+01.0	1715.00				1715.00
TOTAL =		8925.53	1259.77	72488.44	17937.38
GRAND TOTAL =			100611		

GUARDRAIL SCHEDULE

LOCATION	SPBGR REMOVAL	TBT T-1 SPL TANGENT	TERMINAL MARKERS DIRECT APPLIED	GUARDRAIL MARKERS T-B	FURNISHED EXCAVATION (SPECIAL)
(LT / RT) (STA) (+)	FOOT	EACH	EACH	EACH	CU YD
LT 95+86.0	38	1	1	1	10
RT 95+86.0	38	1	1	1	10
LT 97+97.0	38	1	1	1	100*
RT 98+32.0	38	1	1	1	10
RT 318+47.0	38	1	1	7	10
LT 318+97.0	38	1	1	7	10
RT 329+69.0	38	1	1	3	10
LT 330+42.0	38	1	1	5	10
TOTAL =	304	8	8	26 **	170

NOTE: * ADDITIONAL ESTIMATED QUANTITY TO RELOCATE FE.
 ** QUANTITY ESTIMATED FOR MARKERS TO BE PLACED ON EXISTING GUARDRAIL LEFT IN PLACE, NONE TO BE PLACED ON NEW TBT T-1 SPL (TANG).

PLOT DATE = \$DATE\$
 FILE NAME = \$FILEL\$
 PLOT SCALE = \$SCALE\$
 USER NAME = \$USER\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DISTRICT SIX
SCHEDULES FOR RURAL / URBAN
ENTRANCE & MAILBOX TURNOUT
W / O CONCRETE GUTTER
(PPP - PROJECTS)
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____