CONTRACT NO. 72847

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

① FAP 666 & FAP 67
② (SP-Z)RS-4 & (107Z)RS-8

PAVEMENT MARKING

LOCATION	PREFORMED PLASTIC PAVEMENT MARKING TYPE B					POLYUREA PAVEMENT MARKING TYPE I					RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	WORK ZONE PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING	THERMOPLASTIC PAVEMENT MARKING		
	LINE 5" SKIP DASH WHITE	LINE 6" SOLID WHITE	LINE 6" SOLID BLUE	LINE 24" SOLID WHITE	LETTERS AND SYMBOLS WHITE	LINE 5" SKIP DASH WHITE	LINE 5" SOLID YELLOW	LINE 5" SKIP DASH YELLOW	LINE 6" SOLID WHITE	LINE 12" SOLID YELLOW					LINE 5" SKIP DASH WHITE	LINE 5" YELLOW	LINE 12" YELLOW
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	SQ FT	FOOT	FOOT	FOOT	FOOT
NINTH STREET																	
STA 54+47.90 TO STA 45+94.43	421	236			88.0						66	66	137	412	241	1965	
NORTH GRAND AVENUE		502		97													
STA 45+01.00 TO STA 36+82.00	405	540			61.6						62	62	155	464	61	1942	
STA 36+28.40 TO STA 32+09.80	209	419			17.6						26	26	83	250		823	
STA 31+49.80 TO STA 27+42.12	204	408									22	22	82	245		815	
STA 27+00.06 TO STA 21+48.96	277	549									30	30	110	331		1105	
ENOS STREET		286		53													
STA 20+55.38 TO STA 16+81.91	188	375									20	20	75	225		750	
STA 16+31.71 TO STA 12+88.30	167	343			17.6						28	28	83	248		1127	38
CARPENTER STREET		388		61													
STA 12+01.15 TO STA 9+06.50	138	201			26.4						24	24	50	151		552	
STA 8+13.75 TO STA 0+87.50	347	278			52.8						56	56	121	363		1507	55
STA 0+87.50 TO STA 0+60.29						14	42		27				5	15			
MADISON STREET				112					480								
STA 10+80.81 TO STA 11+71.80						46	144	90		47			11	33			
STA 11+71.80 TO STA 14+06.79	117				17.6						24	24	31	94	118	470	49
JEFFERSON STREET		454		57	84.8												
STA 14+89.75 TO STA 18+07.25	158	228			35.2						24	24	57	172		634	
WASHINGTON STREET		436		113													
STA 19+00.00 TO STA 22+22.84	161	125			17.6						26	26	65	194		1042	85
ADAMS STREET		461		69													
STA 23+09.35 TO STA 26+35.32	163	263			35.2						26	26	61	183		655	
MONROE STREET		448		83													
STA 27+22.58 TO STA 30+47.34	163	158			17.6						26	26	61	184		867	63
CAPITOL STREET		431		109													
STA 0+31.00 TO STA 12+38.19	567	394			88.0						84	84	177	532	229	2265	
COOK STREET		681		130													
STA 13+37.82 TO STA 16+26.07	147	340			44.0						28	28	61	182		555	
LAWRENCE STREET		386		57													
STA 17+16.84 TO STA 40+15.58	1102	751			211.2						178	178	364	1092	601	4423	100
SOUTH GRAND AVENUE		183		43													
SUBTOTAL	4934	10264		984	815.2	60	186	90	507	47	750	750	1789	5370	1250	21497	390
ROUNDED					815												
JEFFERSON STREET																	
STA 0+50.50 TO STA 0+64.99													3	8	7		
1ST STREET		377		72									1	4		14	
STA 1+47.63 TO STA 4+93.38		164	100		76.4						10	10	23	69	172		
2ND STREET		371		48													
STA 5+76.68 TO STA 9+38.94		458			71.8						10	10	24	72	181		
STA 9+47.29 TO STA 12+27.80				144	203.1						8	8	19	56	121		
4TH STREET		378		48													
STA 12+95.35 TO STA 16+14.13		193	100		55.4						10	10	21	64	159		
5TH STREET		400		48													
STA 16+97.73 TO STA 20+15.65		463			117.2						19	19	21	64	158		
6TH STREET		415		48													
STA 20+99.04 TO STA 24+17.76					55.4						10	10	21	64	159		
7TH STREET		419		96													
STA 25+01.17 TO STA 32+18.89		599	100	161	132.8						20	20	48	143	346		
9TH S TREET		460		48													
STA 33+04.68 TO STA 40+08.59		931		111	183.6						20	20	23	69	166		
11TH STREET		258															
SUBTOTAL		5886	300	824	895.7						107	107	204	613	1469	14	
ROUNDED					896												
PROJECT TOTAL	4934	16150	300	1808	1710.9	60	186	90	507	47	857	857	1993	5983	2719	21511	390
ROUNDED					1711												

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)
FAP 67 (IL 97/IL 29-JEFFERSON STREET)

SCALE: VERT. HORIZ.
DRAWN BY
DATE
CHECKED BY

PLOT DATE = 2/19/2007
FILE NAME = o:\projects\d0956303\kds_final\schedulesofquantities.dgn
PLOT SCALE = 42.3525 ' / IN.
USER NAME = loughlin

SUB