

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	15	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				

- * - FAI 55, FAI 72, FAI 155, FAI 172, FAP 302 (IL 336), FAP 310 (US 67), FAP 75 (IL 29), FAP 745 (IL 104)
- ** - D-6 SHOULDER RUMBLE STRIPS 2007
- *** - ADAMS, HANCOCK, LOGAN, MACOUPIN, MONTGOMERY, MORGAN, PIKE, SANGAMON & SCOTT

SHOULDER RUMBLE STRIP

LOCATION	NBDL LENGTH (FT)	NBPL LENGTH (FT)	SBDL LENGTH (FT)	SBPL LENGTH (FT)
I-55 MACOUPIN COUNTY				
Mile Markers 38.91 to 50.17 = 11.26mi. • 5,280ft. = 59,453ft.	59,453	59,453	59,453	59,453
Omissions				
Exit 41 NB Exit Ramp	-614			
Exit 41 NB Entrance Ramp	-1,129			
Exit 41 SB Exit Ramp			-659	
Exit 41 SB Entrance Ramp			-1,150	
Mi. Marker 43.03 NB SN 059-0041	-230	-230		
Mi. Marker 43.04 SB SN 059-0040			-230	-230
Exit 44 NB Exit Ramp	-607			
Exit 44 NB Entrance Ramp	-1,139			
Exit 44 SB Exit Ramp			-619	
Exit 44 SB Entrance Ramp			-1,150	
Total:	55,734	59,223	55,645	59,223
I-55 MACOUPIN COUNTY SUBTOTAL: 229,825				

LOCATION	NBDL LENGTH (FT)	NBPL LENGTH (FT)	SBDL LENGTH (FT)	SBPL LENGTH (FT)
I-55 MONTGOMERY COUNTY				
Mile Markers 50.17 to 53.16 = 2.99mi. • 5,280ft. = 15,787ft.	15,787	15,787	15,787	15,787
Omissions				
Exit 52 NB Exit Ramp	-633			
Exit 52 NB Entrance Loop	-1,166			
Exit 52 NB Entrance Ramp	-1,138			
Exit 52 SB Exit Ramp			-545	
Exit 52 SB Entrance Loop			-1,145	
Exit 52 SB Entrance Ramp			-1,120	
Total:	12,850	15,787	12,977	15,787
I-55 MONTGOMERY COUNTY SUBTOTAL: 57,401				

LOCATION	NBDL LENGTH (FT)	NBPL LENGTH (FT)	SBDL LENGTH (FT)	SBPL LENGTH (FT)
I-55 SANGAMON COUNTY				
Mile Markers 97.94 to 110.98 = 13.04mi. • 5,280ft. = 68,851ft.	68,851	68,851	68,851	68,851
Omissions				
Mi. Marker 99.28 to 99.96 NB&SB PL Shldr - Future 3rd Lane		-3,611		-3,611
Exit 100 NB Exit Ramp	-740			
Exit 100 NB Loops and SN 084-0015	-770			
Exit 100 NB Entrance Ramp and SN 084-0017	-1,327			
Exit 100 SB Exit Ramp and SN 084-0016			-700	
Exit 100 SB Loops and SN 084-0014			-770	
Exit 100 SB Entrance Ramp			-1,300	
Mi. Marker 101.52 Railsplitter Rest Area NB Exit Ramp	-690			
Mi. Marker 102.04 Railsplitter Rest Area NB Ent. Ramp & SN 084-0018	-2,546			
Mi. Marker 102.14 NB SN 084-0018		-1,200		
Mi. Marker 102.15 SB SN 084-0019			-1,200	-1,200
Mi. Marker 103.55 Railsplitter Rest Area SB Exit Ramp			-684	
Mi. Marker 103.04 Railsplitter Rest Area SB Entrance Ramp			-1,185	
Mi. Marker 104.03 Existing DL Shldr patch up to standard			-750	
Exit 105 NB Exit Ramp & SN 084-0020	-1,170			
Mi. Marker 104.38 NB SN 084-0020		-380		
Exit 105 SB Exit Ramp			-884	
Exit 105 SB Entrance Ramp & SN 084-0021			-985	
Mi. Marker 104.41 SB SN 084-0021				-380
Mi. Marker 105.47 NB SN 084-0022	-201	-201		
Mi. Marker 105.48 SN SB 084-0023			-201	-201

SHOULDER RUMBLE STRIP (CONT.)

LOCATION	NBDL LENGTH (FT)	NBPL LENGTH (FT)	SBDL LENGTH (FT)	SBPL LENGTH (FT)
I-55 SANGAMON COUNTY (CONT.)				
Mi. Marker 106.33 Weigh Station Entrance Ramp			-1,000	
Mi. Marker 107.12 Weigh Station Exit Ramp			-504	
Exit 109 NB Exit Ramp	-702			
Exit 109 NB Entrance Ramp	-1,100			
Exit 109 SB Exit Ramp			-750	
Exit 109 SB Entrance Ramp			-1,315	
Total:	59,605	63,459	56,623	63,459
I-55 SANGAMON COUNTY SUBTOTAL: 243,146				

LOCATION	NBDL LENGTH (FT)	NBPL LENGTH (FT)	SBDL LENGTH (FT)	SBPL LENGTH (FT)
I-55 LOGAN COUNTY				
Mile Markers 126.50 to 141.47 = 14.97mi. • 5,280ft. = 79,042ft.	79,042	79,042	79,042	79,042
Omissions				
Mi. Marker 127.51 I-55 SB Exit Ramp to I-155 NB			-693	
Mi. Marker 128.99 NB SN 054-0053	-600	-600		
Mi. Marker 129.02 SB SN 054-0054			-600	-600
Mi. Marker 129.39 SB SN 054-0056			-620	-620
Mi. Marker 129.40 NB SN 054-0055	-620	-620		
Mi. Marker 129.79 NB SN 054-0057	-155	-155		
Mi. Marker 129.80 SB SN 054-0058			-155	-155
Mi. Marker 132.06 NB SN 054-0061		-620		
Mi. Marker 132.08 SB SN 054-0060				-545
Exit 133 NB Exit Ramp & SN 054-0061	-1,015			
Exit 133 NB Entrance Ramp	-1,055			
Exit 133 SB Exit Ramp			-767	
Exit 133 SB Entrance Ramp & SN 054-0060			-1,075	
Mi. Marker 135.67 NB SN 054-0063	-320	-320		
Mi. Marker 135.68 SB SN 054-0064			-320	-320
Mi. Marker 138.99 NB SN 054-0065	-130	-130		
Mi. Marker 139.00 SB SN 054-0066			-130	-130
Mi. Marker 139.25 NB SN 054-0067	-160	-160		
Mi. Marker 139.26 SB SN 054-0068			-160	-160
Exit 140 NB Exit Ramp	-696			
Exit 140 NB Entrance Ramp	-1,168			
Exit 140 SB Exit Ramp	-700			
Exit 140 SB Entrance Ramp	-1,140			
Total:	71,283	76,437	74,522	76,512
I-55 LOGAN COUNTY SUBTOTAL: 298,754				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 VARIOUS ROUTES
 SECTION D-6 SHLDR RUMBLE STRIPS 2007
 VARIOUS COUNTIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 3/23/2007
 FILE NAME = d:\projects\72804\shlshr.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = vrsmda