

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	15	9

STA. _____	TO STA. _____
FED. ROAD DIST. NO. _____	ILLINOIS FED. AID PROJECT _____

- * - FAI 55, FAI 72, FAI 155, FAI 172, FAP 302 (IL 336), FAP 310 (US 67), FAP 75 (IL 29), FAP 745 (IL 104)
- ** - D-6 SHOULDER RUMBLE STRIPS 2007
- *** - ADAMS, HANCOCK, LOGAN, MACOUPIN, MONTGOMERY, MORGAN, PIKE, SANGAMON & SCOTT

MAINLINE RESURFACING										
LOCATION	LENGTH	LENGTH	EX PVT WIDTH	EX PVT AREA	HMA SURF REM 3 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLY HMA SURF CSE, SUPER MIX "D" N105 (1.5" THICK.)	POLY HMA BINDER CSE, IL-19.0, N105 (1.75" THICK.)	
	(METER)	(FT)	(FT)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)
I-55 NORTHBOUND DRIVING LANE										
170+223.00 - 173+805.00	3,582.0	11,751.9	12.5	16,322	16,322	9.3	32.6	1371.1	1,828.1*	
I-72 EASTBOUND DRIVING LANE										
189+145.00 - 191+820.00	2,675.0	8,776.2	12.5	12,189	12,189	6.9	24.4	1023.9	1,365.2*	
I-55 TOTALS:					16,322	9.3	32.6	1,371.1	1,828.1	
I-72 TOTALS:					12,189.2	6.9	24.4	1,023.9	1,365.2	
GRAND TOTALS:					28,511	16.3	57.0	2,395.0	3,193.3	

* INCLUDES ADDITIONAL ESTIMATED TONNAGE TO ACCOUNT FOR VARIATIONS IN EXISTING LEVELING BINDER.

BITUMINOUS SHOULDERS										
LOCATION			LENGTH	LENGTH	SHLD WIDTH	HMA SURFACE REMOVAL, 2"	BITUMINOUS MATERIALS (PRIME COAT)	HMA SHOULDERS, 2"		
STATION	TO	STATION	DESCRIPTION	(METER)	(FT)	(FT)	(SQ YD)	(TON)	(SQ YD)	
I-55										
170+223.00	-	173+805.00	NB OUTSIDE	3,582.0	11,751.9	10.0	13,058	4.96	13,058	
170+223.00	-	173+805.00	NB INSIDE	3,582.0	3,582.0	10.0	3,980	1.51	3,980	
169+803.00	-	170+964.00	SB OUTSIDE	1,161.0	1,161.0	10.0	1,290	0.49	1,290	
169+803.00	-	173+298.00	SB INSIDE	3,495.0	11,466.5	10.0	12,741	4.84	12,741	
171+268.00	-	172+244.00	SB OUTSIDE	976.0	3,202.1	10.0	3,558	1.35	3,558	
172+396.00	-	173+298.00	SB OUTSIDE	902.0	2,959.3	10.0	3,288	1.25	3,288	
173+402.00	-	173+805.00	SB OUTSIDE	403.0	1,322.2	10.0	1,469	0.56	1,469	
173+402.00	-	173+805.00	SB INSIDE	403.0	1,322.2	10.0	1,469	0.56	1,469	
I-72										
VARIES*						VARIES*	VARIES	18,000.0*	006.8*	18,000.0*
I-55 TOTALS:							40,852	15.5	40,852	
I-72 TOTALS:							18,000	6.8	18,000	
GRAND TOTALS:							58,852	22.4	58,852	

* FINAL LOCATIONS AND QUANTITIES TO BE DETERMINED IN THE FIELD BY THE ENGINEER.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 VARIOUS ROUTES
 SECTION D-6 SHLDR RUMBLE STRIPS 2007
 VARIOUS COUNTIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

PLOT DATE: 12/22/2007
 FILE NAME: C:\Users\shs\Documents\72B04\72B04.dgn
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: vrsanda