

LONGITUDINAL JOINT REPAIR SCHEDULE			
LOCATION	BEGIN STA	END STA	LOGITUDINAL JOINT REPAIR (FT)
SB RAMP ONTO COLUMBUS RD.	1+80	3+05	125
SB RAMP ONTO COLUMBUS RD.	22+27	22+81	54
I-172 NB CL	225+46	227+00	154
I-172 NB CL	227+90	230+80	290
I-172 NB CL	242+35	242+90	55
I-172 NB CL/DL	259+63	265+47	584
I-172 NB PL	261+28	261+61	33
I-172 NB CL	29+42	35+23	581
I-172 NB PL	52+07	52+40	33
I-172 NB DL	86+10	86+44	34
I-172 NB PL	105+25	106+00	75
I-172 NB DL	107+01	107+77	76
I-172 NB DL	108+62	108+84	22
I-172 NB CL	111+50	113+26	176
I-172 NB PL	113+77	114+55	78
I-172 NB CL	122+00	123+75	175
I-172 NB CL/DL	146+87	149+90	303
I-172 NB PL	221+27	221+65	38
I-172 SB PL	240+57	241+90	133
I-172 SB CL	213+20	213+42	22
I-172 SB CL	207+64	207+95	31
I-172 SB CL	205+13	207+09	196
I-172 SB DL	194+08	194+81	73
I-172 SB DL	169+14	169+71	57
I-172 SB PL	163+50	167+05	355
I-172 SB DL	163+68	163+92	24
I-172 SB CL	143+59	144+44	85
I-172 SB CL	127+81	129+09	128
I-172 SB DL	118+60	120+10	150
I-172 SB DL	117+60	118+12	52
I-172 SB CL	100+30	111+03	1073
I-172 SB CL	97+05	97+81	76
I-172 SB CL	90+27	90+57	30
I-172 SB DL	77+47	88+57	1110
I-172 SB CL	67+53	68+34	81
I-172 SB PL	47+50	48+51	101
I-172 SB CL/DL	45+20	47+92	272
I-172 SB CL	34+60	35+76	116
I-172 SB CL/DL/PL	28+33	32+54	421
I-172 SB CL	14+28	26+28	1200
I-172 SB CL	8+88	11+00	212
I-172 SB CL	7+38	8+00	62
I-172 SB CL	5+00	5+40	40
I-172 SB CL/DL	2+40	288+78	244
I-172 SB DL	259+50	262+21	271
I-172 SB PL	235+92	237+16	124
TOTAL:			9625

PATCHING SCHEDULE									
LOCATION	APPROX. STA	LENGTH (FT)	WIDTH (FT)	PATCHING REINFORCEMENT (SQ YD)	CL. A PATCHES TYPE II, 8" (SQ YD)	CL. A PATCHES TYPE III, 8" (SQ YD)	CL. A PATCHES TYPE IV, 8" (SQ YD)	TIE BARS (EACH)	SAW CUTS (FT)
NBDL	224+78	6	12	8.00	8.00				60
NBDL	256+80	5	12	6.67	6.67				58
NBDL	265+25	15	12	20.00		20.00			78
NBPL	265+25	15	12	20.00		20.00			78
NBDL	284+22	13	12	17.33		17.33			74
NBDL	55+65	15	12	20.00		20.00			78
NBDL	67+20	15	12	20.00		20.00			78
NBDL	91+75	20	12	26.67			26.67	10	88
NBDL	116+25	17	12	22.67		22.67			82
NBPL	116+25	17	12	22.67		22.67			82
NBDL	125+15	8	12	10.67	10.67				64
NBPL	125+15	8	12	10.67	10.67				64
NBDL	139+30	10	12	13.33	13.33				68
NBPL	139+30	10	12	13.33	13.33				68
NBDL	166+70	5	12	6.67	6.67				58
NBPL	226+25	100	12	133.33			133.33	50	248
SBDL	238+15	18	12	24.00		24.00			84
SBPL	238+15	18	12	24.00		24.00			84
SBDL	240+20	8	14	12.44	12.44				72
SBDL	241+50	6	12	8.00	8.00				60
SBDL	139+00	20	12	26.67			26.67	10	88
SBDL	143+85	5	12	6.67	6.67				58
SBDL	166+10	5	12	6.67	6.67				58
SBPL	166+10	5	12	6.67	6.67				58
SBPL	170+30	5	12	6.67	6.67				58
SBDL	177+62	6	12	8.00	8.00				60
SBPL	177+62	6	12	8.00	8.00				60
NB RAMP ONTO US 24	3+00	100	16	177.78			177.78	50	264
TOTALS:				687.56	132.44	190.67	364.44	120	2330

PATCHING SCHEDULES
FAI 172 (I-172)
SECTION 1-5(I); 1-6(I-2)
ADAMS COUNTY