

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	*	WAYNE	19	3

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

(24-2,24)RS-1

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	Y025 50% STATE 50% CITY	Y025 100% CITY
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	45	45		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6485	4667	1818	
40600300	AGGREGATE (PRIME COAT)	TON	130	94	36	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1522	1293	229	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	412	412		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	781	781		
40600990	TEMPORARY RAMP	SQ YD	108	108		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2576	1940	636	
<del>40800050</del>	<del>INCIDENTAL HOT-MIX ASPHALT SURFACING</del>	<del>TON</del>	<del>157</del>	<del>157</del>		
<del>42001200</del>	<del>PAVEMENT FABRIC</del>	<del>SQ YD</del>	<del>67</del>	<del>67</del>		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	20	20		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	492	482	10	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	40	40		
<del>44200976</del>	<del>CLASS B PATCHES, TYPE IV, 10 INCH</del>	<del>SQ YD</del>	<del>27</del>	<del>27</del>		
<del>44213200</del>	<del>SAW CUTS</del>	<del>FOOT</del>	<del>3103</del>	<del>3150</del>	<del>53</del>	
46101200	AGGREGATE SHOULDERS, TYPE B	TON	202	202		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	24	24		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	11	11		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1713	1713		
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	140	140		
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	8146	8146		
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	2745	2745		
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	112	112		
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	65	65		
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	142	142		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	286	286		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140	140		

SUMMARY OF QUANTITIES			URBAN 80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	Y025 50% STATE 50% CITY	Y025 100% CITY
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8146	8146		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2745	2745		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	112	112		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	65	65		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	142	142		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	122	122		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	122	122		
<del>20071100</del>	<del>DOWEL BARS</del>	<del>EACH</del>	<del>1294</del>	<del>1274</del>	<del>20</del>	
20075300	TIE BARS	EACH	23	23		

PLOT DATE = #DATE\*  
 PLOT SCALE = #SCALE\*  
 USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
 DATE: HORIZ.

DRAWN BY  
 CHECKED BY

\* SPECIALTY ITEMS

Rev. 5-31-07

Rev.