

### SCHEDULE OF QUANTITIES (cont'd)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(F-1,1)RS-4	CLARK	46	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**THERMOPLASTIC PAVEMENT MARKINGS, LINE 6" (CROSSWALK)**

STATION	TO	STATION	OFFSET	COLOR	TYPE	FEET
74+41.00		74+41.00	18' LT - 18' RT	WHITE	SOLID	36.0
74+51.00		74+51.00	18' LT - 18' RT	WHITE	SOLID	36.0
99+90.50		100+20.50	31' LT - 21' RT	WHITE	SOLID	59.5
99+96.50		100+29.50	34' LT - 24' RT	WHITE	SOLID	65.9
99+96.50		100+84.00	34' LT - 34' LT	WHITE	SOLID	87.5
100+03.00		100+78.00	40' LT - 40' LT	WHITE	SOLID	75.0
100+44.00		101+24.80	34' RT - 48' RT	WHITE	SOLID	81.1
100+50.00		101+28.30	41' RT - 54' RT	WHITE	SOLID	78.9
100+94.00		101+24.80	30' LT - 48' RT	WHITE	SOLID	82.7
101+00.50		101+32.00	29' LT - 49' RT	WHITE	SOLID	84.3
TOTAL =						687.0

**RAISED REFLECTIVE PAVEMENT MARKERS**

STATION	TO	STATION	2-WAY AMBER	1-WAY AMBER	1-WAY CRYSTAL
37+30.00		63+76.26	34		
63+76.26		65+97.09		11	
66+38.26		68+60.00	12		
66+38.26		68+60.00			6
69+40.00		96+35.00	102		
97+10.00		100+00.00	15		
99+04.00		100+00.00			3
2800+75.50		2801+70.00	6		
2800+75.50		2801+70.00			3
101+21.50		104+10.00			9
101+21.50		104+10.00	14		
104+90.00		141+85.00	152		
TOTAL =			335	11	21

**THERMOPLASTIC PAVEMENT MARKINGS, LINE 12" (PAINTED MEDIAN DIAGONAL)**

STATION	COLOR	FEET
64+24.30	YELLOW	2.7
64+44.30	YELLOW	4.3
64+64.30	YELLOW	5.4
64+84.30	YELLOW	8.6
65+04.30	YELLOW	10.8
65+24.30	YELLOW	12.4
65+44.30	YELLOW	14.6
TOTAL =		59.0

**PARTIAL DEPTH REMOVAL**

STATION	TO	STATION	DIRECTION	LENGTH	WIDTH	SQ YD
*AS DIRECTED BY THE ENGINEER (PARTIAL DEPTH PATCHING TO BE DONE PRIOR TO MILLING)						

**THERMOPLASTIC PAVEMENT MARKINGS, LINE 24" (STOP BAR)**

STATION	TO	STATION	OFFSET	COLOR	FEET
100+00.00		100+00.00	6' LT - 18' RT	WHITE	24.0
2799+36.00		2799+50.54	0' - 29.5' RT	WHITE	33.0
2800+75.50		2800+75.50	0' - 22' LT	WHITE	22.0
2800+75.50		2800+82.60	22' LT - 32.6' LT	WHITE	12.5
101+20.50		101+20.50	30' LT - 6' RT	WHITE	36.0
TOTAL =					128.0

**DETECTOR LOOP, TYPE 1**

STATION	LOOP NO.	LANE	FEET
97+44.00	B5	NORTHBOUND	27.0
98+67.00	B4	NORTHBOUND	27.0
99+67.00	B3	NB - LT. TURN	56.0
99+82.00	B2	NB - LT. TURN	44.0
99+97.00	B1	NB - LT. TURN	52.0
2800+78.00	D1	WB - LT. TURN	57.0
2800+93.00	D2	WB - LT. TURN	51.0
2801+08.00	D3	WB - LT. TURN	63.0
2800+78.00	D4	WESTBOUND	53.0
2800+93.00	D5	WESTBOUND	38.0
101+24.00	A1	SB - LT. TURN	51.0
101+39.00	A2	SB - LT. TURN	56.0
101+54.00	A3	SB - LT. TURN	66.0
102+58.00	A4	SOUTHBOUND	32.0
103+97.00	A5	SOUTHBOUND	28.0
TOTAL =			701.0

PLOT DATE = 3/13/2007  
 FILE NAME = S:\projects\74143\74143\text.dgn  
 USER NAME = staff\ank