

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2701	1101T	EFFINGHAM	7	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		Y007 100% STATE		
20800150	TRENCH BACKFILL	CU YD	516	516		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	50	50		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	30	30		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	10	10		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	10	10		
50105220	PIPE CULVERT REMOVAL	FOOT	31	31		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	169	169		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	799	799		
55100700	STORM SEWER REMOVAL 15"	FOOT	840	840		
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1		
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5	5		
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1		
60235900	INLETS, TYPE A, TYPE 5 FRAME, OPEN LID	EACH	1	1		
60500060	REMOVING INLETS	EACH	2	2		
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	2	2		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
 HORIZ.  
 DATE

DRAWN BY  
 CHECKED BY