CONTRACT NO. 74162

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2701	(101)T	EFFINGHAM	7	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ENTRANCE & SIDEROAD SCHEDULE

STATION	DESCRIPTION	AGGREGATE SURFACE COURSE, TYPE B	INCIDENTAL HOT-MIX ASPHALT SURFACING	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH
		TON	TON	SQ YD
1230+00	S. MONROE ST.		14	
1231+63.5 (RT)	AGGREGATE DRIVEWAY	3		
1232+53 (RT)	AGGREGATE DRIVEWAY	3		
1232+23 TO 1233+95 (LT)	AGGREGATE SHOULDER	26		
1234+26	JACKSON ST.		10	
1234+47 TO 1235+32 (RT)	AGGREGATE SHOULDER	13		
1235+70 (RT)	AGGREGATE DRIVEWAY	5		
1236+85	CONCRETE DRIVEWAY			10
1237+89	VAN BUREN		6	
		50	30	10

* AGGREGATE SURFACE COURSE, TYPE B SHALL BE 6 INCHES.
* INCIDENTAL HOT-MIX ASPHALT SHALL BE 10 INCHES.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $FSCALE$
USER NAME = $USER$