

swartzm
3/29/2007
c:\projects\74202b\d07406pa.dgn

CONTRACT NO. 74202

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	*	MACON	12	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D7 JOINT REPAIRS 2007-3				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SFTY-2A 100% STATE		
50102400	CONCRETE REMOVAL	CU YD	25.6	25.6		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25.6	25.6		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5490	5490		
50800515	BAR SPLICERS	EACH	80	80		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	138	138		
67100100	MOBILIZATION	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	312	312		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9172	9172		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3058	3058		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1187.5	1187.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1187.5	1187.5		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	780	780		
* 78100300	REPLACEMENT REFLECTOR	EACH	52	52		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	260	260		
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	52	52		
X7010825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423 (SPECIAL)	L SUM	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		

*SPECIALTY ITEMS

PLOT DATE = 3/29/2007
FILE NAME = c:\projects\74202b\d07406pa.dgn
PLOT SCALE = 50:0000 / IN.
USER NAME = swartzm

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**SUMMARY
OF
QUANTITIES**
SN 058-0020

SCALE: VERT: DRAWN BY
 HORIZ. CHECKED BY
DATE