



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 30, 2007

SUBJECT: FAP Route 789 (IL 143)
Section 125-RS-3
Madison County
Contract No. 76782
Item No. 20, June 15, 2007 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 6 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Roger Driskell; Estimates; Design & Environment File

TBW:DB:jc

Special attention is called to Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction and the following Highway Standards relating to traffic control:

701006, 701101, 701201, 701301, 701306, 701311, 701336, 701401, 701406, 701411, 701421, 701422, 701426, 702001

In addition, the following Special Provision(s) will also govern traffic control for this project:

Construction and Maintenance Sign Supports
Reflective Sheeting on Channelizing Device

CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS

Effective: April 21, 1981

Revised: November 1, 2006

This work shall be done according to Section 1106 of the Standard Specifications and Highway Standard 702001 except as herein modified.

All construction signs mounted on permanent support for use in temporary traffic control having an area of 10 square feet (1 square meter) or more shall be mounted on two 4 in x 4 in (100 mm x 100 mm) or two 4 in x 6 in (100 mm x 150 mm) wood posts.

Type A metal post (two for each sign) conforming to Article 1006.29 of the Standard Specifications may be used in lieu of wood posts. Type A metal posts used for these signs may be unfinished.

This work shall not be paid for separately; but shall be considered included in the cost of the traffic control items in this contract.

COMPLETE DATE PLUS 5 WORKING DAYS

The Contractor shall complete the work 5 working days after November 30, 2007.

All roadway and shoulder work items shall be completed by the completion date with the exception of permanent pavement marking and raised reflective pavement markers which shall be completed within the allotted working days.

EXPANSION JOINT (SPECIAL)

This work shall consist of installing a traverse expansion joint centered on a proposed Class A Patch. The expansion joint will be constructed concurrently with the Class A Patch. All items of work included in the Standard 442001 will be paid for as a Class A Patch. All other items of work as shown in the EXPANSION JOINT (SPECIAL) detail, will be paid for EXPANSION JOINT (SPECIAL) by the linear foot of expansion joint.

Items included in the expansion joint are dowel bars with expansion cap, preformed flexible foam joint filler, hot poured joint sealer, and dowel bar assemblies.

This work will be paid for at the contract unit price per foot for EXPANSION JOINT (SPECIAL), which price shall include all labor equipment, and materials necessary to complete the work as specified herein and as shown on the plans.

Revised 05/30/2007