

# PATCHING AND RESURFACING SCHEDULE

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	IRS-1	MADISON	26	5
STA. _____		TO STA. _____		
EXISTING CONDITIONS: _____				

DATE \_\_\_\_\_ BY \_\_\_\_\_  
 CHECKED \_\_\_\_\_  
 ALIGNED \_\_\_\_\_  
 PLAN \_\_\_\_\_  
 NOTE BOOK \_\_\_\_\_  
 NO. \_\_\_\_\_

STATION	SIZE	TYPE I SQ. YD.	TYPE II SQ. YD.	LANE
5+97	4 x 11	4.89		E.B. DRIVE LANE
5+97	4 x 11	4.89		LT. TURN LANE
7+49	4 x 13		5.78	E.B. DRIVE LANE
<b>TOTALS</b>		<b>9.78</b>	<b>5.78</b>	

STATION	SIZE	TYPE II SQ. YD.	LANE
254+73	4 x 12	5.33	E.B. DRIVE LANE
254+73	4 x 12	5.33	E.B. PASS LANE
259+68	4 x 12	5.33	E.B. DRIVE LANE
259+68	4 x 12	5.33	E.B. PASS LANE
259+68	4 x 12	5.33	W.B. DRIVE LANE
259+68	4 x 12	5.33	W.B. PASS LANE
259+68	4 x 20	8.89	W.B. LT. TURN LANE
<b>TOTALS</b>		<b>40.87</b>	

STATION	SIZE	TYPE II SQ. YD.	TYPE III SQ. YD.	LANE
104+16	12 x 12		16.00	E.B. DRIVE LANE
104+16	12 x 12		16.00	E.B. PASS LANE
104+16	6 x 16	10.67		W.B. DRIVE LANE
104+16	6 x 12	8.00		W.B. PASS LANE
110+07	6 x 13	8.67		E.B. PASS LANE
111+84	16 x 12.5		22.22	E.B. DRIVE LANE
111+84	16 x 12.5		22.22	E.B. PASS LANE
<b>TOTALS</b>		<b>27.34</b>	<b>76.44</b>	

LOCATIONS	TYPE I SQ. YD.	TYPE II SQ. YD.	TYPE III SQ. YD.
LOCATION #1	9.78	5.78	
LOCATION #2		27.34	76.44
LOCATION #3		40.87	
<b>TOTALS</b>	<b>9.78</b>	<b>73.99</b>	<b>76.44</b>

STATION	HOT MIX ASPHALT SURF. N90 TONS	LEVELING BINDER N90 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	HOT-MIX ASPHALT REMOVAL SQ. YDS.	AGGREGATE SHOULDER TYPE B TONS	HOT-MIX ASPHALT SHOULDER TONS	INCIDENTAL HOT MIX ASPHALT TONS
0+00 TO 9+37	390	195	1.8	9	5643	85	26	29
<b>LOCATION #1 TOTALS</b>	<b>390</b>	<b>195</b>	<b>1.8</b>	<b>9</b>	<b>5643</b>	<b>85</b>	<b>26</b>	<b>29</b>

STATION	HOT MIX ASPHALT SURF. N90 TONS	LEVELING BINDER N90 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	HOT-MIX ASPHALT REMOVAL SQ. YDS.	HOT-MIX ASPHALT SHOULDER TONS
104+10 TO 129+13	1271	636	6.3	30	20269	646
BRIDGE OMISSION	-	-	-	-	-	-
133+87 TO 136+38	298	149	1.2	6	3545	-
<b>LOCATION #2 TOTALS</b>	<b>1569</b>	<b>785</b>	<b>7.5</b>	<b>36</b>	<b>23814</b>	<b>646</b>

STATION	HOT MIX ASPHALT SURF. N90 TONS	LEVELING BINDER N90 TONS	BIT. MATL. PRIME COAT TONS	AGGREGATE PRIME COAT TONS	HOT-MIX ASPHALT REMOVAL SQ. YDS.	HOT-MIX ASPHALT SHOULDER TONS
253+00 TO 264+18	587	294	2.8	14	8831	230
<b>LOCATION #3 TOTALS</b>	<b>587</b>	<b>294</b>	<b>2.8</b>	<b>14</b>	<b>8831</b>	<b>230</b>

DATE: 4/5/2007  
 4:52/2007  
 4:52/2007  
 4:52/2007

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**PATCHING AND RESURFACING SCHEDULES**  
 F.A.P. 789 (IL RTE. 3 & 111)  
 SECTION IRS-1  
 MADISON COUNTY  
 PLOT DATE: 4/5/2007