

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 LOCATION #1	1000 LOCATION #2	1000 LOCATION #3
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	74.7	24.2	24.5	21
<del>40600215</del>	<del>POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>TON</del>	<del>74.5</del>	<del>19.2</del>	<del>34.3</del>	<del>21</del>
40600300	AGGREGATE (PRIME COAT)	TON	326.6	116.5	118.7	91.4
40600895	CONSTRUCTING TEST STRIP	EACH	2			2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	371	188		183
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2332	246	1873	213
40600990	TEMPORARY RAMP	SQ YD	643	128	360	155
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	4626		4626	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	56876			56878
44004250	PAVED SHOULDER REMOVAL	SQ YD	491			491
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	131			131
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	31		31	
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	78		78	
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	659		659	
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	39		39	
44200624	CLASS A PATCHES, TYPE III, 14 INCH	SQ YD	54		54	
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	184		184	
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	39	39		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	551	551		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	74	74		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	143	143		
44213000	PATCHING REINFORCEMENT	SQ YD	1045		1045	
44213100	PAVEMENT FABRIC	SQ YD	160	160		
44213200	SAW CUTS	FOOT	7580	4201	2873	506
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3774	3774		
45100100	CRACK ROUTING (PAVEMENT)	FOOT	193580	95912	97668	
45100200	CRACK FILLING	POUND	71412	31471	39941	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4476	858	3618	
<del>48203005</del>	<del>HOT-MIX ASPHALT SHOULDERS, 2"</del>	<del>SQ YD</del>	<del>2817</del>	<del>2817</del>		
<del>48203012</del>	<del>HOT-MIX ASPHALT SHOULDERS, 3 3/4"</del>	<del>SQ YD</del>	<del>59168</del>	<del>16378</del>	<del>42790</del>	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	9166	2757	6228	181
60100080	FRENCH DRAINS	CU YD	20		20	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	3	3	6
67100100	MOBILIZATION	L SUM	1	0.3	0.3	0.4

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 LOCATION #1	1000 LOCATION #2	1000 LOCATION #3
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	21	8	8	5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.3	0.3	0.4
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	0.3	0.3	0.4
70101805	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	EACH	5			5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	26	1	1	24
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14547	5904	4324	4319
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	140988	37287	61264	42437
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2706	1266		1440
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32077			32077
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2770			2770
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	94910	35987	58923	
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	3641	1300	2341	
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	7590			7590
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2530	492	1266	772
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2530	492	1266	772
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	168			168
X0322729	MATERIAL TRANSFER DEVICE	TON	7983	369	1254	6360
X0324952	DETOUR SIGNING	L SUM	1	0.5	0.5	
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	19,529	6527	6642	6360
△ 40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N105	TON	11,863	2554	9153	155
△ X0325807	PORTLAND CEMENT CONCRETE SURFACE REMOVAL + COLD MILLING 1/2"	SO YD	92,914	20,273	78,641	
△ X0325808	PORTLAND CEMENT CONCRETE SURFACE REMOVAL + COLD MILLING 2"	SO YD	63,853	57,424	6,429	
X4421000	PARTIAL DEPTH PATCHING	TON	1214	194	80	940
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	10827	1728	711	8388
Z0017202	DOWEL BARS 1 1/2"	EACH	1528	1528		
Z0075310	TIE BARS 3/4"	EACH	193		193	

PLOT DATE = 5/1/2007  
 PLOT SCALE = 1/8" = 1'-0"  
 REFERENCE = BREF'S

\*SPECIALTY ITEMS

△ Rev. 6-5-07