

SCHEDULE OF QUANTITIES - LOCATIONS #1 AND #2

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				I000 LOCATION #1	I000 LOCATION #2
	BITUMINOUS MATERIALS (PRIME COAT)	TON	6645	29.2	16.2
	AGGREGATE (PRIME COAT)	TON	195	116.5	78.5
	CONSTRUCTING TEST STRIP	EACH	2		
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	188	188	
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2119	246	1873
	TEMPORARY RAMP	SQ YD	488	128	360
	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0 N105	TON	8333	2554	5779
	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	31		31
	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	78		78
	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	659		659
	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	39		39
	CLASS A PATCHES, TYPE III, 14 INCH	SQ YD	54		54
	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	184		184
	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	39	39	
	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	551	551	
	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	74	74	
	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	143	143	
	PATCHING REINFORCEMENT	SQ YD	1045		1045
	PAVEMENT FABRIC	SQ YD	160	160	
	SAW CUTS	FOOT	7580	4201	2873
	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3774	3774	
	CRACK ROUTING (PAVEMENT)	FOOT	193580	95912	97668
	CRACK FILLING	POUND	71412	31471	39941
	AGGREGATE SHOULDERS, TYPE B	TON	4476	858	3618
	HOT-MIX ASPHALT SHOULDERS	TON	8986	2757	6229
	FRENCH DRAINS	CU YD	20		20
	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
	MOBILIZATION	L SUM	.6	0.3	0.3

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				I000 LOCATION #1	I000 LOCATION #2	I000 LOCATION #3
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	8	8	
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.3	0.3	
	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	.6	0.3	0.3	
	CHANGEABLE MESSAGE SIGN	CAL MO	2	1	1	
	SHORT-TERM PAVEMENT MARKING	FOOT	10228	5904	4324	
	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	98551	37287	61264	
	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1266	1266		
	PAINT PAVEMENT MARKING - LINE 4"	FOOT	94910	35987	58923	
	PAINT PAVEMENT MARKING - LINE 8"	FOOT	3641	1300	2341	
	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1758	492	1266	
	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1758	492	1266	
	MATERIAL TRANSFER DEVICE	TON	1623	369	1254	
	DETOUR SIGNING	L SUM	1	0.5	0.5	
	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	10919	6527	4392	
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/2"	SQ YD	66135	20273	45862	
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2"	SQ YD	63853	57424	6429	
	PARTIAL DEPTH PATCHING	TON	274	194	80	
	PARTIAL DEPTH REMOVAL 2"	SQ YD	2439	1728	711	
	DOWEL BARS 1 1/2"	EACH	1528	1528		
	TIE BARS 3/4"	EACH	193		193	

PLOT DATE = 6/25/2007
 FILE NAME = C:\p2\111111\111111.dwg
 PLOT SCALE = 48.0000 / IN.
 REFERENCE = #REF#

Rev. Sheet 6-5-07