

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MADISON	37	14

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

\*-255-55/70  
 \*\*60-7, 60-9)RS AND 60-(6-1,7-1)RS

LOCATION 1 PAVING SCHEDULE - 3 1/4" RESURFACING

STATIONING	BITUMINOUS	AGGREGATE	POLYMERIZED	POLYMERIZED	PCC SURFACE	PCC	HOT MIX	COMMENTS
	MATERIIL PRIME COAT	PRIME COAT	HMA BINDER COURSE, IL-19.0, N105	HMA SURFACE COURSE, SMA, N80	REMOVAL - 1/2" BUTT JOINT	SURFACE REMOVAL - 1/2" SQ YD	ASPHALT SHOULDERS	
	TON	TON	TON	TON	SQ YD	SQ YD	TON	
310+00 TO 315+55	0.3	1.7	140	93		1110	181	RAMP 3
101+00 TO 107+40	1.1	5.1	427	285		3392	303	RAMP 1
110+00 TO 114+00	0.3	1.6	134	90		1067	75	RAMP 1
114+00 TO 152+25.50	3.2	15.3	1285	857		10201	1250	RAMP 1
152+25.5 TO 162+00	1.2	5.6	470	314		3733	318	RAMP 1
400+00 TO 403+00	0.2	0.8	67	45		533	70	RAMP 4
200+00 TO 224+00	0.1	0.4	30	20	246	237	560	RAMP 2
	6.3	30.4	2554	1703	246	20273	2757	

LOCATION 1 AND 2 PAVING SCHEDULE - 2" RESURFACING

STATIONING	BITUMINOUS	AGGREGATE	POLYMERIZED	PCC	COMMENTS
	MATERIIL PRIME COAT	PRIME COAT	HMA SURFACE COURSE, SMA, N80	SURFACE REMOVAL - 2" SQ YD	
	TON	TON	TON	SQ YD	
760+00 TO 764+64	0.4	1.9	104	1237	LOC. 2 - RAMP 6
764+64 TO 788+28	1.3	6.3	353	4200	LOC. 2 - RAMP 6
788+28 TO 792+00	0.3	1.5	83	992	LOC. 2 - RAMP 6
1256+00 TO 1272+00	3.3	15.8	887	10561	LOC. 1 - MAINLINE (I-270)
1274+00 TO 200+00	0.4	2.0	114	1353	LOC. 1 - RAMP 2
224+00 TO 492+00	14.9	71.5	4002	47644	LOC. 1 - RAMP 2
	20.6	99.0	5543	65987	

LOCATION 2 PAVING SCHEDULE - 3 1/4" RESURFACING

STATIONING	BITUMINOUS	AGGREGATE	POLYMERIZED	POLYMERIZED	PCC SURFACE	BITUMINOUS	PCC	HOT MIX	COMMENTS
	MATERIIL PRIME COAT	PRIME COAT	HMA BINDER COURSE, IL-19.0, N105	HMA SURFACE COURSE, SMA, N80	REMOVAL - 1/2" BUTT JOINT	SURF. REMOV. - 1/2" BUTT JOINT	SURFACE REMOVAL - 1/2" SQ YD	ASPHALT SHOULDERS	
	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON	
340+48 TO 366+50	1.4	6.9	583	389		188	4626	486	RAMP 3
693+63 TO 703+16	0.8	3.8	320	213			2541	311	RAMP 6
703+16 TO 706+00	0.2	1.1	95	64			757	53	RAMP 6
706+00 TO 756+02	4.2	20.0	1681	1120			13339	1634	RAMP 6
756+02 TO 760+00	0.3	1.6	134	89			1061	130	RAMP 6
1558+00 TO 1593+65	1.8	8.8	740	493			5872	0	RAMP 6
703+16 TO 706+00	0.1	0.4	30	20			237	53	RAMP 7
706+00 TO 712+50	0.4	1.7	146	97	188		1156	212	RAMP 7
1564+00 TO 1584+31	0.5	2.5	206	137	246		1634	0	RAMP 1
1584+31 TO 1589+00	0.4	1.9	158	105			1251	69	RAMP 1
1556+00 TO 1598+00	5.3	25.2	2117	1411	722		16800	1372	MAINLINE - I-255(NB)
1556+00 TO 1614+42	7.3	35.1	2944	1963	722		23368	1908	MAINLINE - I-255(SB)
TOTAL	22.7	109.0	9153	6102	1878	188	72641	6229	

PLOT DATE = 5/25/2007  
 FILE NAME = c:\pvs\pvs\ad\081307\cadd\p\081307.dgn  
 PLOT SCALE = 50.0000 / 1" = 100'  
 USER NAME = chaitandante

Rev. Sheet 0-5-04

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

FAI 255, FAI 55/70  
 SECTION (60-7, 60-9)RS &  
 60-(6-1,7-1)RS  
 MADISON COUNTY

SCALE: VERT. DATE  
 HORIZ. DATE

DRAWN BY  
 CHECKED BY