CONTRACT NO. 76B15

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MADISON	37	16
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*-255-55/70
**(60-7, 60-9)RS AND 60-(6-1,7-1)RS

TYPE A PATCHING SCHEDULE - 11"

STATION	DRIV. LANE LTH.	DRIV. LANE WTH.	TYPE I SQ YDS	TYPE II SQ YDS	TYPE III SQ YDS	TYPE IV SQ YDS	SAW CUTTING FEET	PATCHING REINF. SQ YDS	TIE BARS EACH	REMARKS
148+04	30	16				53	125	53	145	RAMP 1 - I-270 (EB) TO I-255 (SB)
148+20	4	16		7			73	7	15	RAMP 1 - I-270 (EB) TO I-255 (SB)
177+00	12	16			21		89	21	55	RAMP 1 - I-270 (EB) TO I-255 (SB)
SUB-TOTAL			0	7	21	53	287	81	215	RAMP 1 - TOTAL
761+50	10	16			18		85	18	45	RAMP 3 - I-270 (SB) TO I-255 (WB)
782+62	6	16		11			77	11	25	RAMP 3 - I-270 (SB) TO I-255 (WB)
793+18	12	16			21		89	21	55	RAMP 3 - I-270 (SB) TO I-255 (WB) (IL 111 RAMP)
798+46	50	16				89	165	89	245	RAMP 3 - I-270 (SB) TO I-255 (WB) (IL 111 RAMP)
SUB-TOTAL			0	11	39	89	416	139	325	RAMP 3 - TOTAL
462+52	10	16			18		85	18	45	RAMP 4 - I-270 (WB) TO I-255 (SB)
468+50	180	16				320	425	320	895	RAMP 4 - I-270 (WB) TO I-255 (SB)
469+64	15	16				27	95	27	70	RAMP 4 - I-270 (WB) TO I-255 (SB)
476+90	20	16				36	105	36	95	RAMP 4 - I-270 (WB) TO I-255 (SB)
SUB-TOTAL			0	0	18	383	710	401	1060	RAMP 4 - TOTAL
1568+00	50	12				67	149	67	196	MAINLINE I-255 (NB)
1579+00	50	12				67	149	67	196	MAINLINE I-255 (NB)
SUB-TOTAL			0	0	0	134	298	134	196	MAINLINE - TOTAL
722+75	10	12		13			69	13	36	RAMP 7 - I-255 (NB) TO I-270 (EB)
SUB-TOTAL			0	13	0	0	69	13	36	RAMP 7 - TOTAL
TOTAL			0	31	78	659	1780	768	1832	

TYPE A PATCHING SCHEDULE - 14"

STATION	DRIV. LANE LTH.	DRIV. LANE WTH.	TYPE I SQ YDS	TYPE II SQ YDS	TYPE III SQ YDS	TYPE IV SQ YDS	SAW CUTTING FEET	PATCHING REINF. SQ YDS	TIE BARS EACH	REMARKS
1551+46	6	16		11			77	11	25	RAMP 6 - I-270 (NB) TO I-255 (WB)
1567+30	4	16		7			73	7	15	RAMP 6 - I-270 (NB) TO I-255 (WB)
1577+80	4	16		7			73	7	15	RAMP 6 - I-270 (NB) TO I-255 (WB)
1593+50	20	32				71	169	71	190	RAMP 6 - I-270 (NB) TO I-255 (WB)
703+18	8	16		14			81	14	35	RAMP 6 - I-270 (NB) TO I-255 (WB)
703+26	10	16			18		85	18	45	RAMP 6 - I-270 (NB) TO I-255 (WB)
708+50	10	16			18		85	18	45	RAMP 6 - I-270 (NB) TO I-255 (WB)
708+60	10	16			18		85	18	45	RAMP 6 - I-270 (NB) TO I-255 (WB)
731+51	170	6				113	365	113	338	RAMP 6 - I-270 (NB) TO I-255 (WB)
RAMP 6 TOTAL			0	39	54	184	1093	277	753	

PLOT DATE = 5/25/2007
FILE NAME = c:\pw_work\ed85367\cadd\plr85367ed.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = chaliandsake

Rev. Sheet 6-5-07

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAI 255, FAI 55/70
SECTION (60-7, 60-9)RS &
60-(6-1,7-1)RS
MADISON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY