

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MADISON	37	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*-255-55/70				
**160-7, 60-9/RS AND 60-16-1,7-1/RS				

11" TYPE B PATCHING SCHEDULE

STATION	DRIV. LANE		TYPE I SQ YDS	TYPE II SQ YDS	TYPE III SQ YDS	TYPE IV SQ YDS	SAW CUT FT	DOWEL BARS EACH	PAVT. FABRIC SQ YDS
	LTH.	WTH.							
ROADWAY "B"									
RT 800+00	6	12		8			49	20	
LT 800+00	6	12		8			49	20	
RT 800+40	6	12		8			49	20	
RT 800+58	6	12		8			49	20	
RT 801+00	6	12		8			49	20	
LT 801+00	6	12		8			49	20	
RT 801+34	6	6	4				31	10	
LT 801+34	6	6	4				31	10	
RT 801+55	6	12		8			49	20	
LT 801+55	6	6	4				31	10	
LT 801+74	6	6	4				31	10	
RT 801+74	6	12		8			49	20	
RT 801+87	6	12		8			49	20	
LT 801+87	6	12		8			49	20	
RT 802+16	6	12		8			49	20	
RT 802+56	6	12		8			49	20	
RT 802+95	6	12		8			49	20	
RT 803+36	6	12		8			49	20	
LT 803+54	6	12		8			49	20	
RT 803+54	6	6	4				31	10	
LT 803+76	6	6	4				31	10	
RT 803+76	6	12		8			49	20	
RT 804+15	6	12		8			49	20	
LT 804+32	6	12		8			49	20	
RT 804+32	6	15		10			58	26	
RT 804+55	6	15		10			58	26	
RT 804+95	6	16		11			61	28	
LT 804+62	6	12		8			49	20	
RT 810+38	6	12		8			49	20	
RT 814+44	6	12		8			49	20	
LT 814+44	6	12		8			49	20	
LT 814+79	6	12		8			49	20	
RT 824+62	6	12		8			49	20	
LT 824+62	6	12		8			49	20	
LT 835+79	6	12		8			49	20	
RT 840+28	6	6	4				31	10	
LT 840+28	6	6	4				31	10	
LT 843+35	6	12		8			49	20	
RT 843+35	6	12		8			49	20	
RT 843+77	6	12		8			49	20	
RT 859+45	6	12		8			49	20	
RT 864+00	6	12		8			49	20	
RT 864+59	6	12		8			49	20	
LT 866+14	6	12		8			49	20	
RT 866+14	6	12		8			49	20	
RT 866+97	6	12		8			49	20	
RDWY "B" TOTAL			32	311	0	0	2140	860	0
ROADWAY "A"									
RT 699+07	12	12			16		61	20	
LT 699+07	6	12		8			49	20	
RT 700+05	20	12				27	77	20	27
RT 700+31	6	12		8			49	20	
RT 735+15	6	12		8			49	20	
RT 735+45	6	12		8			49	20	
LT 735+45	6	12		8			49	20	
LT 737+27	6	12		8			49	20	
RT 737+27	6	12		8			49	20	
RT 737+70	6	12		8			49	20	
LT 737+70	6	12		8			49	20	
RT 738+00	6	12		8			49	20	
LT 738+30	6	12		8			49	20	
RT 738+30	6	12		8			49	20	
RDWY "A" TOTAL			0	96	16	27	726	280	27

STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	PARTIAL DEPTH REMOVAL, 2"	PARTIAL DEPTH PATCHING	BITUMINOUS MATERIAL (PRIME COAT)	REMARKS
				SQ YD	TON		
148+04	100	2	22.2	22.2	2.5	0.0070	RAMP 1 - I-270(EB) TO I-255 (SB)
158+60	100	2	22.2	22.2	2.5	0.0070	RAMP 1 - I-270(EB) TO I-255 (SB)
169+16	1584	2	352.0	352.0	39.4	0.1101	RAMP 1 - I-270(EB) TO I-255 (SB)
SUB-TOTAL				396.4	44.4	0.12	RAMP 1 TOTAL
467+25	8	2	1.8	1.8	0.2	0.0006	RAMP 4 - I-270(WB) TO I-255(SB)
467+33	10	2	2.2	2.2	0.2	0.0007	RAMP 4 - I-270(WB) TO I-255(SB)
467+45	12	2	2.7	2.7	0.3	0.0008	RAMP 4 - I-270(WB) TO I-255(SB)
466+30	1060	2	235.6	235.6	26.4	0.0737	RAMP 4 - I-270(WB) TO I-255(SB)
477+10	125	2	27.8	27.8	3.1	0.0087	RAMP 4 - I-270(WB) TO I-255(SB)
202+00	14	2	3.1	3.1	0.3	0.0010	RAMP 4 - I-270(WB) TO I-255(SB)
SUB-TOTAL				273.1	30.6	0.09	RAMP 4 TOTAL
709+00	100	2	22.2	22.2	2.5	0.0070	RAMP 7 - I-255(NB) TO I-270(EB)
722+85	100	2	22.2	22.2	2.5	0.0070	RAMP 7 - I-255(NB) TO I-270(EB)
SUB-TOTAL				44.4	5.0	0.01	RAMP 7 TOTAL
LOCATION 2 TOTAL				714.0	80.0	0.2	

PLOT DATE = 5/26/2007  
 FILE NAME = c:\pcc\pcc\mads\08307\used\pud\08307.dgn  
 PLOT SCALE = 50.0000' / IN.  
 USER NAME = challandake

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

FAI 255, FAI 55/70  
 SECTION (60-7, 60-9/RS &  
 60-16-1,7-1/RS  
 MADISON COUNTY

SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE

△ Rev. Sheet 6-5-07