

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	96-00094-01-WR	KANE	187	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 83737				

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY STU 1000-2A	SPRING TRAF SIGNAL STU Y031-1F	BOWES TRAF SIGNAL STU Y031-1F	LIGHT SPRING STU Y030-1E	LIGHT BOWES STU Y030-1E	INTER-CONNECT CMAQ Y031-1F	STATE 100% 1000-2A	VILLAGE NON-PART SPRING Y031-1F	VILLAGE NON-PART BOWES Y031-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,380	1,380								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	224	224								
20101100	TREE TRUNK PROTECTION	EACH	20	20								
20200100	EARTH EXCAVATION	CU YD	29,754	28,342						1412		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,817	4,695						122		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	10,000	8,000						2000		
20800150	TRENCH BACKFILL	CU YD	6,277	3,555						2722		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	31,988	25,312						6676		
* 25000210	SEEDING, CLASS 2A	ACRE	5.1	3.9						1.2		
* 25000350	SEEDING, CLASS 7	ACRE	0.3	0.3								
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	459	352						107		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	459	352						107		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	459	352						107		
* 25100115	MULCH, METHOD 2	ACRE	5.1	3.9						1.2		
* 25200110	SODDING, SALT TOLERANT	SQ YD	7,293	6,231						1062		
25200200	SUPPLEMENTAL WATERING	UNIT	305	245						60		
28000300	TEMPORARY DITCH CHECKS	EACH	8	6						2		
28000400	PERIMETER EROSION BARRIER	FOOT	14,070	10,950						3120		
28000500	INLET AND PIPE PROTECTION	EACH	69	63						6		
28000510	INLET FILTERS	EACH	300	240						60		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3,145	2,472						673		
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	143							143		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	599	471						128		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	14,209	9,808						4401		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	140	110						30		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL.	374	308						66		
40600300	AGGREGATE (PRIME COAT)	TON	58	50						8		
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	6	5						1		
40600535	LEVELING BINDER (HAND METHOD), N 70	TON	15	15								
40600635	LEVELING BINDER (MACHINE METHOD), N 70	TON	38	38								
40600895	CONSTRUCTING TEST STRIP	EACH	5	4						1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	332	285						47		
40600990	TEMPORARY RAMP	SQ YD	399	285						114		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N 70	TON	25,271	24,202						1069		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 50	TON	103	91						12		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N 70	TON	660	570						90		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	112	90						22		
42001300	PROTECTIVE COAT	SQ YD	9,044	8,459						585		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	43							43		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,312	1,047						265		

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

**URS** 100 SOUTH WACKER DR, STE 500 TEL (312) 939-1000  
CHICAGO, IL 60606 FAX (312) 939-4198

**MCLEAN BOULEVARD**  
**SUMMARY OF QUANTITIES**

SCALE: NONE DRAWN BY ARM  
DATE 4/6/2007 CHECKED BY DDL