

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509 96-00094-01-WR		KANE	187	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83737

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY STU 1000-2A	SPRING TRAF SIGNAL STU Y031-1F	BOWES TRAF SIGNAL STU Y031-1F	LIGHT SPRING STU Y030-1E	LIGHT BOWES STU Y030-1E	INTER-CONNECT CMAQ Y031-1F	STATE 100% 1000-2A	VILLAGE NON-PART SPRING Y031-1F	VILLAGE NON-PART BOWES Y031-1F
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	30,396	29,307						1089		
42400800	DETECTABLE WARNINGS	SQ FT	420	390						30		
44000100	PAVEMENT REMOVAL	SQ YD	25,276	23,768						1508		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8,714	6,130						2584		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,645	1,925						720		
44000300	CURB REMOVAL	FOOT	755	755								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5,350	4,598						752		
44000600	SIDEWALK REMOVAL	SQ FT	5,051	5,051								
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	900	856						44		
44003100	MEDIAN REMOVAL	SQ FT	66	66								
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	180	72						108		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	135	54						81		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	90	36						54		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	45	18						27		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,315	2,615						1700		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	569	569								
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	438	438								
50300225	CONCRETE STRUCTURES	CU YD	29	29								
50500505	STUD SHEAR CONNECTORS	EACH	160	160								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,620	2,620								
54200640	PIPE CULV. TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	165	165								
5421C015	PIPE CULVERTS, CLASS C, TYPE 1 15" (TEMPORARY)	FOOT	411	401						10		
54213867	STEEL END SECTIONS 12"	EACH	2	2								
54213870	STEEL END SECTIONS 15"	EACH	4	4								
54248510	CONCRETE COLLAR	CU YD	7.2	5.7						1.5		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2,315	2,010						305		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	232	232								
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	6	6								
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	26	26								
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1,267	1,267								
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	372	372								
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	683	75						608		
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	314	314								
550A0780	STORM SEWERS, CLASS A, TYPE 3, 48"	FOOT	305							305		
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	409	395						14		
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	52	52								
550A2610	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 42"	FOOT	100	100								
550A2740	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 3 18"	FOOT	122							122		
55034600	RISE 29 STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 45,	FOOT	335	335								
55035900	RISE 38 STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 60,	FOOT	155	155								

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

URS 100 SOUTH WACKER DR. STE 500 TEL (312) 939-1000
CHICAGO, IL 60606 FAX (312) 939-4198

MCLEAN BOULEVARD

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY ARM
DATE 4/6/2007 CHECKED BY DDL