


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	96-00094-01-WR	KANE	187	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 83737				

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY STU 1000-2A	SPRING TRAF SIGNAL STU Y031-1F	BOWES TRAF SIGNAL STU Y031-1F	LIGHT SPRING STU Y030-1E	LIGHT BOWES STU Y030-1E	INTER-CONNECT CMAQ Y031-1F	STATE 100% 1000-2A	VILLAGE NON-PART SPRING Y031-1F	VILLAGE NON-PART BOWES Y031-1F
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2		1	1						
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		1	1						
89502380	REMOVE EXISTING HANDHOLE	EACH	10		10							
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9							
* A2000112	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	11	10							1	
* A2005014	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	11	10							1	
X0320139	TEMPORARY CONSTRUCTION FENCE	FOOT	5,000	4,000							1000	
* X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	2		1	1						
X0321598	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	5	5								
X0321720	WATER MAIN REMOVAL	FOOT	300	300								
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS), 12 INCH	FOOT	50	50								
X0322344	IMPACT ATTENUATOR REPLACEMENT ASSEMBLY	EACH	6	6								
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3830					3830				
X0323005	AUXILIARY VALVE AND VALVE BOX	EACH	1	1								
* X0323670	PREFORMED DETECTOR LOOP	FOOT	129			129						
X0795800	COARSE AGGREGATE	TON	8	8								
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	11,885	7,969						3916		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4							4		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	14						1		
X4023000	TEMPORARY ACCESS (ROAD)	EACH	6	6								
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	1,776	1,776								
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2		1	1						
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3,855					3855				
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	3205		1624	1581						
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3C, TWISTED, SHIELDED	FOOT	990								325	665
* XX002056	REOPTIMIZE EXISTING SIGNAL SYSTEM	EACH	1						1			
* XX003583	VIDEO ELECTRIC CABLE IN CONDUIT, NO. 16 3/C	FOOT	1,712		937	775						
* XX003584	VIDEO BELDEN 8281 COAXIAL CABLE IN CONDUIT	FOOT	1,712		937	775						
* XX004923	BATTERY BACK-UP UPS SYSTEM	L SUM	1		0.5	0.5						
XX006055	MANHOLES, TYPE A, 7' DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3	2						1		
XX006057	GUARDRAIL, SPECIAL	FOOT	145	145								
Z0001050	AGGREGATE SUBGRADE 12'	SQ YD	41,220	39,600						1620		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	6	6								
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	6	6								
△ Z0076600	TRAINEES	HOUR	2,000	2,000								

\* SPECIALTY ITEM  
 △ Y080

<b>REVISIONS</b>	
NAME	DATE



100 SOUTH WACKER DR. STE 500 TEL (312) 939-1000  
 CHICAGO, IL 60606 FAX (312) 939-4198

**MCLEAN BOULEVARD**

**SUMMARY OF QUANTITIES**

SCALE: NONE      DRAWN BY: ARM  
 DATE: 4/6/2007      CHECKED BY: DDL