

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2509	86-00094-01-WR	KANE	187	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING SCHEDULE

LIMITS FOR TEMP. WIDENING (35600500)
 STA. 29+71 TO 40+00
 STA. 40+00 TO 52+00
 STA. 52+00 TO 64+00
 STA. 64+00 TO 76+00
 STA. 76+00 TO 86+00
 STA. 86+00 TO 90+00

LOCATION	(31101200) SUB-BASE GRANULAR MATERIALS TYPE B, 4"	(35600716) HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	(35501331) HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 11 3/4"	(40603085) HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2 1/4"	(Z0001050) AGGREGATE SUBGRADE, 12"	(40603340) HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 2"	(40600400) MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	(40600100) BITUMINOUS MATERIALS (PRIME COAT)	(40600300) AGGREGATE (PRIME COAT)	(42001300) PROTECTIVE COAT	HOT-MIX ASPHALT BASE COURSE WIDENING, 10" (TEMPORARY PAVEMENT)	(42400200) PCC SIDEWALK 5"
	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(TON)	(GAL)	(TON)	(SQ YD)	(SQ YD)	(SQ FT)	
McLEAN BLVD.												
STA. 33+90 TO 37+00	248	163		88	120	712	20	2	171			
STA. 37+00 TO 45+00	425	322	1530	370	1620	712	46	6	414	2742	1089	
STA. 45+00 TO 49+00			3151		3411	131	36	6	899	1951	4840	
STA. 49+00 TO 55+00			4744		5088	545	46	6	959	753	3113	
STA. 55+00 TO 61+00			4117		4461	473	45	6	713	1303	3130	
STA. 61+00 TO 67+00			4000		4461	460	50	6	733	769	3000	
STA. 67+00 TO 73+00			4000		4344	460	45	6	626	842	3020	
STA. 73+00 TO 79+00			4000		4344	460	50	6	666		2733	
STA. 79+00 TO 85+00			4076		4316	469	35	5	622		3030	
STA. 85+00 TO 90+00			3551		3838	408			649		2500	
SIDE STREETS												
SUNBURY RD.												
HOPPS RD./SPRING ST.	1860	1430	2027	821	2172	963		4	1748		2629	
KANE ST.						25			43			
SANDHURST LANE						24			43			
JENNA DR.						72			89			
SUNDOWN DR.						27			39			
BOWES RD.	612	409	2904	268	3165	573		4	630	1300	1312	
TOTALS	3145	2324	38100	1579	41220	5890	6	374	58	9044	11885	30396

PAVING SCHEDULE (CONT.)

LOCATION	(48101200) AGGREGATE SHOULDERS TYPE B	(48203029) HOT-MIX ASPHALT SHOULDER, 8"	(40600535) LEVELING BINDER (HAND METHOD), N70	(40600635) LEVEL BINDER (MACHINE METHOD), N70	(406033310) HOT-MIX ASPHALT SURFACE COURSE MIX "C", N50 4"	(60603800) CONCRETE MEDIAN TYPE SB-6.06
	(TON)	(SQ YD)			(SQ YD)	(SQ FT)
McLEAN BLVD.						
STA. 31+96 TO 37+00						
STA. 37+00 TO 45+00						
STA. 45+00 TO 49+00						
STA. 49+00 TO 55+00						
STA. 55+00 TO 61+00						
STA. 61+00 TO 67+00						
STA. 67+00 TO 73+00						
STA. 73+00 TO 79+00						
STA. 79+00 TO 85+00						
STA. 85+00 TO 90+00						
SIDE STREETS						
SUNBURY RD.						
HOPPS RD./SPRING ST.					65	828
KANE ST.						
SANDHURST LANE						
JENNA DR.						
SUNDOWN DR.						
BOWES RD.	569	438			130	
TOTALS	569	438	15	38	195	828

TREE REMOVAL SCHEDULE

LOCATION	(20100110) TREE REMOVAL (6 TO 15 UNITS DIA.) AVERAGE 10 UNITS		(20100210) TREE REMOVAL (OVER 15 UNITS DIA.) AVERAGE 18 UNITS	
	NO.	UNITS	NO.	UNITS
McLEAN BLVD.				
STA. 33+90 TO STA. 35+00	0	0	0	0
STA. 35+00 TO STA. 36+00	0	0	0	0
STA. 36+00 TO STA. 37+00	0	0	0	0
STA. 37+00 TO STA. 38+00	0	0	0	0
STA. 38+00 TO STA. 39+00	0	0	0	0
STA. 39+00 TO STA. 40+00	0	0	0	0
STA. 40+00 TO STA. 41+00	0	0	0	0
STA. 41+00 TO STA. 42+00	2	20	0	0
STA. 42+00 TO STA. 43+00	2	20	0	0
STA. 43+00 TO STA. 44+00	3	30	0	0
STA. 44+00 TO STA. 45+00	1	10	0	0
STA. 45+00 TO STA. 46+00	0	0	0	0
STA. 46+00 TO STA. 47+00	0	0	0	0
STA. 47+00 TO STA. 48+00	3	30	0	0
STA. 48+00 TO STA. 49+00	4	40	0	0
STA. 49+00 TO STA. 50+00	1	10	0	0
STA. 50+00 TO STA. 51+00	0	0	0	0
STA. 51+00 TO STA. 52+00	0	0	0	0
STA. 52+00 TO STA. 53+00	0	0	0	0
STA. 53+00 TO STA. 54+00	0	0	0	0
STA. 54+00 TO STA. 55+00	0	0	0	0
STA. 55+00 TO STA. 56+00	4	40	0	0
STA. 56+00 TO STA. 57+00	8	80	0	0
STA. 57+00 TO STA. 58+00	0	0	0	0
STA. 58+00 TO STA. 59+00	12	120	4	72
STA. 59+00 TO STA. 60+00	0	0	1	18
STA. 60+00 TO STA. 61+00	4	40	0	0
STA. 61+00 TO STA. 62+00	3	30	0	0
STA. 62+00 TO STA. 63+00	7	70	0	0
STA. 63+00 TO STA. 64+00	3	30	0	0
STA. 64+00 TO STA. 65+00	1	10	0	0
STA. 65+00 TO STA. 66+00	4	40	0	0
STA. 66+00 TO STA. 67+00	3	30	0	0
STA. 67+00 TO STA. 68+00	6	60	0	0
STA. 68+00 TO STA. 69+00	2	20	0	0
STA. 69+00 TO STA. 70+00	1	10	0	0
STA. 70+00 TO STA. 71+00	3	30	0	0
STA. 71+00 TO STA. 72+00	5	50	0	0
STA. 72+00 TO STA. 73+00	4	40	0	0
STA. 73+00 TO STA. 74+00	6	60	0	0
STA. 74+00 TO STA. 75+00	5	50	0	0
STA. 75+00 TO STA. 76+00	1	10	0	0
STA. 76+00 TO STA. 77+00	0	0	0	0
STA. 77+00 TO STA. 78+00	2	20	0	0
STA. 78+00 TO STA. 79+00	2	20	0	0
STA. 79+00 TO STA. 80+00	1	10	0	0
STA. 80+00 TO STA. 81+00	4	40	0	0
STA. 81+00 TO STA. 82+00	6	60	0	0
STA. 82+00 TO STA. 83+00	3	30	2	36
SUBTOTAL		1160		126

SEE NEXT SHEET FOR THE CONTINUATION OF TREE REMOVAL SCHEDULE.

CONCRETE CURB & GUTTER SCHEDULE

LOCATION	(60605000) COMBINATION CONC. CURB & GUTTER TYPE B-6.24	(60603800) COMBINATION CONC. CURB & GUTTER TYPE B-6.12
	FT	FT
McLEAN BLVD.		
STA. 33+90 TO 37+00	310	
STA. 37+00 TO 45+00	692	
STA. 45+00 TO 49+00	618	
STA. 49+00 TO 55+00	1094	
STA. 55+00 TO 61+00	1095	
STA. 61+00 TO 67+00	1200	
STA. 67+00 TO 73+00	980	
STA. 73+00 TO 79+00	1087	
STA. 79+00 TO 85+00	839	
STA. 85+00 TO 90+00	1000	
SIDE STREETS		
SUNBURY RD.		
HOPPS RD./SPRING ST.	2070	
KANE ST.	128	
SANDHURST LANE	129	
JENNA DR.	267	
SUNDOWN DR.	118	
BOWES RD.	885	664
TOTALS	12512	664

SEE SHT NO. 11 FOR ADDITIONAL C&G B6.12 SCHEDULE.

REMOVAL SCHEDULE

LIMITS FOR TEMP. PAVEMENT REMOVAL (X0919000)

STA. 29+71 TO 40+00
 STA. 40+00 TO 52+00
 STA. 52+00 TO 64+00
 STA. 64+00 TO 76+00
 STA. 76+00 TO 86+00
 STA. 86+00 TO 90+00

LOCATION	(44000100) PAVEMENT REMOVAL	(44000198) HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	(40600982) HOT-MIX ASPHALT SURFACE REMOVAL (BUTT JOINT)	(44000500) COMB. CURB & GUTTER REMOVAL	(44000600) SIDEWALK REMOVAL	(X0919000) TEMPORARY PAVEMENT REMOVAL
	(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(SQ FT)	(SQ YD)
McLEAN BLVD.						
STA. 31+96 TO 37+00	34	1024	47	0	1174	
STA. 37+00 TO 45+00	1474	1560		752	0	2742
STA. 45+00 TO 49+00	1974			620	2288	1951
STA. 49+00 TO 55+00	2311			625	56	753
STA. 55+00 TO 61+00	1838					1303
STA. 61+00 TO 67+00	2177					769
STA. 67+00 TO 73+00	3634				198	
STA. 73+00 TO 79+00	3203				123	842
STA. 79+00 TO 85+00	3132				382	
STA. 85+00 TO 90+00	2093					
SIDE STREETS						
SUNBURY RD.						
HOPPS RD./SPRING ST.	865	4466	188	2234	1826	1050
KANE ST.				144		
SANDHURST LANE				145		
JENNA DR.				254		
SUNDOWN DR.				105		
BOWES RD.	2541	1664	97	471	178	1300
TOTALS	25276	8714	332	5350	5051	11885

URS 100 SOUTH WACKER DRIVE
 SUITE 500 CHICAGO, IL 60606 TEL (312) 939-1000 FAX (312) 939-4198

REVISIONS	
NAME	DATE

McLEAN BOULEVARD SCHEDULE OF QUANTITIES I

SCALE: N/A DRAWN BY: KLM
 DATE: 04/06/2007 CHECKED BY: