

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2545	98-00036-19-FF	WILL	147	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83896

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1	RETAINING WALLS	TRAFFIC SIGNALS 1	TRAFFIC SIGNALS 2	CONSTRUCTION TYPE CODE			NON-PARTICIPATING	
								BOUGHTON RD	104TH ST	BIKE TRAIL	BOLINGBROOK	
				1000-2A	Y007	Y031-1F	Y031-1F	Y046				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	90	90								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	387	387								
20101000	TEMPORARY FENCE	FOOT	784	784								
20101100	TREE TRUNK PROTECTION	EACH	4	4								
20200100	EARTH EXCAVATION	CU YD	30615	30615								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1916	1916								
20400800	FURNISHED EXCAVATION	CU YD	1188	1188								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1500	1500								
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	662	662								
20800150	TRENCH BACKFILL	CU YD	6125	6124.9								
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	9137	9137								
* 25000210	SEEDING, CLASS 2A	ACRE	3.50	3.5								
* 25000312	SEEDING, CLASS 4A	ACRE	1.00	0.5								
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	562	562								
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	562	562								
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	562	562								
* 25100115	MULCH, METHOD 2	ACRE	7.00	7								
* 25100630	EROSION CONTROL BLANKET	SQ YD	17764	17764								
* 25200110	SODDING, SALT TOLERANT	SQ YD	17816	17816								
* 25200200	SUPPLEMENTAL WATERING	UNIT	161	161								
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	700	700								
* X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	27	27								
* 28000400	PERIMETER EROSION BARRIER	FOOT	16788	16788								
28000500	INLET AND PIPE PROTECTION	EACH	26	26								
28100109	STONE RIPRAP, CLASS A5	SQ YD	46	46								
28200200	FILTER FABRIC	SQ YD	46	46								

- DENOTES SPECIALTY ITEM
- ROADWAY - 80% FEDERAL 20% LOCAL
- RETAINING WALLS - 80% FEDERAL 20% LOCAL
- NON-PARTICIPATING - 100% LOCAL

NO.	DATE	REVISION	BY

WILL COUNTY DEPARTMENT OF HIGHWAYS
 PLAINFIELD-NAPERVILLE ROAD (C.H. 14)
 ROADWAY RECONSTRUCTION
 SUMMARY OF QUANTITIES

McDonough Associates Inc.
 Engineers/Architects
 DESIGNED BY: N.J.L.
 CHECKED BY: R.E.
 DRAWN BY: R.E.
 SCALE: N.T.S.

SG1