

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2545	98-00036-19-PP	WILL	147	12
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		


CONTRACT NO. 83896

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1	RETAINING WALLS	TRAFFIC SIGNALS 1	TRAFFIC SIGNALS 2	CONSTRUCTION TYPE CODE			NON-PARTICIPATING	
								BOUGHTON RD	104TH ST	BIKE TRAIL	BOLINGBROOK	
				I000-2A	Y007	Y031-1F	Y031-1F	Y046				
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1				
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	5					5				
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1						
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1						
* 89502380	REMOVE EXISTING HANDHOLE	EACH	7			7						
* 89502500	REMOVE TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1				
* A2000620	TREE, ACER PLATANOIDES (NORWAY MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8								8	
* A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	64								64	
* A2004420	TREE, GINKGO BILOBA (GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8								8	
* A2004620	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9								9	
* A2008820	TREE, ULMUS CARPINIFOLIA (HOMESTEAD ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8								8	
* B2005616	TREE, PYRUS CALLERYANA BRADFORD (BRAD FORD CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	8								8	
X0301394	REMOVE STORM SEWER PLUG	EACH	57	57								
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	24	24								
X0322643	STORM SEWER (WATER MAIN REQUIREMENTS) SPAN 68, RISE 43	FOOT	24	24								
* X0323153	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 IC (GREEN)	FOOT	954			450	504					
* X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	12	12								
51202305	DRIVING PILES	FOOT	7183	7183								
X0325560	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER	EACH	12	12								
X0712400	TEMPORARY PAVEMENT	SQ YD	14483	14483								
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	9	9								
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2								
X4023000	TEMPORARY ACCESS (ROAD)	EACH	7	7								
* X8050015	SERVICE INSTALLATION POLE MOUNTED	EACH	1					1				
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1166			360	806					
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	72217	72217								

• DENOTES SPECIALTY ITEM
 ** ROADWAY - 80% FEDERAL 20% LOCAL
 RETAINING WALLS - 80% FEDERAL 20% LOCAL
 NON-PARTICIPATING - 100% LOCAL

NO.	DATE	REVISION	BY

WILL COUNTY DEPARTMENT OF HIGHWAYS
 PLAINFIELD-NAPERVILLE ROAD (C.H. 14)
 ROADWAY RECONSTRUCTION
 SUMMARY OF QUANTITIES


 McDonough Associates Inc.
 Engineers/Architects

DESIGNED BY: N.J.L.
 CHECKED BY: R.E.
 DRAWN BY: R.E.

SCALE: N.T.S.