

TREE REMOVAL 6 TO 15 UNITS	
LOCATION	UNITS
LT 37.495 STA. 44+84.263	14
LT 36.839 STA. 44+86.104	14
LT 38.369 STA. 44+94.397	8
LT 38.369 STA. 44+94.397	8
LT 37.308 STA. 44+98.902	8
LT 37.308 STA. 44+98.902	8
LT 37.308 STA. 44+98.902	8
LT 38.324 STA. 45+01.949	8
LT 38.324 STA. 45+01.949	8
LT 38.23 STA. 45+05.128	12
LT 38.009 STA. 45+18.267	6
LT 38.527 STA. 45+19.218	8
LT 38.749 STA. 45+25.059	6
LT 39.212 STA. 45+36.567	8
LT 38.687 STA. 45+38.861	7
LT 39.096 STA. 45+43.850	10
LT 36.793 STA. 45+80.821	12
LT 39.363 STA. 45+92.785	12
LT 42.218 STA. 45+94.370	12
LT 39.565 STA. 45+99.014	14
LT 37.718 STA. 46+04.906	10
RT 37.087 STA. 46+14.144	12
LT 42.293 STA. 46+32.711	8
LT 42.568 STA. 46+38.366	10
LT 42.303 STA. 46+40.898	12
LT 41.726 STA. 46+43.064	12
LT 42.734 STA. 46+66.054	8
LT 42.734 STA. 46+66.054	8
LT 41.986 STA. 46+73.406	10
LT 41.986 STA. 46+73.406	10
LT 41.133 STA. 46+89.538	14
LT 41.14 STA. 46+96.562	8
LT 45.64 STA. 47+21.688	6
LT 45.509 STA. 47+38.587	10
LT 45.367 STA. 47+39.890	6
LT 45.245 STA. 47+57.174	12
LT 46.371 STA. 47+61.604	12
LT 45.271 STA. 47+81.477	10
LT 45.947 STA. 48+18.327	8
LT 45.947 STA. 48+18.327	8
LT 45.265 STA. 48+25.642	8
RT 38.26 STA. 48+55.601	6
RT 38.26 STA. 48+55.601	6
RT 37.355 STA. 48+65.645	6
LT 35.752 STA. 48+68.679	8
RT 36.81 STA. 48+75.401	8
RT 53.258 STA. 53+34.692	14
RT 52.298 STA. 53+37.100	10
RT 53.119 STA. 53+39.602	8
RT 53.811 STA. 53+41.848	8
RT 54.352 STA. 53+47.237	6
RT 55.571 STA. 53+47.722	6
RT 57.983 STA. 53+65.503	12
RT 54.944 STA. 53+68.998	6
RT 56.442 STA. 53+78.048	12
RT 57.156 STA. 53+86.837	10
TOTAL	519

CULVERT SCHEDULE									
LOCATION	EXIST. SIZE	PIPE UNDERDRAINS	PRECAST CONCRETE BOX CULVERT	PRECAST CONCRETE BOX CULVERT	BOX CULVERT END SECTIONS	PRECAST CONCRETE END SECTIONS	PRECAST CONCRETE DROP BOX	PIPE CULVERT REMOVAL	ABANDON EXISTING CULVERT
		6"	6' X 6' (M273)	8' X 3' (M273)	C-1 6' X 6'	8' X 3' WITH GRATING	8' X 3' X 10' WITH GRATING	FOOT	CLSM
		FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	CU YD
MAINLINE									
RT. STA. 35+00 TO RT. STA. 39+00		6"	400						
AR STA 39+00		7'X3' BOX							53.1
AR STA 39+20		8'X3' BOX		107		1	1		
AR STA 60+32.20		48" CMP		60	2			68	
TOTAL			400	60	107	2	1	1	68

CLASS D PATCHES, TYPE IV 15 INCH		
LOCATION	PIPE SIZE	TYPE IV
MAINLINE		50 YD
STA. 39+20	8'x3' BOX	83
TOTAL		83

SEEDING SCHEDULE							
LOCATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING CLASS 2A SPECIAL	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 1
	LBS*	ACRES	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE	2 TONS/ACRE	2 TONS/ACRE
LT STA 34+12.04 TO LT STA 40+28.00	202	0.50	45	45	45	1.00	1.00
RT STA 34+12.04 TO RT STA 44+34.00	199	0.50	45	45	45	1.00	1.00
LT STA 40+28.00 TO LT STA 50+00.00	246	0.61	55	55	55	1.22	1.22
RT STA 44+34.00 TO RT STA 50+00.00	134	0.34	31	31	31	0.68	0.68
LT STA 50+00.00 TO LT STA 64+88.11	458	1.15	104	104	104	2.30	2.30
LT STA 50+00.00 TO LT STA 58+50.00	298	0.74	67	67	67	1.48	1.48
LT STA 58+50.00 TO LT STA 64+11.00	243	0.61	55	55	55	1.22	1.22
TOTAL	1780	4.45	402	402	402	8.90	8.90

\* 100 LBS/ACRE FOR 4 APPLICATIONS  
FERTILIZER, LIMESTONE AND MULCH QUANTITIES ARE FOR INFORMATION ONLY

TREE REMOVAL OVER 15 UNITS	
LOCATION	UNITS
LT 39.436 STA. 45+52.806	16
LT 38.399 STA. 45+57.807	18
LT 38.962 STA. 45+67.426	20
LT 43.173 STA. 46+58.514	24
LT 42.322 STA. 46+63.633	16
LT 45.255 STA. 47+95.844	20
RT 36.892 STA. 47+96.136	18
LT 45.386 STA. 48+49.690	30
RT 30.206 STA. 50+67.903	16
RT 32.507 STA. 50+89.818	16
RT 51.953 STA. 53+52.948	16
RT 51.528 STA. 53+54.982	16
RT 56.807 STA. 53+81.781	16
RT 57.461 STA. 53+85.159	16
RT 58.777 STA. 53+95.159	18
TOTAL	276

STONE RIPRAP SCHEDULE				
LOCATION	AREA	RIPRAP CLASS A4	FILTER FABRIC	
		TON	SQ YD	
CULVERTS				
RT STA 39+40	20 X 10 X 1.33	17	22.00	
RT STA 60+32	10 X 10 X 1.33	9	11.00	
SUBTOTAL CULVERTS		26.00	33.00	
DITCHES				
	DITCH DEPTH	DITCH BOTTOM		
LT STA 34+12 TO LT STA. 34+50	2.00	5.00	77	108
LT STA 34+50 TO LT STA. 36+60	2.00	5.00	101	142
LT STA 35+00 TO LT STA. 35+50	2.00	5.00	101	142
LT STA 35+50 TO LT STA. 36+00	2.00	5.00	101	142
LT STA 36+00 TO LT STA. 36+50	2.00	5.00	101	142
LT STA 36+50 TO LT STA. 37+00	2.00	5.00	101	142
LT STA 37+00 TO LT STA. 37+50	2.00	5.00	101	142
LT STA 37+50 TO LT STA. 38+00	2.00	5.00	85	120
LT STA 38+00 TO LT STA. 38+50	2.00	5.00	85	120
LT STA 38+50 TO LT STA. 39+00	2.00	5.00	85	120
LT STA 39+00 TO LT STA. 39+50	2.00	5.00	85	120
SUBTOTAL DITCHES		1,023	1,440	
TOTAL		1,049	1,473	

**HAMPTON, LENZINI & RENWICK, INC.**  
CIVIL & STRUCTURAL ENGINEERS

**HLR** 3085 STEVENSON DRIVE, SUITE 201  
SPRINGFIELD, ILLINOIS 62703  
(217) 546-3400

ELGIN • SPRINGFIELD • DUQUOIN

PROJECT NUMBER: 12-06-0030-1 DATE: 05/04/06  
DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: W.J.S.

QUANTITY SCHEDULES  
SECTION 96-00044-00-BR  
FOX RIVER DRIVE  
KENDALL COUNTY