

COUNTY	SECTION	COUNTY HIGHWAY	SHEET NO.
LASALLE	07-00264-01-WR	CH 8	5 of 8

CONTRACT NO. 87344

GUARDRAIL SCHEDULE

STATION	SIDE	SPBGR (FOOT)	TBT, TY 1 (EACH)	VERTICAL ADJUSTMENT		GUARDRAIL REFLECTORS (EACH)	TERM MKR, DIR APPLIED (EACH)
				GUARDRAIL (FOOT)	TBT, TY 1 (EACH)		
33+49 - 33+74	LT				1	1	1
33+74 - 33+86.5	LT			12.5			
34+04.5 - 34+42	LT			37.5		1	
34+42 - 34+67	LT				1	1	1
33+23 - 33+48	RT				1	1	1
33+48 - 33+85.5	RT			37.5		1	
34+04.5 - 34+17	RT			12.5			
34+17 - 34+42	RT				1	1	1
223+42 - 223+92	LT		1			1	1
223+92 - 224+04.5	LT	12.5				1	
224+04.5 - 224+54.5	LT		1			1	1
223+42 - 223+92	RT		1			1	1
223+92 - 224+04.5	RT	12.5				1	
224+04.5 - 224+54.5	RT		1			1	1
TOTAL		25	4	100	4	12	8

INLET & PIPE PROTECTION

Station	Type	Side	Quantity
15+80	Cross road	CL	2
26+21	Field Entrance	Rt.	1
41+47	Cross road	CL	2
60+92	Cross road	CL	2
73+90	Cross road	CL	2
87+40	Cross road	CL	2
94+35	Cross road	Lt Only	1
101+08	Cross road	Lt Only	1
112+72	Cross road	CL	2
163+50	Cross road	Lt Only	1
183+40	Cross road	CL	2
223+90	Cross road	CL	2
TOTAL EACH			20

CULVERT EXTENSIONS

STATION	SIDE	RC PIPE		METAL END SECTIONS		CULVERT REMOVAL FOOT
		CULVERT	END SEC	18"	24"	
		36"	36"	EACH	EACH	
52+34	LT & RT			2		2
60+95	LT & RT	6 LT	2			
115+91	LT			1		
183+12	LT & RT				2	2
TOTAL		6	2	3	2	4

TEMPORARY DITCH CHECKS

Station	Side	Quantity
10+00	LT - RT	2
18+50	LT - RT	2
33+00	LT - RT	2
34+50	LT - RT	2
65+63	LT - RT	2
76+00	LT - RT	2
79+00	LT	2
101+00	RT	1
101+16	RT	1
110+00	LT - RT	2
134+50	RT	1
135+00	LT	1
135+29	RT	1
147+80	LT - RT	2
149+00	LT - RT	2
151+75	LT - RT	2
187+00	LT - RT	2
222+25	LT - RT	2
226+00	LT - RT	2
235+36	RT	1
236+15	LT	1
TOTAL EACH		35

AGGREGATE SHOULDERS, TY-B

STATION	SIDE	LENGTH	3'	1'
10+00 - 171+03	LT	16,103	5368	
180+18 - 236+69	LT	5,651	1884	
171+03 - 180+18	LT	915		102
10+00 - 62+40	RT	5240	1747	
62+40 - 67+72	RT	532		59
67+72 - 109+10	RT	4138	1379	
109+10 - 114+09	RT	499		55
114+09 - 178+60	RT	6451	2150	
178+60 - 188+43	RT	983		109
188+43 - 236+69	RT	4826	1609	
SUB-TOTAL			14136	325
TOTAL SQ.YDS.				14462

NOTE: AGGREGATE SHOULDER, TYPE B TO BE PLACED ALONG EDGES OF PRIVATE ENTRANCES, SIDE ROADS AND MAILBOX TURNOUTS.

HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT

STATION	SIDE	SQ.YDS.
10+00	CL	73.3
78+83	LT	42.2
78+83	RT	46.7
172+61	RT	44.4
177+70	RT	44.4
180+62	LT	44.4
186+77	LT	44.4
235+44	RT	46.7
236+69	CL	73.3
TOTAL		460

QUANTITY SCHEDULES