

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TR 229-A	06-00000-00-SP	TAZEWELL	5	2
FED. ROAD DIST. NO.	ILLINOIS PROJECT		CONTRACT NO: 89470	

**SUMMARY OF QUANTITIES**

		CONSTRUCTION TYPE CODE:	
CODE	ITEM	UNIT	QUANTITY
* X6310187	TRAFFIC BARRIER TERMINAL, TYPE 6A MODIFIED	EACH	1
* X6320100	GUARDRAIL REMOVAL, SPECIAL	FOOT	92
20400800	FURNISHED EXCAVATION	CU YD	80
40600100	BITUMINOUS MATERIALS PRIME COAT	GALLON	125
40600300	AGGREGATE PRIME COAT	TON	2
40603305	HOT-MIX ASPHALT SURFACE COURSE MIX C N30	TON	145
* 40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	700
X0325701	STEEL RAILING, TYPE 2399	FOOT	116
63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	225
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3
63100167	TRAFFIC BARRIER TERMINAL TYPE 1 SPL TAN	EACH	3
* 67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION SPECIAL	L SUM	1
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	19
78200400	GUARDRAIL REFLECTORS	EACH	8
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3

\* SEE SPECIAL PROVISION

**GENERAL NOTES**

ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE STATE OF ILLINOIS "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007," THESE PLANS AND THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS.

THE LOCATIONS OF EXISTING GAS MAINS, ELECTRIC POWER LINES, TELEPHONE LINES AND OTHER UTILITIES AS SHOWN ON THE PLANS ARE BASED ON CAREFUL FIELD INVESTIGATION AND THE BEST INFORMATION AVAILABLE, BUT THE LOCATIONS ARE NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THEIR EXACT LOCATION FROM THE INDIVIDUAL UTILITY COMPANIES AND BY FIELD INSPECTION.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

HOT-MIX ASPHALT 112 LB / IN / SQ YD  
 BITUMINOUS MATERIALS PRIME COAT 0.1 GAL / SQ YD

LOCATION	EACH
RT. STA. 9+25.7 TO RT. STA. 9+69.4	1
LT. STA. 9+28.7 TO LT. STA. 9+72.4	1
LT. STA. 10+30.4 TO LT. STA. 10+74.0	1
TOTAL	3

LOCATION	EACH
RT. STA. 10+27.4 TO RT. STA. 10+68	1
TOTAL	1

LOCATION	CU YD
RT. STA. 7+15 TO RT. STA. 8+00	20
LT. STA. 8+55 TO LT. STA. 9+30	35
LT. STA. 11+70 TO LT. STA. 12+55	25
TOTAL	80

LOCATION	FOOT
RT. STA. 8+00.7 TO RT. STA. 9+25.7	125
LT. STA. 10+71.0 TO LT. STA. 11+71.0	100
TOTAL	225

LOCATION	EACH
RT. STA. 10+68 TO RT. STA. 10+68	1
TOTAL	1

LOCATION	EACH
RT. STA. 7+50.7 TO RT. STA. 8+00.7	1
LT. STA. 8+78.7 TO LT. STA. 9+28.7	1
LT. STA. 11+71.0 TO LT. STA. 12+21.0	1
TOTAL	3

LOCATION	FOOT
NORTHWEST WINGWALL	24
SOUTHWEST WINGWALL	24
NORTHEAST WINGWALL	20
SOUTHEAST WINGWALL	24
TOTAL	92

SUMMARY OF QUANTITIES  
 SPRINGTOWN RD.  
 SEC. 06-00000-00-SP  
 TAZEWELL COUNTY