

SUMMARY OF QUANTITIES

RTE.	PROJECT NO.	COUNTY	TOTAL SHEETS
05-00218-00-PV	VERMILION	57	02
STA. 00+00.00 TO STA. 335+39.10			
*F.A.P. 729 & F.A.U. 6999 CONTRACT NO. 91367			

CODE NUMBER	ITEM	UNIT	OTHER PRINCIPAL ARTERIAL FEDERAL STATE L20 CITY	070 EASTGATE DRIVE 0% FEDERAL 100% CITY	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	2002	-	2002
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1150	-	1150
25000340	SEEDING, CLASS 6A	ACRE	0.2	-	0.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	-	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	-	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	-	18
25100115	MULCH, METHOD 2	ACRE	0.2	-	0.2
35101600	AGGREGATE BASE COURSE, TYPE B 4'	SQ YD	1777	-	1777
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10'	SQ YD	357	-	357
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10'	SQ YD	309	-	309
35501300	HOT-MIX ASPHALT BASE COURSE, 4'	SQ YD	959	-	959
35650700	BASE COURSE WIDENING	SQ YD	151	-	151
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	10	-	10
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9297	1980	11277
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	-	674	674
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2619	-	2619
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	899	-	899
40600895	CONSTRUCTING TEST STRIP	EACH	2	-	2
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	306.8	-	306.8
40600990	TEMPORARY RAMP	SQ YD	373	86	459
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	175	-	175
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	192	-	192
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	-	1617	1617
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	TON	3972	-	3972
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N90	TON	993	-	993
40701831	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 7 1/2'	SQ YD	20500	-	20500
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	29.3	-	29.3
44000100	PAVEMENT REMOVAL	SQ YD	4	-	4
*44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2'	SQ YD	15613	9648	25261
*44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2'	SQ YD	-	1067	1067
*44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2'	SQ YD	-	7311	7311

CODE NUMBER	ITEM	UNIT	OTHER PRINCIPAL ARTERIAL FEDERAL STATE CITY	EASTGATE DRIVE 0% FEDERAL 100% CITY	TOTAL QUANTITY
*44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3'	SQ YD	7623	-	7623
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	97.0	-	97
*44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1393	-	1393
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	2784.2	-	2784.2
*44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	11846.6	-	11846.6
*44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	35	-	35
*44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	49	-	49
*44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	8	-	8
*44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	21	-	21
*44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	23	-	23
*44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	46	-	46
*44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	10	-	10
*44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	75	-	75
*44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	19	-	19
*44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	-	96	96
*44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	1880	-	1880
44213200	SAW CUTS	FOOT	1924	-	1924
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	21932	-	21932
45200300	JOINT OR CRACK FILLING	POUND	8773	-	8773
48101500	AGGREGATE SHOULDERS, TYPE B 6'	SQ YD	6281	-	6281
48203011	HOT-MIX ASPHALT SHOULDERS, 3 1/2'	SQ YD	6220	-	6220
56109210	WATER VALVES TO BE ADJUSTED	EACH	1	-	1
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	26	-	26
*60107600	PIPE UNDERDRAINS 4'	FOOT	11050	-	11050
60108100	PIPE UNDERDRAINS 4' (SPECIAL)	FOOT	182	-	182
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	-	1	1

\*INDICATES SPECIAL PROVISION

DEPARTMENT OF ENGINEERING  
 DANVILLE, IL. R. DAVID SCHNELLE, CITY ENGINEER  
 LYNCH ROAD IMPROVEMENT  
 SUMMARY OF QUANTITIES I

SCALE: 1:50  
 DATE: 3/12/2007

DRAWN BY: RDS  
 CHECKED BY: JPH

X:\Projects\Civil\Current\95010215-Lynch Spur\Civil\DMN\S000001.dgn

