

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE					
				1000-2A		X071-2A		X081-2A	
				URBAN	RURAL	URBAN	RURAL	URBAN	RURAL
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1933	578	1355				
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2446	III	1335				
2020010	EARTH EXCAVATION	CU YD	81610	13095	68515				
2020120	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2185		2185				
2030010	CHANNEL EXCAVATION	CU YD	1425		1425				
2070040	POROUS GRANULAR EMBANKMENT (SPECIAL) ³ [▲]	CU YD	566			154	412		
2080010	TRENCH BACKFILL	CU YD	345	18	327				
* 2101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	31000	3115	27885				
2140010	GRADING AND SHAPING DITCHES	FOOT	266		266				
* 25000210	SEEDING, CLASS 2A	ACRE	47.25	5.0	42.25				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4253	450	3803				
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4253	450	3803				
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4253	450	3803				
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	94.5	10.0	84.5				
* 2510015	MULCH, METHOD 2	ACRE	47.25	5.0	42.25				
* 25100630	EROSION CONTROL BLANKET	SQ YD	1335	470	865				
* 28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	120		120				
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4725	500	4225				
* 28000300	TEMPORARY DITCH CHECKS	EACH	100	46	54				
* 28000400	PERIMETER EROSION BARRIER	FOOT	1110	710	400				
28000500	INLET AND PIPE PROTECTION	EACH	58	11	47				
28100107	STONE RIPRAP, CLASS A4	SQ YD	2937	896	580	1032	429		
28200200	FILTER FABRIC	SQ YD	3581	1299	821	1032	429		
28400100	GABIONS	CU YD	325	202	123				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	8257		8257				
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	316	114	202				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	882	292	590				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2838		2838				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	10772	754	10,018				
35650700	BASE COURSE WIDENING	SQ YD	1615	519	1096				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	939	262	677				
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1430		1430				
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	3889		3889				
40300500	COVER COAT AGGREGATE	TON	71		71				
40300600	SEAL COAT AGGREGATE	TON	34		34				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	37106	2627	34479				

F BRP
 80% FEDERAL
 20% STATE
 CONSTRUCTION TYPE CODE

F.A.P. RTE. 95 SECTION * COUNTY EFFINGHAM TOTAL SHEETS 409 SHEET NO. 4
 STA. TO STA.
 FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT
 *(6,7)Y, RS-1, 6B-1, 7B-1 & 7BR-2
 CONTRACT NO. 94356
 80% FED. / 20% STATE

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE					
				1000-2A		X071-2A		X081-2A	
				URBAN	RURAL	URBAN	RURAL	URBAN	RURAL
40600300	AGGREGATE (PRIME COAT)	TON	687	51	636				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	6556	431	6125				
40600895	CONSTRUCTING TEST STRIP	EACH	1		1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	513	87	426				
40600990	TEMPORARY RAMP	SQ YD	585	91	494				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	8019	1213	6806				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1123	74	1039				
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	80		80				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	14396	923	13473				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	505	156	349				
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	999	178	821				
4200165	BRIDGE APPROACH PAVEMENT	SQ YD	548	274	274				
42001200	PAVEMENT FABRIC	SQ YD	999	178	821				
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	108	54	54				
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	160		160				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	408	204	204				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	855		855				
44000100	PAVEMENT REMOVAL	SQ YD	2841	599	2242				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1136		1136				
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	151041	9084	141957				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1692	104	1588				
44000400	GUTTER REMOVAL	FOOT	4071	2070	2001				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	758	758					
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	654		654				
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	654		654				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	135	108	27				
44002600	GUTTER OUTLET REMOVAL	FOOT	165	93	72				
44002805	ISLAND REMOVAL	SQ FT	115		115				
44004250	PAVED SHOULDER REMOVAL	SQ YD	1615		1615				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	5426		5426				

URBAN SECTION STA. 142+00.00 TO STA. 180+60.00
 RURAL SECTION STA. 180+60.00 TO STA. 689+81.63
 * DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 1 OF 4
 DRAWN BY ASB
 CHECKED BY SJK
 DATE 6/02