F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	EFFINGHAM	382	17
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

*(6,7)Y, RS-1, 6B-1, 7B-1 & 7BR-2

CONTRACT NO. 94356

ENTRANCE CULVERT SCHEDULE

PROPOSED MATERIAL	TYPE	SIDE/ STATION	EXISTING CULVERT SIZE	PIPE CULVERT, CLASS D, TYPE I 12" FT	15" FT	15" EQUIV ROUND FT	18" FT	18" EQUIV ROUND FT	21" FT	24" FT	24" EQUIV ROUND FT	36" EQUIV ROUND FT	TYPE II 15" FT	END SECTIONS 15" EACH	15" EQUIV ROUND EACH	18" EACH	18" EQUIV ROUND EACH	21" EACH	24" EACH	24" EQUIV ROUND EACH	36" EQUIV ROUND EACH
AGG	FE	LT/150+34.63	N/A		46									2							
AGG	PE	RT/151+65.27	N/A							45									2		
AGG	PE	LT/156+73.10	N/A		49									2							
AGG	PE	LT/165+73.05	N/A		34									2							
AGG	PE	RT/167+14.84	12"Ø		33									2							
AGG	PE	LT/167+55.12	15"Ø			32									2						
AGG	PE	LT/169+10.07	15"Ø			31									2						
AGG	PE	RT/169+48.15	15"Ø		42									2							
AGG	PE	LT/170+85.52	15"Ø		56									2							
AGG	PE	LT/171+36.03	15"Ø		57									1							
AGG	PE	LT/173+30.61	15"Ø			31									2						
AGG	CE	RT/173+43.41	15"Ø		56									1							
CONC	PE	LT/177+48.07	12"Ø										110	2							
AGG	PE	RT/179+49.90	N/A		30									2							
CONC	CE	RT/194+25.72	N/A										79	2							
AGG	FE	LT/194+26.00	N/A										60	2							
AGG	PE	LT/232+24.82	15"Ø		46									2							
BIT	CE	LT/245+66.63	21"Ø						96									2			
AGG	PE	LT/255+18.21	15"Ø			43									2						
AGG	FE	LT/260+98.61	15"Ø		37									2							
AGG	FE	LT/271+04.65	24"Ø								30									2	
AGG	PE	RT/287+77.81	15"Ø		55									2							
AGG	FE	LT/290+92.71	15"Ø		42									2							
EARTH	FE	RT/291+08.92	15"Ø		44									2							
EARTH	FE	LT/305+71.85	6'x3'									31									2
AGG	PE	LT/334+26.06	15"Ø		53									2							
AGG	PE	LT/338+16.38	12"Ø			42									2						
AGG	FE	RT/364+87.40	12"Ø			31									2						
AGG	FE	LT/364+88.74	12"Ø		35									2							
AGG	PE	LT/395+64.47	12"Ø		40									2							
AGG	FE	RT/395+68.60	15"Ø		38									2							
EARTH	FE	LT/471+00.00	15"Ø		42									2							
EARTH	FE	RT/470+73.85	15"Ø		45									2							
AGG	FE	LT/490+69.66	15"Ø			30									2						
AGG	PE	RT/491+01.27	15"Ø		33									2							
BIT	FE	RT/512+27.00	N/A							32									2		
AGG	FE	RT/554+22.56	N/A		51									2							
EARTH	FE	LT/554+24.04	N/A		45									2							
EARTH	FE	LT/578+96.90	18"Ø					30									2				
EARTH	FE	RT/578+97.21	18"Ø					30									2				
AGG	PE	LT/594+26.38	12"Ø			30									2						
EARTH	FE	RT/594+48.72	18"Ø					30									2				
CONC	CE	LT/605+50.93	15"Ø										77	2							
AGG	CE	LT/645+03.33	15"Ø		56									2							
AGG	PE	LT/645+94.27	15"Ø					42									2				
AGG	CE	RT/665+95.32	N/A			43									2						
BIT	CE	RT/675+22.53	15"Ø		61									2							
BIT	CE	RT/680+90.28	18"Ø				73									2					
AGG	PE	LT/101+99.22 1650TH ST/LANE	12"Ø	30																	
AGG	FE	LT/21+75.61 1750TH ST	N/A		30									2							
AGG	FE	LT/25+10.00 1775TH ST	N/A		30									2							
AGG	FE	RT/82+73.00 1100TH AVE	N/A		30									2							
AGG	FE	RT/58+90.00 2200TH ST	N/A			30									2						
			TOTAL	30	1216	343	73	132	96	77	30	31	326	62	20	2	8	2	4	2	2

PUBLIC ROAD CULVERT SCHEDULE

PUBLIC ROAD/ SIDE/ STATION	EXISTING CULVERT SIZE	PIPE CULVERT, CLASS D, TYPE I 15" FT	15" EQUIV ROUND FT	18" FT	18" ROUND FT	21" FT	24" FT	24" EQUIV ROUND FT	27" EQUIV ROUND FT	36" EQUIV ROUND FT	END SECTIONS 15" EACH	15" EQUIV ROUND EACH	18" EACH	18" ROUND EACH	21" EACH	24" EACH	24" EQUIV ROUND EACH	27" EQUIV ROUND EACH	36" EQUIV ROUND EACH
GOBBLER SOUTH RT/160+04.70	N/A		73									2							
1525TH ST LT/180+32.40	N/A		70									2							
TR 109 RT/200+95.86	N/A	41									2								
1600TH ST LT/221+24.83	2'x1.5' BOX								43										2
1650TH ST LT/247+78.42	2'x1.5' BOX							46									2		
1700TH ST LT/274+32.00	2'x2' BOX								47									2	
1750TH ST LT/301+09.14	N/A						51									2			
1800TH ST LT/327+49.59	2'x1.5' BOX						46									2			
1800TH ST RT/327+44.85	2'x1.5' BOX							63									2		
1900TH ST LT/372+50.06	2'x1.5' BOX							62									2		
1900TH ST RT/373+17.89	2'x1.5' BOX			97									2						
1250TH AVE LT/385+20.12	N/A				59									2					
1250TH AVE RT/384+61.50	18"Ø	56									2								
1950TH ST LT/408+77.11	N/A							81									2		
1950TH ST RT/409+52.36	24"Ø						71									2			
1950TH ST RT/409+55.14	18"Ø			73									2						
2100TH ST LT/508+29.93	2'x2' BOX			66									2						
2100TH ST RT/508+51.96	21"Ø					98									2				
1100TH AVE 51+29.85	N/A						41									2			
1100TH AVE LT/514+52.88	2'x2' BOX							66									2		
2200TH ST LT/569+82.15	2'x1.5' BOX						54									2			
2200TH ST RT/570+21.82	2'x1.5' BOX						62									2			
NORB AVE LT/591+95.31	15"Ø	133									2								
TOTAL		230	143	236	59	98	325	318	47	43	6	4	6	2	2	12	10	2	2

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ENTRANCE PIPE CULVERT SCHEDULE

DATE 11/01

DRAWN BY MLO

CHECKED BY SJK

DSN-SPEC
DATE

Revised 5/11/07