

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	*	CRAWFORD	37	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* (102Z, 108Z, 1018)RS-2				

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			801.FED. 201.STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
20400800	FURNISHED EXCAVATION	CU YD	60.4	60.4		
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.07	0.07		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	182	182		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16152	16152		
40600300	AGGREGATE (PRIME COAT)	TON	322	322		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	293	293		
40600990	TEMPORARY RAMP	SQ YD	73	73		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	13569	13569		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	25	25		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	83225	83225		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	78005	78005		
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	556	556		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	1274	1274		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	216	216		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	202	202		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2459	2459		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	175	175		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	60	60		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19836	19836		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	197,062	197,062		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	67892	67892		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	57.6	57.6		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19109	19109		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	33	33		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	177952	177952		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	964	964		

SUMMARY OF QUANTITIES			801.FED. 201.STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
NP X0320882	GUTTERS TO BE CLEANED	FOOT	11107	11107		
<del>70025500</del>	<del>FURNISHING AND INSTALLING PROPERTY MARKERS</del>	<del>EACH</del>	<del>1</del>	<del>1</del>		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

PLOT DATE = #DATE#  
FILE NAME = #FILE#  
PLOT SCALE = #SCALE#  
USER NAME = #USER#

NP=NON-PARTICIPATING  
\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.  
DATE

DRAWN BY  
CHECKED BY