

# SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	123RS-3 122RS-4	RICHLAND	27	3
FED. ROAD DIST. NO. 7		ALWAYS	FED. AID PROJECT NO.	

CONTRACT NO. 94911

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		100% STATE 1000	
				RURAL	URBAN
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	368	311	57
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12071	11078	993
40600300	AGGREGATE (PRIME COAT)	TON	242	222	20
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5064	4646	418
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	750	600	150
40600990	TEMPORARY RAMP	SQ YD	209	167	42
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	132	132	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10134	9299	835
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	86	76	10
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	4331		4331
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	115577	110177	5400
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	2206	2078	128
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	160	160	
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	333	333	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2466	2391	75
66700095	PERMANENT SURVEY MARKERS	EACH	3	3	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14747	13293	1454
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	141		141
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	88687	80551	8136
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	419		419
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	189		189
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	77		77
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1228	1107	121
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	141		141
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2622		2622

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		100% STATE 1000	
				RURAL	URBAN
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	419		419
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	189		189
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	77		77
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	86065	80551	5514
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	491	416	75
78300100	PAVEMENT MARKING REMOVAL	SQ FT	73		73
81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	FOOT	244		244
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	128		128
81500100	GULFBOX JUNCTION	EACH	1		1
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	372		372
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	480		480
87900200	DRILL EXISTING HANDHOLE	EACH	13		13
88500100	INDUCTIVE LOOP DETECTOR	EACH	1		1
88600100	DETECTOR LOOP, TYPE I	FOOT	760		760

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.    DRAWN BY  
DATE            HORIZ.        CHECKED BY