F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

WATER AND SANITARY SEWER MAIN

LOCATION	SELECT GRANULAR BACKFILL	CLASS C PATCHES, TYPE II, 8 INCH	CLASS C PATCHES, TYPE IV, 8 INCH	CLASS C PATCHES, TYPE II, 15 INCH	CLASS C PATCHES, TYPE III, 15 INCH	CLASS C PATCHES, TYPE IV, 15 INCH	POTABLE WATER: PVC WATER MAIN & FITTINGS		CAP & BLOCK					Water Valve		Water Service Line Recon.	Tapping Sleeves and Valves		CURB STOP AND BOX	FIRE HYDRANT W/AUXILIARY VALVE & VALVE BOX	FIRE HYDRANT TO BE REMOVED	SANITARY SEWER: PVC SANITARY SEWER MAIN	SANITARY SEWER REMOVAL REPLACEMENT	SANITARY SEWER REMOVAL REPLACEMENT	CIPP LINER FOR SANITARY SEWER MAIN					RECONNECT SANITARY SERVICE 6"	MANHOLE SANITARY 4'-DIAMETER TYPE 1 FRAME CLOSED LID	SANITARY MANHOLE REMOVE & REPLACE	SANITARY MANHOLES TO BE ADJUSTED	SANITARY SEWER TO BE ABANDONED
							6"	8"	1"	2"	3"	6"	8"	6"	8"		4"	6"				8"	8"	10"	6"	8"	10"	12"	15"				
	CU. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
LT. STA. 98+00 TO RT. STA. 4+00 - GALLATIN	339					217	0	210	0	0	0	1	0	1	2	3	0	1	3	0	0	0	270	0	0	145	0	0	0	5	1	1	0	0
LT. STA. 4+00 TO RT. STA. 10+00 - GALLATIN	576					367	0	600	0	0	1	0	0	0	2	30	0	0	30	1	1	269	0	0	0	349	0	0	0	17	2	1	3	255
LT. STA.10+00 TO RT. STA. 16+05 - GALLATIN	1639					552	0	605	0	0	0	0	0	0	6	17	0	0	17	2	2	70	475	0	0	0	0	0	0	11	2	1	0	100
LT. STA. 16+05 TO RT. STA. 18+26.50 - GALLATIN	660					210	0	221	0	0	0	1	0	1	0	5	0	1	5	1	1	0	200	0	0	0	0	0	0	3	2	0	0	37
SEVENTH STREET	1006		58			434	0	583	0	1	0	1	0	1	2	6	0	1	6	2	0	0	524	0	0	0	0	0	0	8	2	0	0	321
SIXTH STREET	204	7	126	10			0	300	0	0	0	0	0	0	1	3	0	0	3	1	0	0	0	0	0	0	0	0	265	0	2	0	0	0
ALLEY BETWEEN 5TH AND 6TH	197		70				0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	130	0	0	0	0	0	0	2	2	0	0	88
FIFTH STREET	455		304			53	0	730	0	0	0	1	1	1	3	6	1	1	6	0	0	80	0	0	0	110	0	0	0	3	1	0	0	589
ALLEY BETWEEN 4TH AND 5TH	197		141		20		278	0	0	0	2	0	0	1	0	8	0	0	8	1	1	0	0	28	0	278	280	0	0	1	2	1	0	359
FOURTH STREET	157		136		28		393	0	1	0	0	0	0	2	0	5	0	1	5	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0
ALLEY BETWEEN 3RD AND 4TH	32	9					0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	280	0	0	0	0	1	0	0	0
JOHNSON STREET	0						0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	391	0	0	0	0	0	0	0
ALLEY BETWEEN 7TH AND 6TH	25	8					0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	187	0	0	0	0	0	1	0	0	0
TOTAL	5487	24	835	10	48	1833	671	3249	1	1	3	4	1	7	16	83	1	5	83	9	5	419	1599	28	187	1162	280	391	265	50	18	4	3	1749

PAVING SCHEDULE

LOCATION	SUBBASE GRANULAR MATERIAL TYPE A, 4"	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	PORTLAND CEMENT CONCRETE BASE COURSE 10"	BITUMINOUS MATERIALS (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL
	SQ. YD.	SQ. YD.	SQ. YD.	(GALLON)	TON	TON	SQ. YD.		SQ. YD.
GALLATIN STREET									
STA. 98+69 TO STA. 98+96	212		180	21		15			176
LT. STA. 98+96 TO LT. STA. 100+65.9									13
RT. STA. 98+96 TO RT. STA. 2+41.9									65
STA. 98+96 TO STA. 2+55.33				184	177	134	290		
STA. 2+55.33 TO STA. 6+55.79				236	194	172	2048		
RT. STA. 2+70 TO RT. STA. 3+34	73	45							
RT. STA. 4+63.8 TO RT. STA. 5+20	55	36							59
RT. STA. 6+00 TO RT. STA. 6+32	33	19							
LT. STA. 6+28 TO LT. STA. 6+38	73	53							
RT. STA. 6+37.8 TO RT. STA. 7+09	159	159							168
STA. 6+55.79 TO STA. 10+57.98				275	282	201	2391		
LT. STA. 6+87 TO LT. STA. 7+07	19	7							
RT. STA. 10+03 TO RT. STA. 10+31	36	21							
LT. STA. 10+24 TO LT. STA. 10+38	31	19							
STA. 10+57.98 TO STA. 14+56.64				273	262	199	2370		
RT. STA. 10+76 TO RT. STA. 10+93	33	20							
LT. STA. 10+86 TO LT. STA. 11+10	27	15							
RT. STA. 14+03 TO RT. STA. 14+28	29	17							
LT. STA. 14+21 TO LT. STA. 14+36	32	20							
STA. 14+56.64 TO STA. 18+28.5				255	205	186	2211	109	
SEVENTH STREET									
STA. 703+70 TO STA. 704+26				32	39	23		240	
STA. 704+67 TO STA. 704+87				8	9	5		61	
SIXTH STREET									
STA. 603+15 TO STA. 604+15	464		407	47		34			503
STA. 604+68 TO STA. 605+32				50	59	35		361	
LT. STA. 604+76.8 TO LT. STA. 605+02.5									25
LT. STA. 605+21 TO LT. STA. 605+32									8
FIFTH STREET									
STA. 503+72 TO STA. 504+14				31	37	23		239	
STA. 504+67 TO STA. 504+98				23	27	17		176	
FOURTH STREET									
STA. 403+85 TO STA. 404+14				20	22	13		156	
STA. 404+68 TO STA. 404+98				25	29	17		188	
TOTAL	1276	431	587	1480	1342	1074	9310	1530	1017

REVISIONS	
NAME	DATE
LWJ	4-13-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY KOJ

CHECKED BY BWC

H.M. & G. NO. 4812

CADD FILE: /4812/sch_4812.dgn
PLOTTED: 5/9/2007