

# SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	05-00187-01-RP	MADISON	79	3
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
			CONTRACT NO. 97288	

## SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	45
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	112
20200100	EARTH EXCAVATION	CU YD	6254
20201400	SUB-BASE GRANULAR MATERIAL, TYPE A	TONS	2279
20800150	TRENCH BACKFILL	CU YD	2332
25000100	SEEDING, CLASS 1	ACRE	0.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63
25100120	MULCH, METHOD 2	TON	1.4
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.7
28000500	INLET AND PIPE PROTECTION	EACH	59
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	11093
30201500	LIME	TON	275
35100100	AGGREGATE BASE COURSE, TYPE A	TON	59
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	8
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	11
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	500
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2229
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1997
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	998
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	37
42001300	PROTECTIVE COAT	SQ YD	5336
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2147
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	164
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	10536
42400800	DETECTABLE WARNINGS	SQ FT	186
44000100	PAVEMENT REMOVAL	SQ YD	45
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1301

## SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
44000400	GUTTER REMOVAL	FOOT	401
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	71
44000600	SIDEWALK REMOVAL	SQ FT	2894
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	18
50105220	PIPE CULVERT REMOVAL	FOOT	557
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	219
550B0120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	35
550B0410	STORM SEWERS, CLASS B, TYPE 2 24"	FOOT	152
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	1138
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	149
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	568
55020100	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	155
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	123
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	825
55100400	STORM SEWER REMOVAL 10"	FOOT	44
55100700	STORM SEWER REMOVAL 15"	FOOT	30
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	19
60242900	INLETS, SPECIAL, TYPE 1	EACH	11
60243000	INLETS, SPECIAL, TYPE 2	EACH	11
60243100	INLETS, SPECIAL, TYPE 3	EACH	12
60243700	INLETS, SPECIAL, TYPE 4	EACH	1
60500040	REMOVING MANHOLES	EACH	1


## SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60500060	REMOVING INLETS	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5563
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	520
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	638
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	720
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	165
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	911
* 72000100	SIGN PANEL - TYPE 1	SQ FT	125
* 72900200	METAL POST - TYPE B	FOOT	176
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	638
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	720
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	165

DATE	
BY	
FINAL SURVEY PLOTTED	
NOTE BOOK TEMPLATE	
AREAS CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEY PLOTTED	
NOTE BOOK TEMPLATE	
AREAS CHECKED	
NO.	

\* SPECIALTY ITEMS

 <b>Juneau Associates, Inc. P.C.</b> <small>CONSULTING ENGINEERS AND LAND SURVEYORS</small> 2100 State Street, P.O. Box 1320 / 100 North Henderson Drive Granite City, Illinois 62040 / Granite City, Illinois 62040 Phone: (618) 952-1400 / Phone: (618) 952-1400 Fax: (618) 952-0541 / Fax: (618) 952-0541		<b>SUMMARY OF QUANTITIES</b> F.A.U. ROUTE 9024 STRATFORD LANE GRANITE CITY, ILLINOIS SECTION No. 05-00187-01-RP	
<b>REVISIONS</b> NO. DATE BY REMARKS		SCALE: NOT TO SCALE	
DSN. BY: BFK DATE: 1/12/07 DWN. BY: DAN DATE: 1/12/07 CHK'D: BFK DATE: 1/12/07		SHEET <b>3</b>	
DWG. NO.		JOB NO. E050210 DGN. NAME: STRATSCH OF 79 SHTS	