


STORM SEWER SCHEDULE

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	05-00187-01-RP	MADISON	79	11
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 87288				

STRUCTURE ID	LOCATION	RCCP TYPE 1 CLASS IV (FOOT)			RCCP TYPE 1 CLASS III (FOOT)	RCCP TYPE 2 CLASS III (FOOT)		SS, CLASS B TYPE 1 (PVC) (FOOT)		SS, CLASS B TYPE 2 (PVC) (FOOT)	TRENCH BACKFILL (CU YD)
		15"	18"	24"	30"	24"	30"	15"	24"	24"	
STRATFORD LANE											
S-19 TO SE-01	STA. 51+98.88 - 56.85' LT TO STA. 51+82.42 - 56.64' LT					12					11
S-17A TO S-19	STA. 51+98.78 - 32.56' LT TO STA. 51+98.88 - 56.85' LT			20							8
S-17 TO S-17A	STA. 52+40.00 - 23.78' LT TO STA. 51+98.78 - 32.56' LT			38							25
S-18 TO S-17	STA. 52+40.00 - 19.88' RT TO STA. 52+40.00 - 23.78' LT	40									7
S-15 TO S-17	STA. 54+20.00 - 17.50' LT TO STA. 52+40.00 - 23.78' LT			176							136
S-16 TO S-15	STA. 54+20.00 - 17.00' RT TO STA. 54+20.00 - 17.50' LT	31									4
S-21 TO S-15	STA. 55+35.00 - 17.50' LT TO STA. 54+20.00 - 17.50' LT					111					103
S-23 TO S-21	STA. 56+04.33 - 30.50' LT TO STA. 55+35.00 - 17.50' LT							68			8
S-14 TO S-21	STA. 56+84.70 - 22.95' RT TO STA. 55+35.00 - 17.50' LT								152		101
S-13 TO S-14	STA. 56+70.00 - 14.22' LT TO STA. 56+84.70 - 22.95' RT	37									5
S-12 TO S-14	STA. 57+23.73 - 22.95' RT TO STA. 56+84.70 - 22.95' RT							35			16
S-11 TO S-12	STA. 57+60.70 - 17.50' RT TO STA. 57+23.73 - 22.95' RT			34							21
S-08 TO S-11	STA. 57+60.70 - 14.21' LT TO STA. 57+60.70 - 17.50' RT	28									4
S-06 TO S-11	STA. 58+20.00 - 17.00' RT TO STA. 57+60.70 - 17.50' RT		56								21
S-05 TO S-06	STA. 58+20.00 - 14.21' LT TO STA. 58+20.00 - 17.00' RT	28									4
S-04 TO S-06	STA. 59+42.00 - 17.00' RT TO STA. 58+20.00 - 17.00' RT	119									72
S-22 TO S-03	STA. 59+02.06 - 33.90' LT TO STA. 59+42.00 - 14.22' LT							42			10
S-03 TO S-04	STA. 59+42.00 - 14.22' LT TO STA. 59+42.00 - 17.00' RT	28									6
S-01 TO S-04	STA. 60+65.00 - 17.00' RT TO STA. 59+42.00 - 17.00' RT	120									74
S-02 TO S-01	STA. 60+65.00 - 14.21' LT TO STA. 60+65.00 - 17.00' RT	28									4
I-50 TO I-49	STA. 62+89.00 - 14.21' LT TO STA. 62+89.00 - 17.00' RT	28									7
I-49 TO I-47	STA. 62+89.00 - 17.00' RT TO STA. 64+32.00 - 17.00' RT	140									70
I-48 TO I-47	STA. 64+32.00 - 14.22' LT TO STA. 64+32.00 - 17.00' RT	28									4
I-47 TO I-45	STA. 64+32.00 - 17.00' RT TO STA. 65+02.00 - 17.00' RT	67									14
I-46 TO I-45	STA. 65+02.00 - 14.71' LT TO STA. 65+02.00 - 17.00' RT	29									2
I-45 TO I-44	STA. 65+02.00 - 17.00' RT TO STA. 65+63.00 - 17.00' RT		58								12
I-44 TO I-41	STA. 65+63.00 - 17.00' RT TO STA. 66+01.00 - 17.50' RT		35								6
I-43 TO I-41	STA. 65+91.00 - 14.72' LT TO STA. 66+01.00 - 17.50' RT	31									3
I-41 TO I-37	STA. 66+01.00 - 17.50' RT TO STA. 66+32.00 - 17.50' RT			27							6
I-39 TO I-37	STA. 66+32.00 - 14.72' LT TO STA. 66+32.00 - 17.50' RT	29									4
I-37 TO I-55	STA. 66+32.00 - 17.50' RT TO STA. 67+72.12 - 17.50' RT			136							40
I-56 TO I-55	STA. 67+72.12 - 14.72' LT TO STA. 67+72.12 - 17.50' RT	29									6
I-55 TO I-33	STA. 67+72.12 - 17.50' RT TO STA. 68+80.00 - 17.50' RT			104							43
I-33 TO I-32	STA. 68+80.00 - 17.50' RT TO STA. 69+17.00 - 18.00' RT			33							19
I-36 TO I-35	STA. 68+55.00 - 14.22' LT TO STA. 68+96.00 - 14.21' LT							38			6
I-35 TO I-32	STA. 68+96.00 - 14.21' LT TO STA. 69+17.00 - 18.00' RT	35									6
I-32 TO I-29	STA. 69+17.00 - 18.00' RT TO STA. 69+50.00 - 18.00' RT				28						19
I-31 TO I-29	STA. 69+50.00 - 14.21' LT TO STA. 69+50.00 - 18.00' RT	28									4
I-29 TO I-27	STA. 69+50.00 - 18.00' RT TO STA. 70+81.83 - 27.01' RT				127						109
I-28 TO I-27	STA. 70+60.00 - 14.22' LT TO STA. 70+81.83 - 27.01' RT	43									6
I-27 TO I-51	STA. 70+81.83 - 27.01' RT TO STA. 71+29.70 - 27.01' RT							43			34
I-51 TO I-26	STA. 71+29.70 - 27.01' RT TO STA. 72+93.30 - 18.00' RT							159			192
I-26 TO I-22	STA. 72+93.30 - 18.00' RT TO STA. 73+68.31 - 18.00' RT							70			86
I-22 TO I-21	STA. 73+68.31 - 18.00' RT TO STA. 73+78.31 - 18.00' RT							5			7
I-24 TO I-25	STA. 73+44.00 - 14.22' LT TO STA. 73+78.31 - 14.22' LT							32			7
I-25 TO I-21	STA. 73+78.31 - 14.22' LT TO STA. 73+78.31 - 18.00' RT	28									7
I-21 TO I-19	STA. 73+78.31 - 18.00' RT TO STA. 74+27.00 - 18.00' RT							44			59
I-20 TO I-19	STA. 74+49.00 - 14.22' LT TO STA. 74+27.00 - 18.00' RT	35									5
I-19 TO I-17	STA. 74+27.00 - 18.00' RT TO STA. 76+30.00 - 18.00' RT							198			286
I-18 TO I-17	STA. 76+30.00 - 14.22' LT TO STA. 76+30.00 - 18.00' RT	28									4
I-17 TO I-13	STA. 76+30.00 - 18.00' RT TO STA. 76+81.00 - 18.00' RT							46			72
I-15 TO I-13	STA. 76+85.13 - 14.22' LT TO STA. 76+81.00 - 18.00' RT	29									4
I-13 TO I-10	STA. 76+81.00 - 18.00' RT TO STA. 77+40.00 - 18.00' RT							54			85
I-12 TO I-10	STA. 77+40.00 - 14.22' LT TO STA. 77+40.00 - 18.00' RT	28									4
I-10 TO I-53	STA. 77+40.00 - 18.00' RT TO STA. 78+07.57 - 25.40' RT							63			110
I-61 TO I-53	STA. 78+02.56 - 38.05' RT TO STA. 78+07.57 - 25.40' RT	10									0
I-53 TO J-02	STA. 78+07.57 - 25.40' RT TO STA. 78+32.90 - 6.49' RT							27			45
I-54 TO J-02	STA. 78+05.73 - 19.09' LT TO STA. 78+32.90 - 6.49' RT	34									6
I-52 TO J-02	STA. 78+52.38 - 31.70' LT TO STA. 78+32.90 - 6.49' RT							39			5
J-02 TO J-08	STA. 78+32.90 - 6.49' RT TO STA. 79+53.58 - 6.50' RT							116			213
TOTAL		1138	149	568	155	123	825	219	35	152	2257

DATE	BY	SURVEYED	FILED
		AREAS CHECKED	
		NO.	

DATE	BY	SURVEYED	FILED
		AREAS CHECKED	
		NO.	



Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2102 State Street, P.O. Box 1200
Granite City, Illinois 60140
Phone: (618) 277-1400 / (618) 277-5500
Fax: (618) 277-5541

710 North Hancock Drive
Granite City, Illinois 60140
Phone: (618) 277-1400 / (618) 277-5500
Fax: (618) 277-5541

QUANTITY SCHEDULES
F.A.U. ROUTE 9024
STRATFORD LANE
GRANITE CITY, ILLINOIS
SECTION No. 05-00187-01-RP

REVISIONS				SCALE:
NO.	DATE	BY	REMARKS	NOT TO SCALE

DSN. BY: BFK	DATE: 1/12/07	SHEET
DWN. BY: DAN	DATE: 1/12/07	11
CHKD: BFK	DATE: 1/12/07	
JOB NO. E050210	DGN. NAME: STRATSCH	OF 79 SMTS