

### PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKINGS		PREFORMED PLASTIC PAVEMENT MARKINGS
		4" YELLOW (FOOT)	6" WHITE (FOOT)	TYPE B 12" WHITE (FOOT)
STRATFORD LANE				
STA. 52+33.30 TO STA. 79+57.94				
	SKIP-DASH 10'-30'	638		
	STOP BARS			165
	CROSSWALKS		720	
<b>TOTAL</b>		<b>638</b>	<b>720</b>	<b>165</b>

### PIPE CULVERT REMOVAL SCHEDULE

LOCATION	PIPE CULVERT REMOVAL (FOOT)	TRENCH BACKFILL (CU YD)
STRATFORD LANE		
STA. 64+54.14 - 14.97' LT TO STA. 64+77.99 - 15.90' LT	23.85	3
STA. 65+30.13 - 15.31' LT TO STA. 65+50.24 - 15.60' LT	20.11	2
STA. 65+67.95 - 15.86' RT TO STA. 65+92.55 - 15.58' RT	24.61	4
STA. 65+96.68 - 15.19' LT TO STA. 66+21.12 - 15.22' LT	24.44	4
STA. 66+46.69 - 17.02' RT TO STA. 66+77.69 - 17.10' RT	31.00	4
STA. 66+84.71 - 17.32' RT TO STA. 67+09.25 - 18.18' RT	24.55	3
STA. 68+05.98 - 19.85' RT TO STA. 68+29.01 - 20.43' RT	23.03	3
STA. 68+33.02 - 16.11' LT TO STA. 68+53.33 - 15.83' LT	20.31	3
STA. 68+88.97 - 20.29' RT TO STA. 69+09.30 - 20.04' RT	20.34	2
STA. 69+01.73 - 15.15' LT TO STA. 69+20.32 - 15.19' LT	18.59	2
STA. 69+63.17 - 15.11' LT TO STA. 69+87.57 - 15.20' LT	24.40	3
STA. 69+68.02 - 18.80' RT TO STA. 69+90.52 - 17.95' RT	22.52	3
STA. 70+29.66 - 14.68' LT TO STA. 70+45.89 - 14.59' LT	16.23	2
STA. 70+81.85 - 18.57' RT TO STA. 71+31.81 - 17.44' RT	49.97	5
STA. 70+94.08 - 15.07' LT TO STA. 71+10.46 - 15.26' LT	16.38	2
STA. 71+65.06 - 14.94' LT TO STA. 71+80.78 - 15.08' LT	15.71	2
STA. 72+26.36 - 18.63' RT TO STA. 72+46.43 - 18.44' RT	20.07	3
STA. 72+29.09 - 14.93' LT TO STA. 72+44.85 - 14.85' LT	15.76	2
STA. 72+87.61 - 15.02' LT TO STA. 73+03.67 - 15.05' LT	16.05	2
STA. 73+00.96 - 18.37' RT TO STA. 73+28.20 - 18.94' RT	27.25	3
STA. 73+51.12 - 14.97' LT TO STA. 73+71.10 - 14.93' LT	19.98	2
STA. 74+34.66 - 18.78' RT TO STA. 74+54.84 - 19.22' RT	20.19	2
STA. 75+20.28 - 19.21' RT TO STA. 75+40.45 - 19.08' RT	20.17	3
STA. 76+02.79 - 18.43' RT TO STA. 76+23.22 - 18.57' RT	20.43	2
STA. 76+87.77 - 17.96' RT TO STA. 77+08.61 - 17.73' RT	20.84	4
<b>TOTAL</b>	<b>557</b>	<b>70</b>

### SIGN SCHEDULE

LOCATION	LT / RT	PROPOSED OFFSET (FT)	DESCRIPTION	SIGN PANEL T1 (SQ FT)	METAL POSTS SIGN ASSEMBLY TYPE B (FOOT)
STRATFORD LANE					
STA. 52+22.56	LT	31.12	R1-1-30	6.3	1 @ 13.5
STA. 52+92.72	RT	28.49	S1-1-30	5.0	1 @ 13.5
STA. 52+92.72	RT	28.49	R2-1-2430	5.0	
STA. 55+61.45	LT	29.15	R1-1-30	6.3	1 @ 13.5
STA. 55+61.45	LT	29.15	R12-1-2430	5.0	
STA. 56+35.10	LT	18.64	S1-1-30	4.7	1 @ 13.5
STA. 56+35.10	LT	18.64	R2-1-2430	5.0	
STA. 57+22.92	RT	26.67	R1-1-30	6.3	1 @ 13.5
STA. 58+64.10	LT	33.19	R1-1-30	6.3	1 @ 13.5
STA. 59+02.54	LT	43.62	S1-1-30	5.0	1 @ 13.5
STA. 59+02.54	LT	43.62	R2-1-2430	5.0	
STA. 66+81.90	RT	18.64	R1-1-30	6.3	1 @ 13.5
STA. 66+81.90	RT	18.64	R2-1-2430	5.0	
STA. 66+93.60	LT	33.34	R1-1-30	6.3	
STA. 67+60.74	LT	23.15	R1-1-30	6.3	1 @ 13.5
STA. 71+27.94	RT	30.55	R1-1-30	6.3	1 @ 13.5
STA. 78+01.89	RT	21.27	R1-1-30	6.3	1 @ 13.5
STA. 78+01.89	RT	21.27	S1-1-30	5.0	
STA. 78+12.28	LT	33.08	R1-1-30	6.3	
STA. 78+52.83	RT	34.89	R1-1-30	6.3	1 @ 13.5
STA. 78+52.83	RT	34.89	S1-1-30	5.0	
STA. 78+59.89	LT	23.66	R1-1-30	6.3	1 @ 13.5
<b>TOTAL</b>				<b>125</b>	<b>176</b>

### TRENCH BACKFILL SCHEDULE

LOCATION	TRENCH BACKFILL (CU YD)
STORM SEWER SCHEDULE	
	2257
STORM SEWER REMOVAL SCHEDULE	
	5
PIPE CULVERT REMOVAL SCHEDULE	
	70
<b>TOTAL</b>	<b>2332</b>

### PAVEMENT PATCHING SCHEDULE

LOCATION	WIDTH (FOOT)	CLASS D PATCHES TYPE II 10 IN (SQ YD)
STRATFORD LANE		
STA. 51+82.42 TO STA. 51+94.31 LT	8.0	10.6
STA. 51+93.80 TO STA. 52+04.23 LT	17.4	7.6
<b>TOTAL</b>		<b>18</b>



**QUANTITY SCHEDULES**  
**F.A.U. ROUTE 9024**  
**STRATFORD LANE**  
**GRANITE CITY, ILLINOIS**  
**SECTION No. 05-00187-01-RP**

REVISIONS				SCALE: NOT TO SCALE	
NO.	DATE	BY	REMARKS	DSN. BY:	DATE:
				BFK	1/12/07
				DAN	1/12/07
				BFK	1/12/07
DWG. NO.				JOB NO. E050210	DGN. NAME: STRATSCH

SHEET  
12

OF 79 SHTS

BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 SURVEYED \_\_\_\_\_  
 PLOTTED \_\_\_\_\_  
 NOTE BOOK \_\_\_\_\_  
 TEMPLATE \_\_\_\_\_  
 AREAS CHECKED \_\_\_\_\_  
 NO. \_\_\_\_\_

BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 ORIGINAL SURVEY PLOTTED \_\_\_\_\_  
 NOTE BOOK \_\_\_\_\_  
 TEMPLATE \_\_\_\_\_  
 AREAS CHECKED \_\_\_\_\_  
 NO. \_\_\_\_\_