

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	05-00187-01-RP	MADISON	79	13
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
			CONTRACT NO. 97288	

### CURB AND GUTTER REMOVAL SCHEDULE

LOCATION	COMBINATION CURB & GUTTER REMOVAL (FOOT)	GUTTER REMOVAL (FOOT)
STRATFORD LANE		
STA. 52+26.86 - 21.07' RT TO STA. 52+33.35 - 21.44' RT	7	
STA. 57+17.69 - 30.20' RT TO STA. 57+21.17 - 16.17' RT		15
STA. 70+92.76 - 29.73' RT TO STA. 70+92.83 - 45.06' RT		15
STA. 71+18.62 - 30.03' RT TO STA. 71+18.73 - 44.94' RT		15
STA. 78+63.32 - 16.20' RT TO STA. 79+57.35 - 12.90' RT		95
STA. 51+96.31 - 61.31' LT TO STA. 52+33.20 - 21.58' LT	64	
STA. 55+66.69 - 31.98' LT TO STA. 55+70.76 - 47.69' LT		17
STA. 55+97.06 - 47.64' LT TO STA. 56+01.74 - 31.90' LT		17
STA. 58+68.12 - 31.35' LT TO STA. 58+71.37 - 61.96' LT		30
STA. 58+96.27 - 56.80' LT TO STA. 59+00.86 - 32.89' LT		25
STA. 66+97.99 - 32.24' LT TO STA. 67+02.69 - 50.14' LT		19
STA. 67+36.14 - 50.07' LT TO STA. 67+41.29 - 31.88' LT		19
STA. 78+45.32 - 44.88' LT TO STA. 79+48.35 - 12.82' LT		124
STA. 78+17.06 - 34.17' LT TO STA. 78+20.09 - 45.12' LT		11
<b>TOTAL</b>	<b>71</b>	<b>401</b>

### SIDEWALK REMOVAL SCHEDULE

LOCATION	AREA (SQ FT)
STRATFORD LANE	
STA. 51+96.90 - 61.31' LT TO STA. 52+02.90 - 32.95' LT	108.7
STA. 56+07.42 - 27.04' LT TO STA. 56+14.47 - 26.98' LT	27.0
STA. 56+91.39 - 26.83' LT TO STA. 57+18.65 - 26.49' LT	93.9
STA. 58+53.61 - 26.33' LT TO STA. 58+63.40 - 26.27' LT	30.4
STA. 58+99.66 - 30.38' LT TO STA. 59+22.57 - 30.23' LT	84.1
STA. 59+63.28 - 29.91' LT TO STA. 59+87.28 - 29.18' LT	109.5
STA. 60+43.48 - 28.88' LT TO STA. 60+57.48 - 28.88' LT	48.8
STA. 61+41.52 - 28.64' LT TO STA. 61+59.28 - 28.77' LT	62.5
STA. 62+04.67 - 28.89' LT TO STA. 62+45.17 - 28.71' LT	158.1
STA. 63+22.86 - 28.73' LT TO STA. 63+36.86 - 28.85' LT	54.0
STA. 63+83.72 - 28.85' LT TO STA. 64+04.12 - 28.86' LT	79.0
STA. 64+53.99 - 28.86' LT TO STA. 64+80.87 - 28.77' LT	100.1
STA. 65+21.73 - 28.99' LT TO STA. 65+58.93 - 29.00' LT	147.6
STA. 65+90.62 - 28.93' LT TO STA. 66+25.46 - 28.74' LT	128.0
STA. 66+84.88 - 28.65' LT TO STA. 66+89.55 - 28.64' LT	15.3
STA. 67+45.13 - 27.00' LT TO STA. 67+55.12 - 28.99' LT	38.6
STA. 67+78.51 - 28.97' LT TO STA. 68+20.52 - 28.97' LT	164.1
STA. 68+30.59 - 28.94' LT TO STA. 68+50.15 - 28.92' LT	74.0
STA. 68+99.21 - 28.92' LT TO STA. 69+22.61 - 28.96' LT	91.2
STA. 69+54.77 - 28.94' LT TO STA. 69+94.64 - 28.79' LT	155.0
STA. 70+27.02 - 28.64' LT TO STA. 70+49.83 - 28.70' LT	82.6
STA. 70+89.98 - 28.77' LT TO STA. 71+11.58 - 28.79' LT	83.5
STA. 71+65.27 - 28.74' LT TO STA. 71+79.91 - 28.74' LT	57.1
STA. 72+28.07 - 28.81' LT TO STA. 72+44.07 - 28.79' LT	63.2
STA. 72+85.92 - 28.76' LT TO STA. 73+05.24 - 28.77' LT	75.5
STA. 73+48.24 - 28.79' LT TO STA. 73+73.98 - 28.81' LT	98.9
STA. 74+14.86 - 28.91' LT TO STA. 74+47.02 - 29.00' LT	121.8
STA. 74+88.22 - 29.14' LT TO STA. 75+11.22 - 29.26' LT	89.0
STA. 75+54.54 - 29.26' LT TO STA. 76+08.46 - 29.11' LT	211.1
STA. 76+36.43 - 29.03' LT TO STA. 76+60.57 - 28.91' LT	119.4
STA. 76+91.23 - 28.82' LT TO STA. 77+19.07 - 28.75' LT	112.5
STA. 78+04.14 - 28.39' LT TO STA. 78+06.68 - 28.37' LT	9.7
<b>TOTAL</b>	<b>2894</b>

### DRIVEWAY PAVEMENT REMOVAL SCHEDULE

LOCATION	AREA (SQ YD)
STRATFORD LANE	
STA. 53+60.44 RT	50.1
STA. 55+21.53 RT	52.1
STA. 56+26.58 RT	54.0
STA. 58+36.11 RT	25.7
STA. 61+37.95 RT	2.0
STA. 62+61.02 RT	23.6
STA. 63+43.75 RT	57.6
STA. 63+70.68 RT	63.0
STA. 64+55.38 RT	133.7
STA. 65+81.88 RT	76.7
STA. 66+98.24 RT	38.7
STA. 68+99.43 RT	13.0
STA. 69+79.38 RT	64.0
STA. 72+36.29 RT	25.9
STA. 73+14.03 RT	44.9
STA. 74+44.74 RT	42.5
STA. 75+30.79 RT	37.3
STA. 76+13.02 RT	62.6
STA. 76+98.97 RT	12.5
STA. 79+26.32 RT	77.9
STA. 53+67.60 LT	23.5
STA. 57+06.35 LT	10.6
STA. 58+64.84 LT	14.0
STA. 59+75.27 LT	25.5
STA. 60+50.47 LT	1.3
STA. 61+52.89 LT	3.9
STA. 62+16.34 LT	13.4
STA. 62+34.47 LT	6.9
STA. 63+29.85 LT	1.2
STA. 63+93.91 LT	7.1
STA. 64+67.41 LT	17.0
STA. 65+40.32 LT	33.2
STA. 66+08.02 LT	53.1
STA. 68+40.35 LT	5.3
STA. 69+10.90 LT	5.3
STA. 69+68.13 LT	7.4
STA. 69+81.54 LT	6.3
STA. 70+38.41 LT	4.9
STA. 71+00.77 LT	8.1
STA. 71+72.57 LT	1.6
STA. 72+36.05 LT	2.9
STA. 72+95.57 LT	2.8
STA. 73+60.84 LT	17.9
STA. 74+30.93 LT	22.1
STA. 74+99.71 LT	6.7
STA. 75+65.24 LT	10.8
STA. 75+94.34 LT	9.1
STA. 76+45.37 LT	10.0
STA. 77+05.13 LT	10.8
<b>TOTAL</b>	<b>1301</b>

### PAVEMENT REMOVAL SCHEDULE

LOCATION	AREA (SQ YD)
STRATFORD LANE	
STA. 56+85.45 - 15.63' RT TO STA. 57+20.90 - 16.58' RT	44.5
<b>TOTAL</b>	<b>45</b>

### STORM SEWER REMOVAL SCHEDULE

LOCATION	STORM SEWER REMOVAL 10" (FOOT)	STORM SEWER REMOVAL 15" (FOOT)	TRENCH BACKFILL (CU YD)
STRATFORD LANE			
STA. 51+98.38 - 56.83' LT TO STA. 51+82.42 - 56.64' LT	16		
STA. 51+98.38 - 56.83' LT TO STA. 51+98.78 - 30.07' LT	28		
STA. 67+51.55 - 15.32' LT TO STA. 67+39.65 - 43.27' LT		30	5
<b>TOTAL</b>	<b>44</b>	<b>30</b>	<b>5</b>

### TREE REMOVAL SCHEDULE


LOCATION	OVER 15" (UNIT)	UNDER 15" (UNIT)
STRATFORD LANE		
STA. 53+24.59 - 25.80' LT		10
STA. 53+85.23 - 26.01' LT	20	
STA. 54+83.92 - 25.09' RT		15
STA. 57+79.50 - 23.94' RT		8
STA. 59+10.67 - 33.83' LT	30	
STA. 61+56.49 - 23.00' RT		6
STA. 61+88.43 - 22.66' RT		6
STA. 62+69.80 - 20.31' LT	30	
STA. 72+78.23 - 21.04' LT	16	
STA. 72+87.91 - 32.66' RT	16	
<b>TOTAL</b>	<b>112</b>	<b>45</b>

### STRUCTURES TO BE REMOVED

LOCATION	TO BE REMOVED	
	INLET (EA)	MANHOLE (EA)
STRATFORD LANE		
STA. 51+98.38 - 56.83' LT	1	
STA. 67+51.55 - 15.32' LT		1
<b>TOTAL</b>	<b>1</b>	<b>1</b>

DATE	
BY	
FINAL SURVEY	
SURVEYED	
NOTED	
BOOK	
NO.	
AREAS CHECKED	

DATE	
BY	
ORIGINAL SURVEY	
SURVEYED	
NOTED	
BOOK	
NO.	
AREAS CHECKED	



**Juneau Associates, Inc. P.C.**  
CONSULTING ENGINEERS AND LAND SURVEYORS  
2100 Stone Street, P.O. Box 1209  
Granite City, Illinois 62041  
Phone: (618) 271-1400 / (618) 271-1401  
Fax: (618) 271-0411

**QUANTITY SCHEDULES**  
F.A.U. ROUTE 9024  
STRATFORD LANE  
GRANITE CITY, ILLINOIS  
SECTION No. 05-00187-01-RP

REVISIONS				SCALE: NOT TO SCALE	
NO.	DATE	BY	REMARKS	DSN. BY:	DATE:
				BFK	1/12/07
				DAN	1/12/07
				BFK	1/12/07

DWG. NO.	JOB NO. E050210	DGN. NAME: STRATSCH	OF 79 SHTS
----------	-----------------	---------------------	------------