



CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

WATERLOO OFFICE
118 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 938-6060
FAX (618) 938-3988
waterloo@twm-inc.com

ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 236-0082
FAX (314) 872-2194
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGNER	04-02289
PROFESSIONAL ENGINEERING CORP.	04-06270
PROFESSIONAL ARCHITECTURAL ENGINEER CORP.	04-06622
ILLINOIS PROFESSIONAL SURVEYING CORP.	04-00229
MISSOURI PROFESSIONAL ENGINEER CORP.	FC 00000
MISSOURI LAND SURVEYING CORP.	FC 00000

SEAL

Signature: _____
 Signature Date: _____
 Registration Date: _____
STATEMENT OF RESPONSIBILITY
 I hereby confirm that the documents herein to be submitted, by my seal is restricted to this draw, and I hereby declare my responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the construction, engineering or survey project.

STORM SEWER SCHEDULE													
FROM	OFFSET (FEET)	TO STATION	OFFSET (FEET)	STORM SEWER TYPE	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	PRECAST REINF. CONC. FLARED END SEC. (EACH)	PRECAST REINF. CONC. FLARED END SEC. (EACH)	PIPE CULVERT REMOVAL (FEET)	TRENCH BACKFILL (CU YD)
					12"	12"	18"	18"	24"	12"	24"		
SEIBERT ROAD													
33+75.50	14.59	LT 35+25.00	14.59	LT CLASS A, TYPE 2		36		37					10.6
33+75.50	14.59	RT 35+25.00	14.59	RT CLASS A TYPE 2									26.8
35+10.00		RT 35+15.00										115	
35+25.00	14.59	LT 35+25.00	60.33	LT CLASS A TYPE 3					42				
35+25.00	60.33	LT 35+43.11	60.33	LT CLASS A TYPE 3					42				
35+25.00	14.59	RT 35+25.00	14.59	RT CLASS A TYPE 2			25						
35+25.00	14.59	RT 35+24.13	39.03	RT CLASS A TYPE 2			19						28.1
35+43.11	104.33	LT 35+68.58	43.70	LT CLASS A TYPE 3					36				
35+68.58	143.70	LT								1			
37+56.97	14.00	LT 38+93.40	14.00	LT CLASS A, TYPE 2		126							32.6
37+56.97	14.00	RT 37+56.97	14.00	RT CLASS A, TYPE 2		26							6.4
38+93.40	14.00	RT 38+93.40	14.00	RT CLASS A, TYPE 2		26							6.4
38+93.40	14.00	LT 41+43.40	14.00	LT CLASS A, TYPE 2		246							63.7
41+43.40	14.00	RT 41+43.40	14.00	RT CLASS A, TYPE 2		26							6.4
41+43.40	14.00	LT 43+93.40	14.00	LT CLASS A, TYPE 2		247							6.4
43+93.40	14.00	LT 43+93.40	14.00	LT CLASS A, TYPE 2		26							7.3
43+93.40	14.00	RT 44+50.00	14.00	RT CLASS A TYPE 2		53							10.7
44+50.00	14.00	RT 45+25.00	20.07	RT TYPE 1 WATERMAIN QUAL. PIPE SDR 21	70					1			
45+25.00	20.07	RT								1		115	263
TOTAL:					70	812	81	84	36	1	1	115	263

DRAINAGE STRUCTURE SCHEDULE								
STATION	OFFSET (FEET)		INLETS				MH TYPE A	
			TYPE-A		TYPE-B		4' DIA	
			EACH	T-1 F, CL	EACH	SPEC. GRATE	T-3 F&G	T-1 F, CL
SEIBERT ROAD								
33+75.5	14.59	LT			1			
33+75.5	14.59	RT			1			
35+24.13	39.03	RT				1		
35+25.00	14.59	LT					1	
35+25.00	60.33	LT						1
35+25.00	14.59	RT					1	
35+43.11	104.33	LT						1
37+56.97	14.00	LT			1			
37+56.97	14.00	RT	1					
38+93.40	14.00	LT			1			
38+93.40	14.00	RT	1					
41+43.40	14.00	LT			1			
41+43.40	14.00	RT	1					
43+93.40	14.00	LT			1			
43+93.40	14.00	RT	1					
44+50.00	14.00	RT		1				
TOTAL:			4	3	4	1	2	2

TITLE	PROJECT:
SCHEDULE OF QUANTITIES	SEIBERT ROAD RECONSTRUCTION - PHASE IV VILLAGE OF SHILOH ST. CLAIR COUNTY, ILLINOIS

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY: M.J.J.	SHEET
DESIGNED BY: M.J.J.	4
CHECKED BY: XXX	
APPROVED BY: XXX	
PROJECT NUMBER: D20010479	
OF 36 SHEETS	
<input type="checkbox"/> ISSUED FOR REVIEW <input type="checkbox"/> ISSUED FOR BIDDING <input type="checkbox"/> ISSUED FOR CONSTR. <input type="checkbox"/> RECORD DRAWING	