

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	77-03, 4-1, 4-2RS-2	PULASKI	52	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

## SUMMARY OF QUANTITIES

SHEET 1 OF 3

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	90% FEDERAL / 10% STATE PULASKI COUNTY		
			TOTAL QUANTITY	I-57	MOUNDS RD FAS 939
				I 000	I 000
X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	87	87	
X0322278	RODENT SHIELDS	EACH	20	20	
X0322653	BITUMINOUS SIGN PADS	TON	32	32	
X0322729	MATERIAL TRANSFER DEVICE	TON	28841	28841	
<del>X0329907</del>	<del>PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/2"</del>	<del>SQ YD</del>	<del>284</del>	<del>284</del>	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
Z0010500	CLEANING CULVERTS	L SUM	1	1	
Z0017202	DOWEL BARS 1 1/2"	EACH	472	336	336
Z0075310	TIE BARS 3/4"	EACH	670	670	
Z0076600	TRAINEES	Hour	500	500	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	76	76	
25000350	SEEDING, CLASS 7	ACRE	3.5	3.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	560	560	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	420	420	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	420	420	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	7	7	
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	3.5	3.5	
25100115	MULCH, METHOD 2	ACRE	6	6	
25100630	EROSION CONTROL BLANKET	SQ YD	5246	5246	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	350	350	
28000300	TEMPORARY DITCH CHECKS	EACH	28	28	
28000400	PERIMETER EROSION BARRIER	FOOT	1869	1869	
28000500	INLET AND PIPE PROTECTION	EACH	23	23	
28100107	STONE RIPRAP, CLASS A4	SQ YD	107	107	
28100205	STONE RIPRAP, CLASS A3	TON	142	142	
28102600	STONE RIPRAP DITCH	TON	140	140	
28200200	FILTER FABRIC	SQ YD	107	107	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1438		1438
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	21270	21270	
40600300	AGGREGATE (PRIME COAT)	TON	380	356	24
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19	19	
<del>40600645</del>	<del>LEVELING BINDER (MACHINE METHOD), N90</del>	<del>TON</del>	<del>717</del>	<del>105</del>	<del>612</del>
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2501	2280	221
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	414		414
40600990	TEMPORARY RAMP	SQ YD	540	486	54
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	17092	17092	
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	919		919

Y080

Rev.