

F.A.C. RYS.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	18	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

*859 & 132
**IRS-2,20XRS,103,104,105RS-2

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	GALATIA LOCATION	PANKEYVILLE LOCATION
				STP-RURAL-STATE 80% FED / 20% STATE SALINE COUNTY	STP-RURAL-STATE 80% FED / 20% STATE SALINE COUNTY
				1000 QUANTITY	1000 QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	19,630.0	17,626.0	2,004.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25,613.0	22,785.0	2,828.0
40600300	AGGREGATE (PRIME COAT)	TON	422.9	374.5	48.4
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	6,278.0	5,627.0	651.0
40600895	CONSTRUCTING TEST STRIP	EACH	5.0	5.0	0.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,229.0	1,095.0	134.0
40600990	TEMPORARY RAMP	SQ YD	133.0	106.4	26.6
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE "D", N90	TON	12,920.0	11,607.0	1,313.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	437.1	392.0	45.1
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	165.0	0.0	165.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	130,772.0	124,454.0	6,318.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	18,840.0	9,680.0	9,160.0
44201823	CLASS D PATCHES, TYPE I, 15 INCH	SQ YD	123.0	85.0	38.0
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	3,339.0	3,151.0	188.0
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	54.0	54.0	0.0
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	54.0	54.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	434.0	404.0	30.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	2.0	1.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.5	0.5
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0	0.5	0.5
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	4,260.0	4,025.0	235.0
70300210	TEMPORARY PAVEMENT MARKING, LETTERS ^{AND} SYMBOLS	SQ FT	122.4	122.4	0.0
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	152,410.0	137,228.0	15,182.0
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	72.0	72.0	0.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	51,701.0	46,613.0	5,088.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS ^{AND} SYMBOLS	SQ FT	122.4	122.4	0.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	72.0	72.0	0.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	152,410.0	137,228.0	15,182.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	703.0	629.0	74.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	703.0	629.0	74.0

*SPECIALTY ITEMS

DATE = 3/12/2007
FILE NAME = a:\projects\98945\98945.dwg
PLOT SCALE = 1/8"=1'-0"
USER NAME = masonr