

PAVEMENT MARKING SCHEDULE

F.A.P. R.T.C.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	18	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

\*869 & 132  
\*\*IRS-2,20XRS(103,104,105)RS-2

STATION TO STATION	PAINT PAVEMENT MARKING			THPL PAVT MARK		TEMPORARY			NOTES		
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH	24 INCH WHITE	LETTERS & SYMBOLS WHITE	4 INCH	24 INCH	LETTERS & SYMBOLS			
	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	SQ FT			
<b>IL 34 - GALATIA TO MT. MORIAH</b>											
Station 1060+00 To Sta. 1570+00											
	1063+50	TO	1093+38								
	1120+00	TO	1191+60		747.0			747.0			
	1206+59	TO	1267+72		1,790.0			1,790.0			
	1273+95	TO	1310+64		1,579.0			1,579.0			
	1318+52	TO	1328+55		918.0			918.0			
	1329+82	TO	1340+21		251.0			251.0			
	1347+60	TO	1370+31		260.0			260.0			
					568.0			568.0			
Railroad Crossing at Sta. 1370+15											
	1370+36	TO	1570+00		5,050.0			5,050.0			
LEFT	1063+50	TO	1570+00	49,505.0				49,505.0	Edgeline		
LEFT	1093+38	TO	1126+02		2,844.0			2,844.0	NPZ		
LEFT	1157+91	TO	1167+26		935.0			935.0	NPZ		
LEFT	1191+60	TO	1219+00		2,940.0			2,940.0	NPZ		
LEFT	1246+97	TO	1255+31		834.0			834.0	NPZ		
LEFT	1267+72	TO	1285+51		1,779.0			1,779.0	NPZ		
LEFT	1310+64	TO	1329+82		1,918.0			1,918.0	NPZ		
LEFT	1340+21	TO	1358+32		1,811.0			1,811.0	NPZ		
LEFT	1370+36	TO	1377+44		708.0			708.0	NPZ		
LEFT	1370+36					12.0		12.0	Stop Bar		
LEFT	1373+27					12.0		12.0	Stop Bar		
LEFT	1373+53						7.2	7.2	2-Railroad R's		
LEFT	1373+53						54.0	54.0	1-Railroad X		
LEFT	1373+79					12.0		12.0	Stop Bar		
LEFT	1403+57	TO	1411+60		803.0			803.0	NPZ		
RIGHT	1063+50	TO	1570+00	49,525.0				49,525.0	Edgeline		
RIGHT	1082+27	TO	1120+00		3,371.0			3,371.0	NPZ		
RIGHT	1151+05	TO	1155+43		438.0			438.0	NPZ		
RIGHT	1157+91	TO	1167+26		935.0			935.0	NPZ		
RIGHT	1235+78	TO	1245+12		934.0			934.0	NPZ		
RIGHT	1256+58	TO	1273+95		1,737.0			1,737.0	NPZ		
RIGHT	1300+30	TO	1318+52		1,822.0			1,822.0	NPZ		
RIGHT	1328+55	TO	1347+60		1,905.0			1,905.0	NPZ		
RIGHT	1365+87	TO	1369+99		412.0			412.0	NPZ		
RIGHT	1366+67					12.0		12.0	Stop Bar		
RIGHT	1366+83						7.2	7.2	2-Railroad R's		
RIGHT	1366+93						54.0	54.0	1-Railroad X		
RIGHT	1367+14					12.0		12.0	Stop Bar		
RIGHT	1369+99					12.0		12.0	Stop Bar		
RIGHT	1391+01	TO	1400+09		908.0			908.0	NPZ		
<b>GALATIA SUB-TOTALS</b>				<b>99,030.0</b>	<b>27,035.0</b>	<b>11,163.0</b>	<b>72.0</b>	<b>122.4</b>	<b>137,228.0</b>	<b>72.0</b>	<b>122.4</b>
<b>IL 34 - PANKEYVILLE</b>											
Station 5+00 To Station 52+35											
	16+31	TO	10+00								
	0+00	TO	18+00		158.0			158.0			
	20+00	TO	52+35		450.0			450.0			
					809.0			809.0			
LEFT	16+31.0	TO	10+00	631.0				631.0	Edgeline		
LEFT	0+00	TO	52+35	5,133.0				5,133.0	Edgeline		
LEFT	18+00	TO	30+00		1,200.0			1,200.0	NPZ		
RIGHT	16+31	TO	10+00	631.0				631.0	Edgeline		
RIGHT	0+00	TO	52+35	5,170.0				5,170.0	Edgeline		
RIGHT	13+00	TO	20+00		700.0			700.0	NPZ		
RIGHT	49+35	TO	52+35		300.0			300.0	NPZ		
<b>PANKEYVILLE SUB-TOTALS</b>				<b>11,565.0</b>	<b>2,200.0</b>	<b>1,417.0</b>	<b>0.0</b>	<b>0.0</b>	<b>15,182.0</b>	<b>0.0</b>	<b>0.0</b>
<b>SUB-TOTALS</b>				<b>110,595.0</b>	<b>29,235.0</b>	<b>12,580.0</b>	<b>72.0</b>	<b>122.4</b>	<b>152,410.0</b>	<b>72.0</b>	<b>122.4</b>
<b>TOTALS</b>				<b>110,595.0</b>	<b>29,235.0</b>	<b>12,580.0</b>	<b>72</b>	<b>122.4</b>	<b>152,410.0</b>	<b>72</b>	<b>122.4</b>

PLOT DATE: 5/1/2007  
 FILE NAME: C:\Program Files\Autodesk\AutoCAD 2007\acad2007.lsp  
 USER NAME: Administrator