

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/64	(41-3)HBK	JEFFERSON	518	074
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 98963				

CURB AND GUTTER, MEDIAN AND SIDEWALK SCHEDULE - GRADE SEPARATION										
LOCATION			PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	COMBINATION CONCRETE CURB & GUTTER B-6.06	COMBINATION CONCRETE CURB & GUTTER B-6.12	COMBINATION CONCRETE CURB & GUTTER B-6.18	COMBINATION CONCRETE CURB & GUTTER B-6.24	CONCRETE MEDIAN SURFACE, 4 INCH	CONCRETE MEDIAN, TYPE SB-6	
			SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	
VETERANS MEMORIAL DRIVE										
STA.	34+00.00	TO STA.	34+70.52	779.3						
STA.	34+00.00	TO STA.	34+73.47						690.0	
STA.	35+65.45	TO STA.	38+45.00						2754.0	
STA.	35+97.63	TO STA.	43+94.54	911.8						
STA.	38+45.00	TO STA.	48+12.27		1077.9			10798.2		
STA.	44+61.73	TO STA.	48+20.78							
STA.	45+28.25	TO STA.	47+02.25						1619.7	
STA.	51+32.27	TO STA.	58+81.00					7165.9		
STA.	51+40.78	TO STA.	54+96.23	396.2						
STA.	52+77.64	TO STA.	54+23.70						1339.5	
STA.	55+70.97	TO STA.	61+29.21	641.5						
STA.	58+81.00	TO STA.	61+51.33						2657.4	
STA.	62+33.53	TO STA.	64+42.00						2037.3	
STA.	62+54.59	TO STA.	76+40.34	13860.0						
STA.	64+42.00	TO STA.	69+05.05					7001.2		
STA.	69+40.00	TO STA.	69+98.18						404.4	
STA.	34+00.00	TO STA.	34+95.30				133.0			
STA.	34+00.00	TO STA.	35+16.15				147.0			
STA.	35+35.31	TO STA.	48+05.18				1195.0			
STA.	35+63.14	TO STA.	48+19.76				1150.0			
STA.	38+45.00	TO STA.	40+45.00	200.0						
STA.	47+02.25	TO STA.	48+11.00	108.8						
STA.	51+25.18	TO STA.	61+69.58				953.0			
STA.	51+32.27	TO STA.	56+81.00		460.0					
STA.	51+34.30	TO STA.	52+77.64	143.3						
STA.	51+39.76	TO STA.	61+73.18				962.0			
STA.	56+81.00	TO STA.	58+81.00	200.0	200.0					
STA.	62+05.87	TO STA.	76+40.34				2983.0			
STA.	64+42.00	TO STA.	66+42.00	200.0	200.0					
STA.	66+42.00	TO STA.	66+50.00		16.0					
STA.	66+50.00	TO STA.	69+05.05		580.0					
			SUBTOTAL	16993.2	852.1	2533.9	0.0	7523.0	24965.3	11502.3
45TH STREET										
STA.	109+74.09	TO STA.	111+20.00	751.8						
STA.	110+12.23	TO STA.	111+20.00				108.0			
STA.	110+88.47	TO STA.	111+20.00				32.0			
STA.	113+51.19	TO STA.	114+02.19				51.0			
			SUBTOTAL	751.8	0.0	0.0	0.0	191.0	0.0	0.0
42ND STREET										
STA.	192+15.21	TO STA.	198+22.47				701.0			
STA.	192+15.21	TO STA.	198+99.50				684.0			
STA.	192+18.27	TO STA.	195+36.44			322.0				
STA.	192+18.27	TO STA.	195+36.44			322.0				
STA.	201+03.21	TO STA.	203+32.15				629.0			
STA.	201+70.77	TO STA.	207+32.15				561.0			
			SUBTOTAL	0.0	0.0	0.0	644.0	2575.0	0.0	0.0
ACCESS ROAD #1										
STA.	9+69.67	TO STA.	15+38.00							
STA.	15+38.00	TO STA.	16+82.96				73.0			
			SUBTOTAL	0.0	0.0	0.0	73	0.0	0.0	0.0
ACCESS ROAD #2										
STA.	20+31.80	TO STA.	22+12.77				240.0			
STA.	21+20.50	TO STA.	22+12.77				212.0			
			SUBTOTAL	0.0	0.0	0.0	452.0	0.0	0.0	0.0
			TOTAL	17745.0	852.1	2533.9	1169.0	10289.0	24965.3	11502.3
			USE TOTAL	17745.0	852	2534	1169	10289	24965	11502

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
VETERANS MEMORIAL DRIVE INTERCHANGE
SECTION (41-3)HBK
SCALE: NO SCALE DRAWN BY RL
DATE 3-22-07 CHECKED BY MTM

Copyright Hanson Professional Services Inc. 2007
HANSON
 Hanson Professional Services Inc.

03/22/2007 05:35 PM
 I:\06\pds\9820\98\road\stee\Ac-616-sch.dgn

LAYOUT	RLT	02/26/04
DRAWN	JED	04/12/04
REVIEWED	MTM	03/22/07