

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(X1-6-2)HBK	WILLIAMSON	272	7
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
				1000-2A FED 80% STATE 20%	X281-2A FED 80% STATE 20%	Y080 FED 80% STATE 20%	STATE 100%
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6,670	6,670			
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	29	29			
* 82500540	LIGHTING CONTROLLER TYPE CB-RCS 100AMP - 480VOLT	EACH	1	1			
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M. H., 15 FT. MAST ARM	EACH	29	29			
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	203	203			
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3	3			
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	4	4			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1			
* Z0049100	RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT	EACH	76	76			
o Z0076600	TRAINEES	HOUR	2,000			2,000	
Z0076800	TURF REINFORCEMENT MAT	SQ YD	8,708	8,708			
50901730	BRIDGE FENCE RAILING	FOOT	369		369		
X0321781	MECHANICAL SPLICE	EACH	180		180		
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	149		149		
X0322729	MATERIAL TRANSFER DEVICE	TON	(TABLE 1)		(TABLE 1)		
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1,280		1,280		
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	2		2		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	146		146		
X0325769	SUB-BASE GRANULAR MATERIAL, 8 1/2", TYPE C	SQ YD	(TABLE 1)		(TABLE 1)		
X0325758	MANHOLES, TYPE A, 8' DIAMETER, TYPE 8 GRATE	EACH	2		2		
Δ(*) Z5000305	SEEDING, CLASS 3A	ACRE	2.6		2.6		
X0325759	TRAFFIC CONTROL AND PROTECTION - STAGE 1	L SUM	1		1		
X0325760	TRAFFIC CONTROL AND PROTECTION - STAGE 2	L SUM	1		1		
X0325761	TRAFFIC CONTROL AND PROTECTION - STAGE 3	L SUM	1		1		
X0325762	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH TOP & 17 INCH BOTTOM BOLT	EACH	29		29		
X0325763	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1		1		

* 82001167	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 8' HEIGHT BALLED AND BURLAPPED	EACH	15	15			
* 82002108	TREE, CRATAEGUS VIKOIS (GREEN HAWTHORN) 7' HEIGHT MULTI-STEM, BALLED AND BURLAPPED	EACH	10	10			
* K0030404	PERENNIAL, RUOBECKIA FULGIDA 'GOLDSTRUM', (GOLDSTRUM BLACK EYED SUSAN), 1 GALLON	EACH	250	250			

* SPECIALTY ITEMS
o Y080

REVISIONS		NAME	DATE
NO.	DESCRIPTION		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
MORGAN AVENUE INTERCHANGE
FAI ROUTE 57 WITH FAU ROUTE 9718
WILLIAMSON COUNTY
5 OF 5

SCALE: N/A
DATE: 5-04-2007
DRAWN BY: DH
CHECKED BY: RD

Rev. 5-30-07

Rev.

PLT DATE = 5/17/2007
FILE NAME = P:\A\08500\dgn\0489600.dgn
PLT SCALE = 56.0000 / IN.
USER NAME = dhoerner