

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	IX1-6-2HBK	WILLIAMSON	272	6
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A	X281-2A	Y080	Y002-1C
				FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	STATE 100%
72000100	SIGN PANEL - TYPE 1	SQ FT	134.0	134.0			
72000200	SIGN PANEL - TYPE 2	SQ FT	119.0	119.0			
72000300	SIGN PANEL - TYPE 3	SQ FT	2,572.0	739.5			1,832.5
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	919.5	919.5			
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	10,723	10,723			
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	124	124			
73000100	WOOD SIGN SUPPORT	FOOT	212	212			
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	3	3			
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4' -0" X 4' -6")	FOOT	96	96			
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4' -6" X 5' -3")	FOOT	87	87			
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5' -6")	FOOT	30	30			
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	33	33			
73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	116	116			
73400100	CONCRETE FOUNDATIONS	CU YD	57.0	57.0			
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	18.1	18.1			
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1	1			
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	10	10			
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	10	10			
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2	2			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	(TABLE 1)	(TABLE 1)			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	(TABLE 1)	(TABLE 1)			
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	(TABLE 1)	(TABLE 1)			
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	(TABLE 1)	(TABLE 1)			
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	(TABLE 1)	(TABLE 1)			
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8	72.8			
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,632	5,632			
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	342	342			
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SQ FT	(TABLE 1)	(TABLE 1)			
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	(TABLE 1)	(TABLE 1)			
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	(TABLE 1)	(TABLE 1)			
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	(TABLE 1)	(TABLE 1)			
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	(TABLE 1)	(TABLE 1)			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	255	255			
78200300	PRISMATIC CURB REFLECTOR	EACH	51	51			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	21	21			
78200530	BARRIER WALL MARKERS, TYPE C	EACH	10	10			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,341.0	2,341.0			
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	500	500			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1			
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	94	94			
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1,130	1,130			
* 81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	6,049	6,049			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

MORGAN AVENUE INTERCHANGE  
FAU ROUTE 57 WITH FAU ROUTE 9718  
WILLIAMSON COUNTY

4 OF 5

SCALE: N/A  
DATE: 5-04-2007

DRAWN BY: DH  
CHECKED BY: RD