| FAU | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 9713 | 99-02118-00-FP | JACKSON | 122 | 25 |
| STA. 62+00 | TO STA. 68+00 | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

CONTRACT NO. 99219

PARCEL 19
HAROLD F & VIVIAN M YOUNG, TRUSTEES

LT. STA 63+14
CONSTRUCT 15' PE
NO PIPE

LT. STA 63+87
CONSTRUCT 16' CE
NO PIPE

LT. STA 66+66
CONSTRUCT 20' CE
NO PIPE

LT. STA 67+35
CONSTRUCT 12' PE
NO PIPE

TRAILER PARK

EXISTING R.O.W. LINE

CONSTRUCTION LIMITS

TEMP. EASEMENT

+50.00 28.00' LT
+50.00 30.00' LT
+50.00 20.00' LT
+10.00 30.00' LT.
+10.00 25.00' LT
+82.51 25.00' LT.
+40.00 30.00' LT.
+40.00 25.00' LT.
+10.00 50.00' LT.
+10.00 30.00' LT.
+60.00 50.00' LT.
PARCEL 22
MICHAEL D. & CONNIE YOUNG
+60.00 20.00' LT.
+82.51 20.00' LT
+85.55 20.00' LT.

P.E. +14 15' AGG.
C.E. +87 16' AGG.
C.E. +66 20' BIT.
P.E. +35 12' BIT.
P.E. +85 18' AGG.
P.E. +64 18' AGG.
P.E. +38 20' BIT.

403 110 120 313

MATCH LINE STA. 62+00

MATCH LINE STA. 68+00

EAST PLEASANT HILL ROAD

PLEASANT HILL RD

12" CMP
18" RCP
8" PE CORRUGATED PLASTIC PIPE
8" CI
18" RCCP

EXISTING R.O.W. LINE
CONSTRUCTION LIMITS
PROPOSED R.O.W. LINE
TEMP. EASEMENT

+00.00 45.00' RT.
+06.11 45.00' RT.
+50.00 45.00' RT.
+50.00 60.00' RT.
+82.51 45.00' RT.
+82.51 60.00' RT.
+00.00 45.00' RT.
+85.55 45.00' RT.
+85.55 55.00' RT.
+00.00 55.00' RT.

℄ PROPOSED IMPROVEMENT

AR. STA 62+28
EXISTING 18" RCCP TO BE REMOVED
PIPE CULVERT REMOVAL = 28 FOOT
C.L.S.M. = 16.7 CU.YD.

P.R.C.F.E.S. 12"
INV. = 415.35

RT. STA 64+85
CONSTRUCT 16' FE
15" CMP 30' LONG
END SECTION = 2

RT. STA 65+64
CONSTRUCT 18' PE
NO PIPE

RT. STA 66+38
CONSTRUCT 20' PE
15" CMP 34' LONG
END SECTIONS = 2

RAYMOND & ESTELLA C BENZ
PARCEL 20

JAMES & JENNY PREST
PARCEL 21

NOTE:
FOR ADDITIONAL STORM SEWER PROFILES
SEE STORM SEWER PROFILE SHEET 33

**LEGEND**

TREE REMOVAL ACRE

**CURVE #2**
**CURVE DATA**
PI STA. 66+84.04
Δ = 2° 22' 07.96" (RT)
D = 1° 10' 31"
R = 4,911.07'
T = 101.54'
L = 203.05'
E = 1.05'
PC STA. 65+82.51
PT STA. 67+85.55
S.E. = NONE

0 20' 40'
GRAPHIC SCALE

N

MECHANIZED LAND CLEARING EQUIPMENT WILL NOT BE ALLOWED FOR TREE REMOVAL IN THE DESIGNATED WETLAND AREAS

EXISTING ℄ GRADE
PROPOSED ℄ GRADE
VPI STA. 67+20.00
ELEV. 419.70
K = 31
260' V.C.
+0.50%
-8.00%
+0.30%
+0.30%
-0.81%
411.50 RT.
411.75 RT.
SPECIAL DITCH RIGHT
415.05 RT.
INV. = 415.47
415.35 RT.
SPECIAL DITCH RIGHT
415.43 RT.
+78
RT 15" C.M.P.
30' LONG & END
SECTIONS
RT 15" C.M.P.
34' LONG & END
SECTIONS

| 62+00 | 62+40 | 62+80 | 63+20 | 63+60 | 64+00 | 64+40 | 64+80 | 65+20 | 65+60 | 66+00 | 66+40 | 66+80 | 67+20 | 67+60 | 68+00 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 416.47 417.11 | 416.45 417.21 | 416.43 417.31 | 416.41 417.41 | 416.38 417.51 | 416.37 417.61 | 416.49 417.71 | 416.74 417.81 | 416.98 417.91 | 417.22 418.01 | 417.40 418.11 | 417.53 418.20 | 417.65 418.30 | 417.78 418.40 | 417.90 418.50 | 418.02 418.60 | 418.20 418.70 | 418.39 418.80 | 418.58 418.90 | 419.07 419.00 | 419.56 419.09 | 419.91 419.05 | 420.19 418.89 | 419.91 418.60 | 419.44 418.18 | 418.88 417.62 | 418.09 416.94 | 417.07 416.12 | 415.77 415.18 | 414.24 414.10 | 412.70 412.89 |

DATE: 19-Mar-07 15:15
FILE: P:\03\0347000l\Cad\Phase II\4700lppl0.dgn