

| ROUTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------|----------------|--------------|--------------|-----------|
| 9550 | 07-00083-00-RP | SALINE | 21 | 4 |
| CITY OF HARRISBURG | | SLOAN STREET | | |

CONTRACT NO. 99300

PC DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT

| * LOCATION | EXIST. SURFACE | DRIVEWAY PAVT. REMOVAL | | | PCC DRIVEWAY PAVT. 7" | | |
|------------|----------------|------------------------|-------|---------|-----------------------|-------|---------|
| | | LENGTH | WIDTH | SQ. YD. | LENGTH | WIDTH | SQ. YD. |
| 18+10 RT | CONCRETE | 15.0' | 24' | 41.9 | 13.4' | 24' | 32.6 |
| 18+94 RT | CONCRETE | 15.0' | 24' | 41.9 | - | - | - |
| 19+75.6 LT | NONE | - | - | - | 64.9' | 24' | 199.4 |

TOTAL DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT 83.8 232.0

* EXACT LOCATION TO BE DESIGNATED BY THE ENGINEER

PCC BASE COURSE, 10"

| STATION | LOCATION | OFFSET | AREA SQ YD |
|----------------|--------------------|--------|------------|
| 17+30 TO 24+14 | 18.0'LT TO 12.4'LT | | 389.0 |
| 17+30 TO 18+90 | 12.2'RT TO 18.0'RT | | 101.0 |
| 18+90 TO 20+70 | 12.2'RT TO 26.8'RT | | 251.0 |
| 20+70 TO 24+14 | 18.0'RT TO 12.2'RT | | 165.0 |

TOTAL PCC BASE COURSE, 10" 906.0

COMBINATION CURB AND GUTTER REMOVAL

| STATION | LOCATION | OFFSET | LENGTH FOOT |
|----------------|--------------------|--------|-------------|
| 17+30 TO 24+60 | 14.1'LT TO 13.3'LT | | 730.0 |
| 17+30 TO 24+60 | 13.9'RT TO 13.1'RT | | 730.0 |
| 17+88 TO 17+98 | 13.2'RT TO 28.8'RT | | 20.0 |
| 18+22 TO 18+31 | 28.7'RT TO 13.3'RT | | 19.1 |
| 18+74 TO 18+83 | 13.2'RT TO 28.7'RT | | 19.1 |
| 19+06 TO 19+15 | 28.7'RT TO 13.2'RT | | 19.6 |

TOTAL COMBINATION CURB AND GUTTER REMOVAL 1537.8

PC SIDEWALK REMOVAL AND REPLACEMENT

| STATION | LOCATION | OFFSET | PC SIDEWALK REMOVAL 4" | | | PC SIDEWALK 4" | | |
|----------------|---------------------|--------|------------------------|-------|--------|----------------|-------|--------|
| | | | LENGTH | WIDTH | SQ FT | LENGTH | WIDTH | SQ FT |
| 17+30 TO 24+75 | 18.7'LT TO 13.8'LT | | 745' | 4.0' | 2980.0 | - | - | - |
| 17+30 TO 24+75 | 26.6' LT TO 13.8'LT | | - | - | - | 745' | 4.0' | 2980.0 |

TOTAL SIDEWALK REMOVAL AND REPLACEMENT 2980.0 2980.0

COMBINATION CURB AND GUTTER TYPE B6.12

| STATION | LOCATION | OFFSET | LENGTH FOOT |
|--------------------|------------------|--------|-------------|
| 19+33.5 TO 19+63.5 | 20.1'RT TO 85'RT | | 82.0 |
| 19+87.6 TO 20+17.6 | 85'RT TO 20.1'RT | | 82.0 |

TOTAL COMBINATION CURB AND GUTTER TYPE B6.12 164.0

COMBINATION CURB AND GUTTER TYPE B-6.24

| STATION | LOCATION | OFFSET | LENGTH FOOT |
|--------------------|------------------|--------|-------------|
| 17+30 TO 24+60 | 20'LT TO 13.3'LT | | 730.0 |
| 17+30 TO 19+18.4 | 20'RT TO 28.5'RT | | 190.0 |
| 17+86.8 TO 17+98.2 | 20'RT TO 34'RT | | 21.0 |
| 18+21.7 TO 18+31.5 | 34'RT TO 20'RT | | 21.0 |
| 20+35.9 TO 24+60 | 28.5'RT TO 20'RT | | 425.5 |

TOTAL COMBINATION CURB AND GUTTER TYPE B-6.24 1387.0

DRAINAGE STRUCTURE SCHEDULE

| | STATION | OFFSET | SIDE | STRUCTURE TYPE | TOP OF CASTING ELEVATION | FLOWLINE ELEVATION | RIPRAP (TONS) |
|----|---------|--------|------|-----------------------------|--------------------------|--------------------|---------------|
| 1 | 17+77 | 28.0 | RT | FLUSH INLET FOR MEDIAN | 359.40 | 357.90 | |
| 2 | 18+70 | 28.0 | RT | FLUSH INLET FOR MEDIAN | 359.62 | 357.53 | |
| 3 | 18+71 | 39.3 | RT | PRC FLARED END SECTION, 12" | - | 359.00 | |
| 4 | 19+00 | 41.0 | RT | PRC FLARED END SECTION, 15" | - | 357.40 | |
| 5 | 19+53 | 56.8 | LT | PCBC END SECTION 8X5 | - | 353.12 | 25 |
| 6 | 19+99 | 56.8 | LT | PCBC END SECTION 8X5 | - | 352.75 | 30 |
| 7 | 20+25 | 47.3 | LT | PRC FLARED END SECTION, 12" | - | 355.48 | 10 |
| 8 | 20+25 | 20.0 | LT | INLETS, TYPE A, SPECIAL | 360.92 | 357.92 | |
| 9 | 20+48 | 46.0 | RT | PRC FLARED END SECTION, 24" | - | 356.90 | |
| 10 | 20+48 | 24.1 | RT | INLET SPECIAL, TYPE 3, 5' | XXX.XX | 356.68 | |
| 11 | 20+48 | 44.0 | LT | PRC FLARED END SECTION, 24" | - | 356.00 | 30 |
| 12 | 22+31 | 44.0 | RT | PRC FLARED END SECTION, 36" | - | 431.76 | |
| 13 | 22+35 | 52.0 | LT | PRC FLARED END SECTION, 36" | - | 431.33 | 30 |

TOTAL STONE DUMPED RIPRAP CLASS A4 (TON) 125

12 Apr 2007 - 9:16am X:\2007\07016\AC\plans\3-5summary and schedules.dwg