

DATE	REVISION	BY

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108108	1/C #8 5 KV UG CABLE	L.F.	1,420	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	1,380	
AR110554	EXTEND 4-WAY DUCT	L.F.	50	
AR125410	MITL-STAKE MOUNTED	EA.	22	
AR125415	MITL-BASE MOUNTED	EA.	4	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA.	24	
AR125902	REMOVE BASE MOUNTED LIGHT	EA.	4	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	810	
AR155540	BY-PRODUCT LIME	TON	73	
AR155616	SOIL PROCESSING - 16"	S.Y.	1,693	
AR156511	DITCH CHECK	EA.	4	
AR156520	INLET PROTECTION	EA.	8	
AR156531	EROSION CONTROL BLANKET	S.Y.	2,677	
AR201610	BITUMINOUS BASE COURSE	TON	777	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	931	
AR401611	BIT. SURFACE COURSE - METHOD 1	TON	1,491	
AR401620	BIT. SURFACE COURSE, LEVELING	TON	2,237	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	1,115	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	1,345	
AR602510	BITUMINOUS PRIME COAT	GAL.	567	
AR603510	BITUMINOUS TACK COAT	GAL.	1,800	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	2,024	
AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	2,024	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	1,032	
AR705630	UNDERDRAIN INSPECTION HOLE	EA.	2	
AR705640	UNDERDRAIN CLEANOUT	EA.	2	
AR705900	REMOVE UNDERDRAIN	L.F.	986	
AR751943	ADJUST MANHOLE	EA.	1	
AR800449	WEED CONTROL LIGHT RING	EA.	26	
AR901510	SEEDING	AC.	1	
AR908510	MULCHING	AC.	1	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN STA. 134+98 TO STA. 145+00
5	PROPOSED CONSTRUCTION PLAN STA. 145+00 TO STA. 153+68.13
6	TYPICAL SECTIONS AND DETAILS
7	PROPOSED STORM WATER POLLUTION PREVENTION PLAN
8	PLAN AND PROFILE STA. 134+98 TO STA. 145+00
9	PLAN AND PROFILE STA. 145+00 TO STA. 153+68.13
10	PROPOSED DRAINAGE PLAN STA. 134+98 TO STA. 145+00
11	PROPOSED DRAINAGE PLAN STA. 145+00 TO STA. 153+68.13
12	PROPOSED DRAINAGE DETAILS
13	EXISTING ELECTRICAL PLAN STA. 134+98 TO STA. 145+00
14	EXISTING ELECTRICAL PLAN STA. 145+00 TO STA. 153+68.13
15	PROPOSED ELECTRICAL PLAN STA. 134+98 TO STA. 145+00
16	PROPOSED ELECTRICAL PLAN STA. 145+00 TO STA. 153+68.13
17	PROPOSED ELECTRICAL DETAILS
18	PROPOSED ELECTRICAL DETAILS
19	PROPOSED ELECTRICAL NOTES
20	PROPOSED ELECTRICAL NOTES
21	PROPOSED MARKING PLAN STA. 134+98 TO STA. 145+00
22	PROPOSED MARKING PLAN STA. 145+00 TO STA. 153+68.13
23	PROPOSED CROSS SECTIONS STA. 136+00 TO STA. 138+50
24	PROPOSED CROSS SECTIONS STA. 139+00 TO STA. 141+50
25	PROPOSED CROSS SECTIONS STA. 142+00 TO STA. 144+50
26	PROPOSED CROSS SECTIONS STA. 145+00 TO STA. 148+00
27	PROPOSED CROSS SECTIONS STA. 148+00 TO STA. 150+50
28	PROPOSED CROSS SECTIONS - TXY C-1 STA. 1+25 TO STA. 2+00
29	PROPOSED CROSS SECTIONS - TXY C-2 STA. 1+59.50 TO STA. 2+00

QUINCY REGIONAL AIRPORT
BALDWIN FIELD
ADAMS COUNTY, ILLINOIS



HEI Project No. 82407TXD.0100	FILENAME R-002ELP.DWG	DATE 03/13/07
SCALE M/A	DATE 03/13/07	LAYOUT JDW 03/13/07
		DRAWN ESC 03/13/07
		REVIEWED JDW 03/21/07



REALIGN, WIDEN
AND REHABILITATE
TAXIWAY "C" - PHASE 2
SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS