

SUMMARY OF QUANTITIES

ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	ENTRANCE ROAD		PARKING LOT LOCAL	
				FED/STATE/LOCAL BID QUANTITY	FINAL QUANTITY	BID QUANTITY	FINAL QUANTITY
AR106512	TYPE A AREA LGT POLE W/2 FIXTURES	EACH	3			3	
AR106521	TYPE B AREA LGT POLE W/1 FIXTURE	EACH	8			2	
AR106531	TYPE C AREA LGT POLE W/1 FIXTURE	EACH	6			7	
AR106841	TYPE D ASSEMBLY--1 FIXTURE	EACH	9			8,000	
AR106985	RELOCATE LIGHT POLE & FIXTURE	L.F.	6,480			450	
AR108406	1/C #6 600 V UG CABLE	L.F.	12,000			2,000	
AR108410	1/C #10 600 V UG CABLE	L.F.	450				
AR108800	CONTROL CABLE	L.F.	3,350				
AR110201	1" PVC DUCT, DIRECT BURY	L.F.	1,000				
AR110200	1--1/4" PVC DUCT, DIRECT BURY	L.F.	1,000				
AR110610	ELECTRICAL HANDHOLE	EACH	10			5	
AR110906	REMOVE ELECTRICAL HANDHOLE	EACH	2				
AR150530	TRAFFIC MAINTENANCE	L.S.	1		0.90	0.10	
AR151420	CLEARING TREES 0-2.5' BUTT. DIA.	EACH	38		10	28	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	764		364	400	
AR152440	BORROW EXCAVATION	C.Y.	30,137		15,408	14,729	
AR156500	TEMPORARY EROSION CONTROL SEPARATION FABRIC	L.S.	1		0.75	0.25	
AR156513	SEPARATION FABRIC	S.Y.	23,570		7,802	15,768	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	5,789		1,909	3,880	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	570		570		
AR501506	6" PCC PAVEMENT	S.Y.	15,925		6,574	15,925	
AR501908	8" PCC PAVEMENT	S.Y.	6,574		0.36	0.64	
AR501930	PCC TEST BATCH	EACH	1		1	6,482	
AR501804	4" PCC SIDEWALK	S.F.	6,482		2,526	2,526	
AR501890	PCC SIDEWALK REMOVAL	S.F.	2,526		7,098	1,250	
AR501900	REMOVE PCC PAVEMENT	S.Y.	8,348				
AR620520	PAVEMENT MARKING--WATERBORNE	S.F.	4,562		372	4,190	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	438			438	
AR701200	SLOTTED DRAIN	L.F.	1,047			1,047	
AR701206	6" CMP	L.F.	20		20		
AR701224	24" CMP	L.F.	58			58	
AR701412	12" RCP, CLASS III	L.F.	345		277	68	
AR701415	15" RCP, CLASS III	L.F.	113		57	56	
AR701418	18" RCP, CLASS III	L.F.	20		20		
AR701424	24" RCP, CLASS III	L.F.	617		617	11	
AR701430	30" RCP, CLASS III	L.F.	186		186		
AR701436	36" RCP, CLASS III	L.F.	136		136		
AR701900	REMOVE PIPE	L.F.	1,543		1,543		
AR705504	4" PERFORATED UNDERDRAIN	L.F.	3,850		3,850		
AR751411	INLET - TYPE A	EACH	11		9	2	
AR751412	INLET - TYPE B	EACH	4		4		
AR751413	INLET - SPECIAL	EACH	1			1	
AR751940	MANHOLE 4'	EACH	3			3	
AR751950	MANHOLE 5'	EACH	3		3		
AR751900	REMOVE INLET	EACH	21		21		
AR751903	REMOVE MANHOLE	EACH	8		8		
AR751983	RECONSTRUCT MANHOLE	EACH	3			3	
AR752206	METAL END SECTION 6"	EACH	1		1		
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	1		1		
AR760506	6" DUCTILE IRON WATER MAIN	L.F.	87		87		
AR760508	8" DUCTILE IRON WATER MAIN	L.F.	80		80		
AR760516	16" DUCTILE IRON WATER MAIN	L.F.	185		185		
AR760800	FIRE HYDRANT	EACH	1		1		
AR760905	REMOVE FIRE HYDRANT	EACH	2		2		
AR801552	6" WATER VALVE	EACH	1		1		
AR801553	8" WATER VALVE	EACH	1		1		
AR801554	16" WATER VALVE	EACH	1		1		
AR801555	ABANDON WATERMAIN	L.S.	1		1		
AR801556	REMOVE GUARD RAIL	L.F.	1,253			1,253	
AR801557	REMOVE AND REERECT STEEL PLATE BEAM GUARD RAIL	L.F.	748			748	
AR801558	SIGN BRIDGE	EACH	1		1		
AR801559	REMOVE SIGN BRIDGE	EACH	1			1	
AR801560	SITE SIGNS	EACH	31			31	
AR801561	RETAINING WALL SIGN	EACH	3			3	
AR801562	RETAINING WALL	L.F.	437		437		
AR801563	RECONSTRUCT TELEPHONE VAULT	EACH	1		1		
AR801564	RELOCATE TICKET DISPENSER & GATE ARM	EACH	1			1	
AR801565	DETECTOR LOOP, TYPE 1	L.F.	122		122		
AR801566	RELOCATE SIGN BRIDGE LIGHTING	L.S.	1		1		
AR801567	ABANDON STORM SEWER	L.S.	1		1		
AR901510	SEEDING	ACRE	1.84		1.42	0.42	
AR908510	MULCHING	ACRE	1.84		1.42	0.42	
AR910400	GUARD RAIL	L.F.	960		545	415	
AR910410	PARKING BLOCK	EACH	12			12	
AR910420	BOLLARD	EACH	3			3	
AR910976	RELOCATE ROADWAY SIGNS	L.S.	1		1		



REVISONS		DATE
NO.	ITEM	
1	CHANGED 2" PVC DUCT TO 1-1/4" PVC DUCT	JUNE 7, 2007

PLOTTING SCALE: 1" = 1'	DRAWN BY: BJJ
CHECKED BY: SAS	DATE: APRIL 2007

McClure Engineering Associates, Inc.
Est. 1954
4700 Rockwell Drive
(309) 792-9150
Design Firm License: Illinois 184-000816
Copyright 2007 By McClure Engineering Associates, Inc.

IL PROJ: ML-3673 AIP PROJ: 3-17-0068-XX