

SUMMARY OF QUANTITIES

SEQ. NO.	ITEM NO.	DESCRIPTION	UNIT	BASE BID					ADD. ALT. NO. 1		TOTAL	
				1	2	3	4	TOTAL	5	TOTAL	TOTAL	TOTAL
				ELECTR. VAULT IMPR.	HOMERUN DUCTS AND CABLING	TAXIWAY CIRCUIT 1 (WEST OF RWY 18/36)	RUNWAY 7/25	BASE BID	INSTALL REIL'S ON RWY 18/36	ADD. ALT. NO. 1	EST. QTY.	RECORD QTY.
EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.	EST. QTY.			
1	AR108108	1/C #8 5KV UG CABLE	LF		1,395.00	465.00	465.00	2,325.00			2,325.00	
2	AR108158	1/C #8 5KV UG CABLE IN UD	LF		5,230.00	8,135.00	16,335.00	29,700.00			29,700.00	
3	AR109210	VAULT MODIFICATIONS	LS	1.00				1.00			1.00	
4	AR110810	ELECTRICAL HANDHOLE	EACH		4.00			4.00			4.00	
5	AR110710	ELECTRICAL MANHOLE	EACH		2.00			2.00			2.00	
6	AS125610	REILS	PAIR					2.00	2.00		2.00	
7	AR125901	REMOVE STAKE MOUNTED LIGHT	EACH			45.00		45.00			45.00	
8	AR125902	REMOVE BASE MOUNTED LIGHT	EACH			20.00		20.00			20.00	
9	AR125982	REFURBISH BASE MOUNTED LIGHT	EACH				76.00	76.00			76.00	
10	AR125983	REFURBISH IN PAVEMENT LIGHT	EACH				4.00	4.00			4.00	
11	AR800808	MITL-BASE MOUNTED, ANCHORED	EACH			65.00		65.00			65.00	
12	AR800809	2" HDPE CONDUIT, DIRECTIONAL BORE	LF			200.00	345.00	545.00			545.00	
13	AR800810	2" HDPE CONDUIT, DIRECT BURIED	LF		3,560.00			3,560.00			3,560.00	
14	AR800811	4 - 2" HDPE SCH. 80, DIRECTIONAL BO	LF		220.00			220.00			220.00	
15	AR800812	SPLICE CAN, ANCHORED	EACH			4.00	10.00	14.00			14.00	
16	AR800813	REFURBISH AND GROUND GUIDANCE SIG	EACH			6.00	1.00	7.00			7.00	
17												
18												
19												
20												

WH006



Whiteside County **AIRPORT**
JOSEPH H. BITTORF FIELD

Whiteside County Airport

Sterling / Rock Falls, Illinois

Whiteside County Airport

AIP: 3-17-0098-XX
SQI-3694

Recable Airfield

FINAL SUBMITTAL

Revisions		
No.	Date	Description

0 1
THIS BAR IS EQUAL TO 1" AT FULL SCALE (17 X 11).

DESIGN BY: CMT- RFD
DRAWN BY: CMT- RFD
CHECKED BY: CMT- RFD
APPROVED BY: JGP
DATE: 4.20.2007
JOB No: 06292-03-00

SUMMARY OF QUANTITIES (QTY1)